g		GE Industrial Syst	GE Industrial Systems Fu			Functional Testing Specification			
	Renewal Serv Louisville, KY		LOU-GED-DS2020UCOC						
		Test Procedu	ure for a (Card					
DOCUI	MENT REVISION STATUS:	: Determined by the last entry in t	he "REV" a	nd "DATE" co	lumn				
REV.		DESCRIPTION					REV. DATE		
Α	Initial release				R. Tho	mpson	05/05/95		
В	Typo communication)				mpson	06/05/95		
С	Fixed 230 V default					mpson	07/12/95		
D		2, all OPEN step 10.4				mpson	02/04/97		
E		spection step for DS200LRP/	AG1A			mpson	12/02/01		
F	Converted to Louisvi	•				uvall	06/27/02		
G	Added Section for U				R. D	uvall	12/16/03		
Н		to assembly to keep control c	ard from o	coming		arling	6/9/2010		
	loose during shipping			3		3			
	, , , ,	~							
	1						1		
	YRIGHT GENERAL ELECTS pies are uncontrolled and are f								
		THIS DOCUMENT CONTAINS PROP	RIETARY IN	FORMATION (OF GENERAL	ELECTRIC (COMPANY AND		
		ED TO OTHERS, EXCEPT WITH THE							
PRFD/	ARED BY	REVIEWED BY	REVIEWE	D BY	QUALITY APPROVAL				
R. Du		M. Starling	INT A IT AA		Rober Dunll				
		•	DATE				Owell		
DATE	/02	DATE 6/0/2010	DATE 06/27/02						
06/27	/UZ	6/9/2010	1		0	U/Z1/UZ			

LOU-GED-DS2020UCOC

g

GE Industrial Systems Renewal Services Louisville, KY

Page 2 of 8

Functional test procedure for OC2000 Operator Console.

1. SCOPE

1.1 This is a functional testing procedure for a OC2000 Operator Console or UC2000 Controller.

2. STANDARDS OF QUALITY

REV. H

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
 - 2.1.1 Appropriate Bill Of Materials for item being tested
 - 2.1.2 Assembly Drawings: 336A3548 & 336A3549
 - 2.1.3 DS200UPLAG# documents
 - 2.1.4 DS200UDSAG# documents
 - 2.1.5 GEH-6334 UC2000 Manual
 - 2.1.6 GEH-6335 OC2000 Manual

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.
- 4.2 Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - 4.2.1.1 Wires broken or cracked
 - **4.2.1.2** Terminal strips / connectors broken or cracked
 - **4.2.1.3** Loose wires
 - 4.2.1.4 Components visually damaged
 - 4.2.1.5 Capacitors leaking
 - 4.2.1.6 Solder joints damaged or cold
 - 4.2.1.7 Circuit board burned or de-laminated
 - 4.2.1.8 Printed wire runs burned or damaged

5. EQUIPMENT REQUIRED

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		60 Hz Power Source
1		115 VAC Power Cord w/gnd.
1		DC200 Simulator for Arcnet test
1		Test PC with appropriate software (Control Systems Toolbox, Serial Loader)
1		OC2000 Test Unit
1		UC2000 Test Unit

g

LOU-GED-DS2020UCOC REV. H

GE Industrial Systems Renewal Services Louisville, KY

Page 3 of 8

6. TESTING PROCESS (OC2000)

- **6.1** New Modification 6-9-2010.
 - **6.1.1** In an effort to reduce shipping damage please performed the following modifications.
 - **6.1.2** Cut nipples off of the four corners, front and back side of the grey card carrier. Leaved all other nipples intact.
 - **6.1.3** Using a scrap card that fits the card carrier, select a drill bit that is the same size as the four corner holes of the scrap card.
 - **6.1.4** Snap scrap board into the carrier and use drill press to drill holes through the four corners of the carrier. The scrap card acts as a guide to keep the drill centered, and to locate holes in proper position.
 - **6.1.5** Remove scrap board and install customers card. Select the appropriate length #6 screw and #6 shoulder nut and fasten customers card to the card carrier.





LOU-GED-DS2020UCOC
REV. H

GE Industrial Systems
Renewal Services
Louisville, KY

Page 4 of 8
Renewal Services

6.2 INSPECTION PROCEDURE

- **6.2.1** Verify DS200UDSAG1A Card revision level is "USE" in ORANGE book.
- **6.2.2** Verify 1 thick Gasket a one thin under keypad frame.
 - **6.2.2.1** The keypad frame (inside) screws should be snug but not tight.
 - **6.2.2.2** 10 outside screws should be in a bag attached to Unit.
- 6.2.3 Lexan TB cover over 1TB. #34
- **6.2.4** Check all hardware for tightness.
- **6.2.5** Check all labels for proper location and nomenclature:
 - **6.2.5.1** GENERAL ELECTRIC (logo on upper left front)
 - 6.2.5.2 DS2020UCOCN1G1A (for Module id)
 - **6.2.5.3** GND (for GND Lug)
 - 6.2.5.4 CH A CH B 1TB (for ARCNET CH and 1TB id)
 - **6.2.5.5** INPUT VOLTS: POWER (for Power, Fuse and RS232 id)
- **6.2.6** Verify assembly/MRP notes have been followed.
- **6.2.7** Visual Wire Check:

FROM	TO
1TB-AC1 (RED) 1TB-AC2 (BLK) 1TB-CCOM (WHT) 1TB-TX (CLR SLV) 1TB-RX (BLU) 1TB-SHD IN CAPACITOR UPLAG1A-CMPL1 UPLAG1A-CMPL2	UPLAG1A-PWRPL-1 (Watch connector offset) UPLAG1A-PWRPL-2 UPLAG1A-SGND UPLAG1A-ARCPL-7 UPLAG1A-ARCPL-8 CAPACITOR CHASSIS GND RS232 OPTION (should have 180ø twist) UDSAG1A-CMPL (should lay flat)
UPLAG1A-2PL UPLAG1A-ARCPL	UDSAG1A-2PL (Watch connector offset) ACNAG1A-ARCPL (Watch connector offset)
3 KeyPad Ribbons	UDSAG1A-1KPL, 2KPL, 3KPL

g

LOU-GED-DS2020UCOC REV. H

GE Industrial Systems Renewal Services Louisville, KY

Page 5 of 8

- 6.3 JUMPER and SWITCH SETTINGS
 - **6.3.1** POWER SW4 to OFF position.
 - **6.3.2** JP1 & JP2 to 115 position.
 - **6.3.3** JP25 to 9600 position. RS232 baud rate selection.
 - **6.3.4** Set all jumpers to default position 1-2.
 - **6.3.5** Set DIP Sw CFG1: (Selects Station Drop Number 5) SW1=F7/05
 - **6.3.5.1** 1, 3 OPEN position.
 - **6.3.5.2** 2, 4, 5, 6, 7, 8 CLOSED position.
 - **6.3.6** Set DIP Sw CFG2: (Selects Operating Mode TEST MODE)
 - **6.3.6.1** 1, 2, 3, 5, 6, 7, 8 OPEN position.
 - **6.3.6.2** 4 CLOSED position.
- **6.4** TEST CONNECTIONS
 - 6.4.1 Connect 115VAC Power Cord to 1TB-AC1 & 1TB-AC2 & GND-GND LUG.
 - **6.4.2** Leave ARCNET COAX cable disconnected at this time.
- **6.5** POWER TEST
 - **6.5.1** Apply power to the OC2000 and DC2000 Simulator.
 - 6.5.2 Set POWER SW4 ON.
 - **6.5.3** P24, N24 Volt test.
 - 6.5.3.1 Verify UPLAG1A GREEN LED (DS1) is on.
 - **6.5.4** UPLAG1A serial communication with UDSAG1A test.
 - 6.5.4.1 Verify UPLAG1A RED LED (DS2) is flickering.
- 6.6 DISPLAY TEST
 - **6.6.1** Set UUT so to visually inspect the display.
 - 6.6.2 Self Test
 - **6.6.3** Momentarily press UPLAG1A SW5 RESET PB and verify display:

General Electric Operator Interface

Hardware Self Test Passed

Unit OK

- **6.6.4** You may repeat Self Test by pressing RESET PB again.
- **6.6.5** 10 seconds later, LAMP test.
- **6.6.6** Verify all Display elements are on.
- **6.6.7** Verify all Keypad LEDs are on.

LOU-GED-DS2020UCOC

GE Industrial Systems Renewal Services Louisville, KY

Page 6 of 8

6.6.8 Verify LEDs centered in all the keypad windows.

g

6.7 KEYPAD TEST

REV. H

6.7.1 Momentarily press all 32 keypad keys with LED indicator and verify the keys' LED goes out.

NOTE: When the first key is pressed, the display exits lamp test.

- **6.7.2** Momentarily press each of the 16 control keys and verify the 3rd row
- 6.7.3 display shows: --Key xx=0--
- **6.7.4** where xx is key code shown below:

Control Keys			Function Keys										
41	42	43	4A		01	02	03	04		11	12	13	14
44	45	46	4B		05	06	07	80		15	16	17	18
47	48	49	4C		09	0A	0B	0C		19	1A	1B	1C
4D	40	4E	4F		0D	0E	0F	10		1D	1E	1F	20

Note: Function keys are not tested via display. They are listed for info only.

- 6.8 9.0 ARCNET TEST
 - **6.8.1** ARCNET Line Reconfiguration (LR) Test.
 - 6.8.2 Connect the ARCNET COAX from the Simulator to CH A
 - 6.8.3 BNC connector on Unit Under Test (UUT) and
 - **6.8.4** LISTEN for the ACNA RELAY to pick up.
 - **6.8.5** Verify displayed value of LR=** (second line) is NOT counting up.
 - 6.8.6 Unhook ARCNET COAX from CH A on UUT.
 - **6.8.7** Verify displayed value of LR=** is counting up.
 - 6.8.8 Reconnect ARCNET COAX to CH B on UUT.
 - **6.8.9** Verify displayed value of LR=** (second line) is NOT counting up.

LOU-GED-DS2020UCOC
REV. H

GE Industrial Systems
Renewal Services
Louisville, KY

Page 7 of 8

Renewal Services
Louisville, KY

- **6.9** FINAL INSTRUCTIONS
 - **6.9.1** Turn off power to the OC2000.
 - 6.9.2 Set POWER SW4 OFF.
 - **6.9.3** Set JP1 & JP2 to 230 position.
 - **6.9.4** Set DIP Sw CFG2, position 4 to OPEN (position 1 thru 8, all OPEN).

115 Volt position					230 Volt Position						
			115				115				
	0	0	0	JP1	0	0	0	JP1			
				I							
	0	0	0	JP2	0	0	0	JP2			
	115		1		115		1				

- 6.9.5
- **6.9.6** Verify bag of remaining frame screws (10) is attached to unit and that any other items(s) to be shipped with unit is complete per parts list.
- **6.9.7** Replace/tighten any parts removed during test.
 - **6.9.7.1** Lexan 1TB cover.
- 6.10 ***TEST COMPLETE ***

g

LOU-GED-DS2020UCOC REV. H

GE Industrial Systems Renewal Services Louisville, KY

Page 8 of 8

7. TESTING PROCESS (OC2000)

7.1 <u>UCIA/UCPB Testing</u>

7.1.1 Setup

- 7.1.1.1 Install UUT in shop UC2000 test unit.
- 7.1.1.2 Install micro Geni cards.
- 7.1.1.3 Set Arcnet drop ID on UCPB card to 100 (Switch 3,6,7 up)
- 7.1.1.4 Connect and verify all cables.

7.1.2 Initial Test

- **7.1.2.1** Power up test unit and wait for boot up to complete.
- 7.1.2.2 Record any fault code present on the DN1 LED bank on the UCIA card.
- **7.1.2.3** Use the Serial Loader software on the test PC to read the current IP address.

7.1.3 Serial Load

- **7.1.3.1** Follow the instructions of the Serial loader software to reload the BIOS with the current BIOS information.
- 7.1.3.2 Use the Serial Loader software to reload the Flash File System and program the TCP IP settings. (192.168.101.122)
- **7.1.3.3** Close the Serial Loader software when complete.

7.1.4 Toolbox Load

- **7.1.4.1** Use the current version of GE Control Systems Toolbox to load the Product Code (Runtime).
- **7.1.4.2** After a successful Runtime load and reboot, download the UC1.ucb file to the UUT.
- **7.1.4.3** Reboot the UUT when complete.

7.1.5 Final Checkout

- **7.1.5.1** Verify the operation of the Genius I/O by using the OC2000.
- **7.1.5.2** Verify control of the DC2000 drive from the OC2000. (DC2000 must be setup for Arcnet, param 706=9)
- **7.1.5.3** Let UUT run for several hours and perform Final Checkout again.

7.1.6 Testing Complete

8. NOTES

8.1 None at this time