

REV NO. <b>21</b>	TITLE <b>CIRCUIT BOARD SPECIFICATIONS</b>	COUNT ON SHEET <b>2</b>
<b>PJK-AL-0656-A01</b>	<b>VALVE POSITION DRIVER 169C4773, 1F1-F3</b> <b>VALVE POSITION DRIVER - AMS 196C2105, 1F1-F4</b> <b>FIRST MADE FOR ENG MARK II 148D164764</b>	SH NO. <b>1</b>

**A. BOARD CONTENTS**

1. Two (2) regulated power supplies, (IC4, IC5)
2. Servoamplifier, (IC3)
3. 3 KHz oscillator, (IC1, IC2)
4. Demodulator
5. Low pass filter
6. Feedback amplifier, (IC6) (1F1-F3 Only)

*Changes in red were made 12-19-88 By H. Bernard and I could this instrument work for the 148D164764 JMC*

**B. TEST SETUP**

See Figure 1.

**C. POWER SUPPLIES**

1.  $V_{TP1} = 15 \pm 1 \text{ VDC}, < 15 \text{ mv ptp ripple}$
  2.  $V_{TP2} = -15 \pm 1 \text{ VDC}, < 15 \text{ mv ptp ripple}$
  3.  $I_{pin 37} < 100 \text{ ma}$  READ AT P.S. CURRENT METER 44.1  
39.5
  4.  $I_{pin 41} < -100 \text{ ma}$
- Com 39 (M)

THIS DOCUMENT CONTAINS INFORMATION OF A CONFIDENTIAL NATURE. IT IS TO BE KEPT SECRET AND IS NOT TO BE DISCLOSED TO ANY UNAUTHORIZED PERSON OR ORGANIZATION. IT IS THE PROPERTY OF THE UNITED STATES GOVERNMENT AND IS LOANED TO YOUR AGENCY. IT IS TO BE RETURNED TO THE SOURCE OF ORIGIN WHEN NO LONGER NEEDED. IT IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. THIS DOCUMENT AND THE INFORMATION IT CONTAINS ARE UNCLASSIFIED DATE 10/1/88 BY 1045/UC

**D. SERVO AMPLIFIER**

1. Assure that ~~VR2 null~~ ~~gives~~ ~~VTP6~~ ~~= 0V~~ ~~(VTP5 = 0)~~ ~~for~~ ~~1.002~~

- a.  $R_{SV} = 124 \Omega$  Per-sh-6
  - b.  $R_{SV} = 249 \Omega$
- Pin 10 = 3.95 V -4.01 3.98 -3.99*  
*Pin 11 = 1V DC*  
*Pin 12 = -3.4* (VR2 CCW, VR54, CCW,  $V_{TP5} = -3.98$ )

*1VDC on Pin 11 READ WITH VR2 CCW VR54 CCW*

- a.  $R_{SV} = 124 \Omega$
  - b.  $R_{SV} = 249 \Omega$
- for: **CHANGE VALUE NO CHANGE AT TP59**

- c. ~~Ascertain that the SV meter, U6023AS, is operational.~~
- c. **MEASURE CURRENT PIN 12 TO PIN 13**  
**READ CURRENT = -0.92 mA TO -0.97 mA DC**  
**(WHEN USING FLUKE TO READ USE 2 mA SCALE)**

**COPYRIGHT 1983 GENERAL ELECTRIC CO. INTERNAL SHUNT RESISTOR IS A FACTOR**

MADE BY <b>J. Aulisi 14 Sept. 1981</b>	APPROVALS <b>Steam Turbine</b>	DIV OR DEPT. <b>Schenectady, N.Y.</b>	LOCATION <b>PJK-AL-0656-A01</b>
ISSUED <b>SEP 14 1981</b>	CONT ON SHEET <b>2</b>		SH NO. <b>1</b>

REVISION
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100

GENERAL ELECTRIC

PJK-AL-0656-A01

CONT ON SHEET 3

SM NO 2

PJK-AL-0656-A01

CONT ON SHEET 3

SM NO. 2

TITLE  
CIRCUIT BOARD SPECIFICATIONS  
VALVE POSITION DRIVER 186C8105, 1F1-F3  
VALVE POSITION DRIVER - AMS 186C8105, 1F1-F4  
FIRST MADE FOR EHC MARK II

REVISION

## D. SERVO AMPLIFIER (continued)

3.  $-5.4 \text{ V}$   $\leftarrow$   $\text{TP59}$   $\leftarrow$   $-4.83 \text{ V}$   $\leftarrow$   $-5.01$   $\leftarrow$   $-5.00$   $\leftarrow$   $(\text{PIN} 11) +1.00 \text{ VDC}$   
 $\leftarrow$   $-4.93$   $\leftarrow$   $(\text{VR2 CCW, VR54 CW, } |V_{\text{TP55}}| = \text{---})$

for:

a.  $R_{\text{SV}} = 124 \Omega$ b.  $R_{\text{SV}} = 249 \Omega$ 

Very little or  
NO CHANGE AT TP59  
(GREY)

C. MEASURE CURRENT  
PIN 12 TO PIN 13 =  
-0.114 MA TO -0.124 MA  
1164

4.  $-78 \text{ mV/V}_{\text{TP55}} \leftarrow -82 \text{ mV/V}$   $(\text{VR2 CCW, VR54 CW, } |V_{\text{TP55}}| \leq 3 \text{ VDC})$

for:

a.  $R_{\text{SV}} = 124 \Omega$ b.  $R_{\text{SV}} = 249 \Omega$ 

4. INPUT 1VDC TO PIN 11  
VR54 = CW  
ADJUST VR2 FOR -0.4VDC AT TP6

READ CURRENT 12 TO 13 = -0.202 TO -0.206

## 5. Current Limit

$|I_{\text{SV MAX}}| \leq 20 \text{ mA}$   $\leftarrow$   $|V_{\text{TP55}}| \leq 5 \text{ VDC}$   $(\text{VR2 CW})$   
 FOR: VERIFY THIS READING IS ALWAYS LOW ON ALL CARDS

a.  $R_{\text{SV}} = 124 \Omega$ b.  $R_{\text{SV}} = 249 \Omega$ 

## E. SERVO AMPLIFIER Transient State

With VR2 CCW, VR54 CCW, apply  $V_{\text{TP55}} = -1 \text{ V}$  step and observe  $V_{\text{TP59}}$  (Figure 2).

## F. 3 KHZ OSCILLATOR

All tests, except that for temperature sensitivity, are to be done with the oscillator normally loaded.

## 1. Initial Start-up

Adjust VR50 to mid range and observe TP12 with a scope (2 volt/div. amplitude, 50  $\mu\text{s}/\text{div}$  sweep). If necessary, readjust for a non-distorted sine wave.

MADE BY J. Aulisi 14 Sept. 1981

APPROVALS

Steam Turbine

DIV OR DEPT.

PJK-AL-0656-A01

PRINTS

285191 MAY 16 1983  
 ① PAILIN

REV NO. 1  
P3K-AL-0656-A01  
CONT ON SHEET 4 SH NO. 3

TITLE  
CIRCUIT BOARD SPECIFICATIONS  
VALVE POSITION DRIVER 169C4773, 1F1-F3  
VALVE POSITION DRIVER - AMS 186C3105, 1F1-F4  
FIRST MADE FOR ENG MARK II

## F. 3 KHZ OSCILLATOR (continued)

### 2. Distortion

#### a. FET (2N3822) Distortion

Adjusting VR50 too far CW will cause the output TP12 to distort. Check distortion by centering the signal on both the amplitude and sweep coordinates as shown in Figure 3. Distortion occurs when  $|T_1 - T_2| > 10 \mu\text{sec}$  and can be eliminated by backing down on VR50 (TP50).

#### b. Saturation Distortion

Saturation will occur when  $V_{\text{peak TP12}} > V_{TP1}$  or  $V_{TP2}$  and is eliminated by decreasing VR51.

### 3. Gate ( $V_{TP50}$ ) Setting

Adjust VR50 so that the oscillator runs at the upper limit of linearity ( $|T_1 - T_2| \approx 10 \mu\text{sec}$ ); i.e.

$$|V_{\text{GATE}}| \approx |V_{\text{GATE FET DIST}}| = .010$$

Operation around this point gives maximum temperature and load change stability. A sampling of 25 FET's has shown the upper limit to be:

$$2.6 \leftarrow V_{\text{GATE}} \leftarrow 1.0$$

NOTE VR50 CCW shuts down  
CARD FOR

ADJUST VR 50 FOR -2.5VDC  
AT TP 50 WITH VR51 CCW.  
(VIOLET TOP)

### 4. Amplitude Setting

Adjust VR51 for  $V_{TP12} = 6.000 \pm .010 \text{ VRMS}$ . 16.97v P-P

### 5. Frequency

$$3000 < f < 3400 \text{ Hz @ TP12}$$

3062 3152  
3030

### 6. Regeneration

The oscillator must restart in all of the following situations:

- Simultaneously interrupt the +22 VDC and the -22 VDC power. Reconnect.
- Interrupt the +22 VDC power. Reconnect.

REVISION

16 ISS3

1 CHG. THIS SHEET

1 CHG. THIS SHEET

PRINTS

MADE BY J. Aulisi 14 Sept. 1981

ISSUED SEP 14 1981

APPROVALS

Steam Turbine

DIV OR DEPT.

Schenectady, N.Y.

LOCATION

P3K-AL-0656-A01

CONT ON SHEET 4

SH NO. 1

CODE 16-1

REV. NO. 1	TITLE CIRCUIT BOARD SPECIFICATIONS VALVE POSITION DRIVER 169C4773, 1F1-F3 VALVE POSITION DRIVER - AWS 186C8105, 1F1-F4 FIRST MADE FOR EHC MARK II	CONT. ON SHEET 5
P3K-AL-0656-A01		
CONT. ON SHEET 5	SH. NO. 4	

F. 3 KHZ OSCILLATOR (continued)6. Regeneration (continued)

- c. Interrupt the -22 VDC power. Reconnect.
- d. Withdraw and insert the Valve Position Driver Board.

7. Temperature Stability *MAKE SURE AT AMBIENT Temp  $\Delta V_{TP12}$  Does NOT DRIFT  $\geq .060$  VRMS*  
 This test may be conducted with oscillator unloaded.

With  $V_G$  set as in Step 3 at ambient temperature ( $T_A$ ) then:

$$|\Delta V_{TP12}| \leq .060 \text{ VRMS} \quad (T_A \leq T \leq 130^\circ\text{F})$$

A small change in  $V_G$  may be necessary to meet this spec. If

$\Delta V_{TP12} > +.060$  for  $T_A \leq T \leq 130^\circ\text{F}$ , decrease  $V_{GATE}$ . If

$\Delta V_{TP12} > -.060$ , increase  $V_{GATE}$ .

8. Load Variance

No transducer position should change  $V_{TP12}$  more than 15 mV RMS.

$$\Delta V_{TP12} \leq .015 \text{ VRMS}$$

9. Envelope Modulation

Envelope modulation should not exceed .015V ptp.

G. DEMODULATOR

*NOTE: Region of Transducer used is  $V_{TP12} = 6 \text{ VRMS}$  (BS) 2.5" FROM BODY TO 6" FROM BS NTS 8.5"*

1. Fully extend the transducer to its linear limit (as in valves wide open position) and adjust VR3 so that:

$$V_{TP8} = 0.000 \pm 0.010 \text{ VDC}$$

TOP STOP

- a. Verify  $V_{TP7}$  by Figure 4. (Use Scope) 50MS SCOPE 20/div
- b. Verify  $V_{TP52}$  by Figure 5. (Use Scope)

REVIS:0

MAY 16 1993  
 PAUL  
 CHC  
 THIS COPY

PRINTS

MADE BY J. Aulisi 14 Sept. 1981	APPROVALS	DIV OR DEPT. Steam Turbine	P3K-AL-0656-A01
ISSUED SEP 14 1981		LOCATION Schenectady, N.Y.	CONT. ON SHEET 5
			SH. NO. 4

REV NO. 01  
P3K-AL-0656-A01  
CONT ON SHEET 6 SH NO. 5

TITLE  
CIRCUIT BOARD SPECIFICATION  
VALVE POSITION DRIVER - 169C4773, 1F1-F3  
VALVE POSITION DRIVER - AMS 186C8105, 1F1-F4  
FIRST MADE FOR ENG MARK II

CONT ON SHEET 6 SH NO. 5

REVISION

MAY 16 1993  
D. P. PAULI

G. DEMODULATOR (continued)

2. Insert the transducer ~~by 0.4~~.  
a. Verify  $V_{TP7}$  by Figure 6.  
b. Verify  $V_{TP52}$  by Figure 7.

to Bottom shaft (2.5" from Body)

H. FILTER

1. With the CB inactive, apply  $V_{TP52} = 1$  VRMS @ 100 Hz. Then:

~~$0.88 < V_{TP8} (V_{TP13}) / V_{TP52} < 0.94$  (1F1-F3, 1F1-F4)~~

2. Under normal operating conditions with  $V_{TP12} = 6$  VRMS:

- a. Transducer fully extended to its linear limit:

~~$V_{TP8} = 0.000 \pm .010$  VDC~~

~~$V_{TP8} < 10$  mv pcp; 3 KHz fundamental~~

- b. Transducer inserted by R"

~~$4.5 < V_{TP8} < 5.2$  VDC~~

~~$V_{TP8} < 10$  mv pcp; 3 KHz fundamental~~

I. FEEDBACK AMPLIFIER (1F1-F3 Only)

1. Assure that VR53 nulls IC6 when  $V_{TP8} = 0$ . ~~TP13 = 0~~

Set TP8 to zero with Transducer.  
Set TP8 to +1 VDC Set IV with Transducer

2. ~~-7.97~~  $V_{TP13} / V_{TP8}$  ~~-6.58~~

(VR4 CW,  $V_{TP8} < 1.5$ ) -7.53 -7.29

- ~~-1.24~~  $V_{TP13} / V_{TP8}$  ~~-1.18~~

(VR4 CCW,  $V_{TP8} < 0.0$ ) -1.209  
-1.214 -1.204

PRINTS

REV NO. 01	TITLE CIRCUIT BOARD SPECIFICATIONS VALVE POSITION DRIVER - 169C4773, 1F1-F3 VALVE POSITION DRIVER - AMS 186C8105, 1F1-F4	CONT ON SHEET 7	SH NO. 6
P3K-AL-0656-A01	FIRST MADE FOR EHC MARK II	CONT ON SHEET 7	SH NO. 6




FIGURE 1: TEST SETUP

REVISED

MAY 16 1983  
D. DAVIES  
1500 THE SHIP

MADE BY J. Aulisi 14 Sept. 1981	APPROVALS	Steam Turbine	DIV. OR DEPT.	P3K-AL-0656-A01
ISSUED SEP 14 1981		Schenectady, N.Y.	LOCATION	CONT ON SHEET 7
				SH NO. 6

PRINTS

REF. NO. 01  
P3K-AL-U656-A01

TITLE  
CIRCUIT BOARD SPECIFICATIONS  
VALVE POSITION DRIVER - L69C4773, 1F1-F3  
VALVE POSITION DRIVER - AMS 186C8105, 1F1-F4  
FIRST MADE FOR ENG MARK II

CONT ON SHEET 8

SH. NO. 7




FIGURE 2: Servoamp response to unit step input (Section E)




FIGURE 3: FET distortion  $|T_1 - T_2| > 10 \text{ us}$

MADE BY J. Aulisi 14 Sept. 1981

ISSUED

SEP 14 1981

APPROVALS

Steam Turbine

Schenectady, N.Y.

DIV OR DEPT.

LOCATION

P3K-AL-U656-A01

CONT ON SHEET 8

SH. NO. 7

CODE 1241

REV. 1

MAY 16 1983

C. PAULINE

PRINTS

REV. NO. 1  
 P3K-AL-0656-A01  
 CONT ON SHEET 9 SH NO. 8

TITLE  
 CIRCUIT BOARD SPECIFICATIONS  
 VALVE POSITION DRIVER - 169C4773, 1F1-F3  
 VALVE POSITION DRIVER - AMS 186CB105, 1F1-F4  
 FIRST MADE FOR EHC MARK II

REVISION

MAY 16 1983

① P. AULISI




FIGURE 4:  $V_{TP7}$  - Transducer fully extended  
 TOP STOP  
 TS




FIGURE 5:  $V_{TP52}$  - Transducer fully extended  
 TOP STOP  
 TS

PRINT

MADE BY  
 J. Aulisi 14 Sept. 1981  
 ISSUED  
 SEP 14 1981

APPROVALS

Steam Turbine

DIV OR  
DEPT.

P3K-AL-0656-A01

Schenectady, N.Y.

LOCATION

CONT ON SHEET 9

SH NO. 8



REV NO. <b>1</b>	TITLE CIRCUIT BOARD SPECIFICATIONS VALVE POSITION DRIVER 169C4773, 1F1-F3 VALVE POSITION DRIVER - A25 186CM105, 1F1-F4
P3K-AL-0656-A01	FIRST MADE FOR EHC MARK II
CONT ON SHEET 10	SN NO. 9




FIGURE 6:  $V_{TP7}$  - Transducer Inserted 8" Bottom Stop BS




FIGURE 7:  $V_{TP52}$  - Transducer Inserted 8" Bottom Stop BS

MADE BY J. Aulisi 14 Sept. 1981	APPROVALS	Steam Turbine	DIV OR DEPT.	P3K-AL-0656-A01
ISSUED SEP 14 1981		Schenectady N.Y.	LOCATION	CONT ON SHEET 10 SN NO. 9

# MKIII INDUSTRIAL

PRINT ON SHEET

SH NO.

COORD ON SHEET

SH NO.


FIRST MADE FOR

E.H.C.


SERVO INPUT 0 TO 10V

REV


MCV



MSV



ICV



ISSUED

APPROVALS

SH OR DEPT.

1-77 Test

LOCATION CONT ON SHEET

SH NO.

PRINTS

REV NO. 1  
P3K-AL-0656-A01  
CONT ON SHEET — SH NO. 10

TITLE  
CIRCUIT BOARD SPECIFICATIONS  
VALVE POSITION DRIVER 169C4773, 1F1-F3  
VALVE POSITION DRIVER - AMS 186C8105, 1F1-F4  
FIRST MADE FOR EHC MARK II

CONT ON SHEET — SH NO. 10

REV: 3

DATE MAY 16 1981

PREPARED BY: S.S. Abelson DATE 5/12/83  
9/10/81

S.S. Abelson  
EHC DESIGN ENGINEERING  
Building 285 Room 231

APPROVED BY: R.L. Olson DATE 9/10/81

R.L. Olson, Manager  
EHC DESIGN ENGINEERING  
Building 285 Room 231

PRINT

MADE BY J. Rullisi 14 Sept. 1981  
ISSUED SEP 14 1981

APPROVALS

Stream Turbine  
Schenectady, N.Y.

DIV OR DEPT. LOCATION  
P3K-AL-0656-A01  
CONT ON SHEET — SH NO. 10