IC3602A127ANL1

Using the attached diagram verify all resistors, capacitors and wiring of the unit.

Using the big blue load cart connect a 30-ohm load between the output terminals P1 and N1.

Connect 220VAC 3 phase to input terminals L1, L2 and L3.

Apply power and verify approx. 300VDC @ 10 Adc between output terminals P1 and N1.

Verify +3.2mvdc between S1 and S2 with S2 being the positive.

End of test.

