



GE Energy

## Functional Testing Specification

*Parts & Repair Services  
Louisville, KY*

**LOU-GED-DS3800NAIF**

### Test Procedure for a DS3800NAIF

**DOCUMENT REVISION STATUS:** Determined by the last entry in the "REV" and "DATE" column

REV.	DESCRIPTION	SIGNATURE	REV. DATE
A	Initial release	Steve Pharris	11/23/09
B			
C			

© COPYRIGHT GENERAL ELECTRIC COMPANY

Hard copies are uncontrolled and are for reference only.

PROPRIETARY INFORMATION – THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION OF GENERAL ELECTRIC COMPANY AND MAY NOT BE USED OR DISCLOSED TO OTHERS, EXCEPT WITH THE WRITTEN PERMISSION OF GENERAL ELECTRIC COMPANY.

<b>PREPARED BY</b> Steve Pharris	<b>REVIEWED BY</b>	<b>REVIEWED BY</b>	<b>QUALITY APPROVAL</b> Robert Duvall
<b>DATE</b> 11/23/09	<b>DATE</b>	<b>DATE</b>	<b>DATE</b> 11/30/09

<p><b>LOU-GED-DS3800NAIF REV. A</b></p>	<p><b>g</b></p> <p><b>GE Energy</b> Parts &amp; Repair Services Louisville, KY</p>	<p><b>Page 2 of 11</b></p>
---	--	----------------------------

## 1. SCOPE

1.1 This is a functional testing procedure for a DS3800NAIF.

## 2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

## 3. APPLICABLE DOCUMENTS

3.1 The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.

3.1.1 Check Electronic folder for more information

## 4. ENGINEERING REQUIREMENTS

### 4.1 Equipment Cleaning

4.1.1 Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.

### 4.2 Equipment Inspection

4.2.1 Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:

4.2.1.1 Wires - broken, cracked, or loosely connected

4.2.1.2 Terminal strips / connectors - broken or cracked

4.2.1.3 Components - visually damaged

4.2.1.4 Capacitors - bloated or leaking

4.2.1.5 Solder joints - damaged or cold

4.2.1.6 Circuit board - burned or de-laminated

4.2.1.7 Printed wire runs / Traces - burned or damaged

## 5. EQUIPMENT REQUIRED

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		Fluke 87 DMM (or Equivalent)
1		O-Scope
1		Fluke 715 Voltage Calibrator
1		Rainbow Box
1		DS3800 Power Supply
1		DS3800 Connector Box

<p><b>LOU-GED-DS3800NAIF REV. A</b></p>	<p><b>g</b></p> <p><b>GE Energy</b> Parts &amp; Repair Services Louisville, KY</p>	<p><b>Page 3 of 11</b></p>
---	--	----------------------------

## 6. TESTING PROCESS

### 6.1 Setup

#### 6.1.1 Make the following connections

PA1-PA9  
PA4-PA1  
SW81-PA53-H  
SW82-PA59-H  
SW83-PA58-H  
SW84-PA68-L  
SW85-PA66-L  
SW86-PA11-H  
SW87-PA72-L  
SW88-PA14-H

### 6.2 Testing Procedure

#### 6.2.1 Before testing replace the three 8254's

#### 6.2.2 Verify IMOK is illuminated

#### 6.2.3 Verify 10.24VDC at pin1 of U42, pin17 of U19, and pin4 of U18

#### 6.2.4 Using Fluke apply 5VDC to PA6 (continue using fluke at the following points at the specified voltage)

#### 6.2.5 Verify 330Khz signal at pins 9 and 15 of U15

#### 6.2.6 Apply 6VDC to PA32

#### 6.2.7 Verify 400Khz signal at pins 9 and 15 of U15

#### 6.2.8 Apply 8VDC to PA8

#### 6.2.9 Verify 260Khz signal at pins 9 and 15 of U15

#### 6.2.10 Verify 440Khz signal at pin 9 of U16, and pin 18 of U15

#### 6.2.11 Apply 9VDC to PA37

#### 6.2.12 Verify 295Khz signal at pins 9 and 15 of U15

#### 6.2.13 Verify 496Khz signal at pin 9 of U16, and pin 18 of U15

#### 6.2.14 Apply 10VDC to PA10

#### 6.2.15 Verify 330Khz signal at pins 9 and 15 of U15


#### 6.2.16 Verify 553Khz signal at pin 9 of U16 and pin 18 of U15

#### 6.2.17 Apply 11VDC to PA44

#### 6.2.18 Verify 365Khz signal at pins 9 and 15 of U15

<b>LOU-GED-DS3800NAIF REV. A</b>	<div data-bbox="548 205 581 254" data-label="Image"></div> <div data-bbox="737 258 980 333" data-label="Text"> <p><b>GE Energy</b> Parts &amp; Repair Services Louisville, KY</p> </div>	<b>Page 4 of 11</b>
--------------------------------------	--	---------------------

- 6.2.19** Verify 610Khz signal at pin 9 of U16 and pin 18 of U15
- 6.2.20** Remove VDC from PA44
- 6.2.21** Set SW87-H
- 6.2.22** Toggle SW86-L-H
- 6.2.23** Set SW84 and SW85-H
- 6.2.24** Toggle SW86
- 6.2.25** Verify 581Khz signal at pins 9 and 15 of U15
- 6.2.26** Verify 550Khz signal at pin 9 of U16, and pin18 of U15
- 6.2.27** Set SW85-L
- 6.2.28** Toggle SW86
- 6.2.29** Verify <10hz signal at pins 9 and 15 of U15
- 6.2.30** Verify <10hz signal at pin 9 of U16, and pin 18 of U15
- 6.2.31** Set SW84-L
- 6.2.32** Set SW85-H
- 6.2.33** Toggle SW86
- 6.2.34** Verify 583Khz signal at pins 9 and 15 of U15
- 6.2.35** Verify 550Khz signal at pin 9 of U16 and pin 18 of U15
- 6.2.36** Set SW85-L
- 6.2.37** Set SW87-L
- 6.2.38** Toggle SW86
- 6.2.39** Apply 7VDC to PA12
- 6.2.40** Verify 486Khz signal at pins 15 and 18 of U16
- 6.2.41** Apply 8VDC to PA13
- 6.2.42** Verify 203Khz signal at pins 15 and 18 of U16
- 6.2.43** Apply 9VDC to PA15
- 6.2.44** Verify 166Khz signal at pins 15 and 18 of U16
- 6.2.45** Verify 292Khz signal at pins 15 and 18 of U17
- 6.2.46** Connect PA2-SW89
- 6.2.47** Verify pin 9 of U17 follows SW89
- 6.2.48** Remove connection at PA2
- 6.2.49** Set SW87-H
- 6.2.50** Set SW84-H
- 6.2.51** Set SW85-H
- 6.2.52** Toggle SW86

<b>LOU-GED-DS3800NAIF REV. A</b>	 <b>GE Energy</b> <i>Parts &amp; Repair Services</i> <i>Louisville, KY</i>	<b>Page 5 of 11</b>
--------------------------------------	--	---------------------

**6.2.53** Verify 532Khz signal at pins 15 and 18 of U16

**6.2.54** Verify 532Khz signal at pins 15 and 18 of U17

**6.2.55** Set SW84-L

**6.2.56** Toggle SW86

**6.2.57** Verify 532Khz signal at pins 15 and 18 of U16

**6.2.58** Verify 532Khz signal at pins 15 and 18 of U17

**6.2.59** Set SW84-H

**6.2.60** Set SW85-L

**6.2.61** Toggle SW86

**6.2.62** Verify <10hz signal at pins 15 and 18 of U16

**6.2.63** Verify <10hz signal at pins 15 and 18 of U17

**6.2.64** Remove all connections from SW85-SW96

**6.2.65** Connect PA11-SW84-L

**6.2.66** Make the following connections

SW85-PA68-H

SW86-PA66-H

SW87-PA74-H

SW88-PA64-H

SW89-PA76-H

SW90-PA61-H

SW91-PA72-H

SW92-PA70-H

SW93-PA41-H

SW94-PA48-H

SW95-PA47-H

SW96-PA50-H

**6.2.67** Set SW81-H

**6.2.68** Set SW82-H

**6.2.69** Set SW83-L


**6.2.70** Set SW84-L

**6.2.71** Connect DMM to TP16


**6.2.72** Verify table below

Output	SW85	SW86	SW87	SW88	SW89	SW90	SW91	SW92	SW93	SW94	SW95	SW96
-10VDC	H	H	H	H	H	H	H	H	H	H	H	H
-0.031	H	H	H	H	H	H	H	H	H	H	H	L
-0.026	L	H	H	H	H	H	H	H	H	H	H	L
-0.016	L	L	H	H	H	H	H	H	H	H	H	L
0.003	L	L	L	H	H	H	H	H	H	H	H	L
0.043	L	L	L	L	H	H	H	H	H	H	H	L
0.121	L	L	L	L	L	H	H	H	H	H	H	L
0.277	L	L	L	L	L	L	H	H	H	H	H	L
0.589	L	L	L	L	L	L	L	H	H	H	H	L
1.21	L	L	L	L	L	L	L	L	H	H	H	L
2.46	L	L	L	L	L	L	L	L	L	H	H	L
4.95	L	L	L	L	L	L	L	L	L	L	H	L
9.95	L	L	L	L	L	L	L	L	L	L	L	L
-.035	L	L	L	L	L	L	L	L	L	L	L	H
-.040	H	L	L	L	L	L	L	L	L	L	L	H
-.050	H	H	L	L	L	L	L	L	L	L	L	H
-.069	H	H	H	L	L	L	L	L	L	L	L	H
-.109	H	H	H	H	L	L	L	L	L	L	L	H
-.187	H	H	H	H	H	L	L	L	L	L	L	H
-.342	H	H	H	H	H	H	L	L	L	L	L	H
-.654	H	H	H	H	H	H	H	L	L	L	L	H
-1.278	H	H	H	H	H	H	H	H	L	L	L	H
-2.52	H	H	H	H	H	H	H	H	H	L	L	H
-5.02	H	H	H	H	H	H	H	H	H	H	L	H
-10.00	H	H	H	H	H	H	H	H	H	H	H	H

- 6.2.73** Move DMM to TP15
- 6.2.74** Connect PA56 to PA9
- 6.2.75** Repeat above table
- 6.2.76** Move DMM to TP14
- 6.2.77** Move PA56-PA60
- 6.2.78** Repeat above table
- 6.2.79** Move DMM to TP13
- 6.2.80** Connect PA56-PA9
- 6.2.81** Repeat above table
- 6.2.82** Move DMM to TP12

<b>LOU-GED-DS3800NAIF REV. A</b>	  <b>GE Energy</b> <i>Parts &amp; Repair Services</i> <i>Louisville, KY</i>	<b>Page 7 of 11</b>
--------------------------------------	--	---------------------

- 6.2.83** Set SW82-L
- 6.2.84** Set SW83-H
- 6.2.85** Remove connections at PA56 and PA60
- 6.2.86** Repeat above table
- 6.2.87** Move DMM to TP11
- 6.2.88** Connect PA56 to PA9
- 6.2.89** Repeat above table
- 6.2.90** Move DMM to TP8
- 6.2.91** Move PA56-PA60
- 6.2.92** Repeat above table
- 6.2.93** Move DMM to TP9
- 6.2.94** Connect PA56-PA9
- 6.2.95** Repeat above table
- 6.2.96** Verify -15VDC at PA18 and PA22
- 6.2.97** Remove all connections from SW85-SW96
- 6.2.98** Apply 7VDC to PA17 and PA21
- 6.2.99** Verify TP6 and TP7 = -4.3VDC
- 6.2.100** Set SW81-H
- 6.2.101** Set SW82-H
- 6.2.102** Set SW83-H
- 6.2.103** Connect SW85-PA14-H
- 6.2.104** Set SW84-H
- 6.2.105** Make the following connections
  - SW86-PA72-L
  - SW87-PA61-H
  - SW89-PA74-H
  - SW90-PA64-H
  - SW91-PA76-H
- 6.2.106** Using Fluke Voltage Calibrator set pin 13 of U25 for -5VDC
- 6.2.107** Set SW87-L
- 6.2.108** Toggle SW84
- 6.2.109** Set SW87-H
- 6.2.110** Toggle SW84
- 6.2.111** Set SW85-L

<b>LOU-GED-DS3800NAIF REV. A</b>	  <b>GE Energy</b> <i>Parts &amp; Repair Services</i> <i>Louisville, KY</i>	<b>Page 8 of 11</b>
--------------------------------------	--	---------------------

**6.2.112** Remove PA72

**6.2.113** Verify the following

PA39-H

PA41-H

PA46-H

PA47-H

PA48-H

PA49-H

PA50-H

PA51-H

PA70-H

PA72-H

**6.2.114** Reconnect PA72

**6.2.115** Set SW85-H

**6.2.116** Toggle SW84

**6.2.117** Using Fluke Voltage Calibrator set for 0VDC at pin 13 of U25

**6.2.118** Set SW87-L

**6.2.119** Toggle SW84

**6.2.120** Set SW87-H

**6.2.121** Toggle SW84

**6.2.122** Set SW85-L

**6.2.123** Remove PA72

**6.2.124** Verify the following

PA39-L

PA46-H

PA49-H

PA51-H

PA50-H

PA47-H

PA48-H


PA41-H

PA70-H


PA72-L

**6.2.125** Reconnect PA72



<b>LOU-GED-DS3800NAIF REV. A</b>	  <b>GE Energy</b> <i>Parts &amp; Repair Services</i> <i>Louisville, KY</i>	<b>Page 9 of 11</b>
--------------------------------------	--	---------------------

- 6.2.126** Set SW85-H
- 6.2.127** Toggle SW84
- 6.2.128** Apply 10.52VDC to PA17 and PA21
- 6.2.129** Verify 4.99VDC at pin 13 of U25
- 6.2.130** Set SW87-L
- 6.2.131** Toggle SW84
- 6.2.132** Set SW87-H
- 6.2.133** Toggle SW84
- 6.2.134** Set SW85-L
- 6.2.135** Remove PA72
- 6.2.136** Verify the following
  - PA39-L
  - PA46-L
  - PA49-L
  - PA51-L
  - PA50-L
  - PA47-L
  - PA48-L
  - PA41-L
  - PA70-L
  - PA72-L
- 6.2.137** Reconnect PA72
- 6.2.138** Set SW89-L
- 6.2.139** Set SW85-H
- 6.2.140** Repeat steps 6.2.106-6.2.137
- 6.2.141** Move PA17 and PA21 to PA54 and PA57
- 6.2.142** Set SW89-H
- 6.2.143** Set SW90-L
- 6.2.144** Connect PA64 and PA66 to PA1
- 6.2.145** Set SW85-H
- 6.2.146** Toggle SW84
- 6.2.147** Repeat steps 6.2.106-6.2.137
- 6.2.148** Set SW91-H
- 6.2.149** Set SW89-L

<b>LOU-GED-DS3800NAIF REV. A</b>	 <b>GE Energy</b> <i>Parts &amp; Repair Services</i> <i>Louisville, KY</i>	<b>Page 10 of 11</b>
--------------------------------------	--	----------------------

- 6.2.150** Toggle SW84
- 6.2.151** Repeat steps 6.2.106-6.2.137
- 6.2.152** Move PA54-PA32
- 6.2.153** Remove PA57
- 6.2.154** Set SW89-H
- 6.2.155** Set SW90-H
- 6.2.156** Set SW91-L
- 6.2.157** Set SW85-H
- 6.2.158** Toggle SW84
- 6.2.159** Repeat steps 6.2.106-6.2.137
- 6.2.160** Move PA32-PA37
- 6.2.161** Set SW89-L
- 6.2.162** Set SW90-H
- 6.2.163** Set SW91-L
- 6.2.164** Set SW85-H
- 6.2.165** Toggle SW84
- 6.2.166** Repeat steps 6.2.106-6.2.137
- 6.2.167** Move PA37-PA12
- 6.2.168** Set SW89-H
- 6.2.169** Set SW90-L
- 6.2.170** Set SW91-L
- 6.2.171** Set SW85-H
- 6.2.172** Toggle SW84
- 6.2.173** Repeat steps 6.2.106-6.2.124
- 6.2.174** Move PA12-PA15
- 6.2.175** Set SW89-L
- 6.2.176** Set SW90-L
- 6.2.177** Set SW91-L
- 6.2.178** Repeat steps 6.2.126-6.2.137
- 6.2.179** Connect PA70-SW93-L
- 6.2.180** Set SW85-H
- 6.2.181** Toggle SW84
- 6.2.182** Verify IMOK LED turns off
- 6.2.183** Set SW93-H

<b>LOU-GED-DS3800NAIF REV. A</b>	<div data-bbox="548 205 581 252" data-label="Image"></div> <div data-bbox="737 258 980 333" data-label="Text"> <p><b>GE Energy</b> Parts &amp; Repair Services Louisville, KY</p> </div>	<b>Page 11 of 11</b>
--------------------------------------	--	----------------------

**6.2.184** Toggle SW84

**6.2.185** Verify IMOK LED turns on

**6.2.186** Set SW84L

**6.2.187** Using DMM monitor PA20

**6.2.188** Verify PA20-H when any of the following points are grounded

PA23

PA24

PA25

PA26

PA27

PA28

PA29

PA30

PA31

PA33

PA34

PA35

PA36

PA38

PA40

PA42

**6.3 \*\*\*TEST COMPLETE \*\*\***

## **7. NOTES**

**7.1**

## **8. ATTACHMENTS**

**8.1**