g		GE Energy	Functional	Functional Testing Specification				
	Parts & Repair Services Louisville, KY			LOU-GED-DS200TCPAG1A				
Test Procedure for a TCPA								
	MENT REVISION STATUS:	Determined by the last entry in t	he "REV" and "DATE" column					
REV.	Initial release	DESCRIPTION		SIGNATURE	REV. DATE			
Α	miliai ielease			JBARTON	12/4/2014			
В	New Cimplicty Scree	n		JBARTON	12/10/15			
С								
© COP	YRIGHT GENERAL ELECTF	CIC COMPANY						
Hard copies are uncontrolled and are for reference only. PROPRIETARY INFORMATION – THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION OF GENERAL ELECTRIC COMPANY AND MAY NOT BE USED OR DISCLOSED TO OTHERS, EXCEPT WITH THE WRITTEN PERMISSION OF GENERAL ELECTRIC COMPANY.								
JBAR	ARED BY TON	REVIEWED BY	REVIEWED BY	QUALITY AP	PROVAL			
DATE 12/4/2	2014	DATE	DATE	DATE				

	g	
LOU-	GE Energy	Page 2 of 5
REV. A	Parts & Repair Services	
	Louisville, KY	

1. SCOPE

1.1 This is a functional testing procedure for a Card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
 - **3.1.1** Check board's electronic folder for more information

4. **ENGINEERING REQUIREMENTS**

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to site specific SRA's for cleaning guidelines.
- **4.2** Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - 4.2.1.1 Wires broken, cracked, or loosely connected
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - 4.2.1.3 Components visually damaged
 - **4.2.1.4** Capacitors bloated or leaking
 - 4.2.1.5 Solder joints damaged or cold
 - 4.2.1.6 Circuit board burned or de-laminated
 - 4.2.1.7 Printed wire runs / Traces burned or damaged

5. EQUIPMENT REQUIRED

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		SM1 HMI
1		MKV SIMPLEX STEAM PANEL
1		DMM

	g	
LOU-	GE Energy	Page 3 of 5
REV. A	Parts & Repair Services Louisville, KY	

6. Modifications/Upgrades

6.1 Fill out if applicable.

7. Testing Process

7.1 Setup

- 7.1.1 Remove power to PLU core
- **7.1.2** Remove the test card from the PLU Core in location X
- 7.1.3 Install the DS200DCPAG1A card to the UUT
- **7.1.4** Install the 4 PROM's from the test card
- **7.1.5** Set all jumpers to match test card
- 7.1.6 Install UUT and attach ALL related ribbon cables and power connection and IONET
- 7.1.7 Power back up PLU core
- 7.1.8 Reset R to obtain A7 status
- 7.1.9



Note:


7.2 Testing Procedure

- **7.2.1** Using DMM verify: COM located next to PROM's and crystal
 - 7.2.1.1 5VDC located just above COM
 - **7.2.1.1.1** If not 5VDC, adjust pot RV1 to within +5.05Vdc regulated
 - 7.2.1.1.2 Verify +15VDC +/- 10% (located top left corner) regulated
 - 7.2.1.1.3 Verify -15VDC +/- 10% (located top left corner) regulated
 - 7.2.1.1.4 Verify +24VDC +/- 20% (located top left corner) NOT regulated
 - 7.2.1.1.5 Verify -24VDC +/- 20% (located top left corner) NOT regulated
- 7.2.2 Open up TCPA Test screen on ST1 HMI
 - 7.2.2.1 Verify All I/O are ~ equal in values

LOU-REV. A g

GE EnergyParts & Repair Services
Louisville, KY

Page 4 of 5




- 7.2.2.2
- .2.3 Using DiagC Screen: Locate the <R> TCPA
 - **7.2.3.1** Verify TCPA Power Supply screen reads correct voltages.
 - 7.2.3.2 Verify the PROX 1-10 are all functioning and equal in value
 - **7.2.3.2.1** (Attach screenshot)
 - 7.2.3.3 Verify the PROX 11-10 are all functioning and equal in value
 - **7.2.3.3.1** (See above)
 - 7.2.3.4 Same screen verify the 4 mA
 - **7.2.3.4.1** (See above)
- **7.2.4** Open the Logic Forcing Program
 - 7.2.4.1 Open the TCPA_RELAY_TEST In the F:\Unit1\TCPA directory
 - **7.2.4.1.1** (attach screenshot)
- 7.2.5 Force the TCPACO01 signal to 1 and verify the relay engages and RELAY1 illuminates

LOU-

REV. A

g

GE Energy Parts & Repair Services Louisville, KY Page 5 of 5



7.2.5.2 Force TCPACO01 signal back to 0 and verify the relay disengages and LED goes

7.2.6 Continue this throughout the list ending in TCPACO21

Note: Some RELAY's are set for a delay in the I/O Config. This may be set for 1 second or 5 seconds.

- **7.3** Select the UN-FORCE ALL Button and verify ALL are at 0 with < > removed from signal designation
- 7.4 Post Testing Burn-in Required __x_Yes ___ No

Note: All MARK I, II, & III Nuclear Turbine related cards require a post testing burn-in of 100 hours.

7.5 ***TEST COMPLETE ***

7.2.5.1

- 8. Notes
 - **8.1** None at this time?
- 9. Attachments
 - **9.1** None at this time?