g	GE Industrial Systems	Functional Testing Specification	
	Renewal Services Louisville, KY	LOU-GED-531X146E	3DHx-
	Functional test procedure for 531X1	46BDHx base driver card	
DOCUMENT REVIS	SION STATUS: Determined by the last entry in the "RE	V" and "DATE" column	
REV. DESCRIPTION Revised By		REV. DATE	

REV.	DESCRIPTION	Revised By	REV. DATE
Α	Initial release	D. Smith	06-01-98
В	Imported procedure into new format	R. Duvall	06-17-02
С			

#### © COPYRIGHT GENERAL ELECTRIC COMPANY

 $PROPRIETARY\ INFORMATION-THIS\ DOCUMENT\ CONTAINS\ PROPRIETARY\ INFORMATION\ OF\ GENERAL\ ELECTRIC\ COMPANY\ AND\ MAY\ NOT\ BE\ USED\ OR\ DISCLOSED\ TO\ OTHERS,\ EXCEPT\ WITH\ THE\ WRITTEN\ PERMISSION\ OF\ GENERAL\ ELECTRIC\ COMPANY.$ 

PREPARED BY David Smith	REVIEWED BY David Bush	REVIEWED BY	Robet Dunll
<b>DATE</b> 06-01-98	<b>DATE</b> 06-01-98	DATE	<b>DATE</b> 06-17-02

g

# LOU-GED-531X146BDHx - REV. B

#### GE Industrial Systems Renewal Services Louisville, KY

Page 2 of 4

#### Functional test procedure for 531X146BDHx base driver card

#### 1. SCOPE

1.1 This is a functional testing procedure for 531X146BDHxx AC-300 base driver card.

### 2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

### 3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
  - 3.1.1 GEK-85781

#### 4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
  - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.
- 4.2 Equipment Inspection
  - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
    - 4.2.1.1 Wires broken or cracked
    - 4.2.1.2 Terminal strips / connectors broken or cracked
    - **4.2.1.3** Loose wires
    - 4.2.1.4 Components visually damaged
    - 4.2.1.5 Capacitors leaking
    - 4.2.1.6 Solder joints damaged or cold
    - 4.2.1.7 Circuit board burned or de-laminated
    - 4.2.1.8 Printed wire runs burned or damaged

#### 5. EQUIPMENT REQUIRED

**5.1** The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description	
1	N/A	Tektronix 2215 or equivalent O-Scope	
1	N/A	Fluke 85 or equivalent DMM	
1	H033732	531X146BDHx Test Fixture	
1	H033764	AC-300 Drive test fixture	

	g	
LOU-GED-531X146BDHx -	GE Industrial Systems	Page 3 of 4
REV. B	Renewal Services	
	Louisville, KY	

## 6. TESTING PROCESS

**6.1** Verify with DMM the following table 1 resistance values on all RN\_ resistor packs.


**NOTE**: On all RN\_ resistor packs pins 5 and 6 have been clipped and pin 1 on RN\_ is circled on circuit board . All jumpers on board should be out.

From pin 1 to 2	1.4 to 1.5 Ohms
From pin 1 to 3	1.4 to 1.5 Ohms
From pin 1 to 4	.8 to 1.0 Ohms
From pin 7 to 8	10.4 to 10.8 Ohms
From pin 7 to 9	10.4 to 10.8 Ohms
From pin 7 to 10	3.8 to 4.0 Ohms

Table 1

- **6.2** Verify with DMM that the following yellow or orange tantalum capacitors are not shorted . C8, C9, C18, C19, C28, C29, C61, C62, C50, C60, C63, C64.
- **6.3** Place board on test fixture and connect all cables
- 6.4 Turn CURRENT FEEDBACK on test fixture to MIN.
- 6.5 Turn SELECTOR SWITCH on test fixture to POS 1
- **6.6** Push POWER switch to ON red light should come on.
- 6.7 Connect channel 1 of oscilloscope to BNC connector on front of test fixture
- 6.8 Set scope as follows; probe for x1, CH1V / DIV to 5, A and B SEC / DIV 20 us.
- **6.9** Turn SELECTOR SWITCH to positions 1-6 verify the waveform below is on all pos.


POS 1	POS 2	POS 3	POS 4	POS 5	POS 6
1APL	1BPL	1CPL	2APL	2BPL	2CPL
PINS 1-2					



	g	
LOU-GED-531X146BDHx - REV. B	GE Industrial Systems Renewal Services	Page 4 of 4
ICEV. B	Louisville, KY	

6.10 Turn SELECTOR SWITCH to positions 7-9 verify the waveform below is on all pos

POS 7	POS 8	POS 9
U17 PIN 6	U18 PIN 6	U19 PIN 6



- **6.11** Verify on positions 7-9 that when CURRENT FEEDBACK is increased duty cycle changes and output goes to + 5 VDC. CURRENT FEEDBACK on test fixture puts a variable DCV input to IAPL PINS 3-4 to IBPL PINS 3-4 to ICPL PINS 3-4 with pin 4 as ground and pin 3 as the input.
- 6.12 Verify that pin 1 of U20 has + 5 VDC.
- 6.13 Remove board from fixture
- 6.14 Reference GEK 85781 and install into AC 300
- 6.15 Turn 480 Disconnect on
- **6.16** Push START on Drive and turn speed pot up motor should turn and be smooth.
- 6.17 Remove from Drive
- 6.18 End of test

## 7. NOTES

**7.1** None at this time.