g	GE Energy		Func	ctional Testing Sp	ecification	
<u> </u>				one recuiring op		
	Parts & Repa Louisville, KY		L	LOU-TOFFEE-IS200WETCH1A		
	Test Pr	ocedure for IS200WE	TCH1A card tested on t	he Toffee System		
DOCUMENT REVISION STATUS: Determined by the last entry in the "REV" and "DATE" column						
REV.		DESCRIPTION		SIGNATURE	REV. DATE	
Α	Initial release			P. Kelley	4/26/2013	
В						
С						
	YRIGHT GENERAL ELECTI					
	opies are uncontrolled and are to IETARY INFORMATION –		NS PROPRIETARY INFORMATIO	ON OF GENERAL ELECTRIC	COMPANY AND	
PROPRIETARY INFORMATION – THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION OF GENERAL ELECTRIC COMPANY AND MAY NOT BE USED OR DISCLOSED TO OTHERS, EXCEPT WITH THE WRITTEN PERMISSION OF GENERAL ELECTRIC COMPANY.						
PREPA	ARED BY	REVIEWED BY	REVIEWED BY	QUALITY AP	PROVAL	
P. Ke				Charlie We		
DATE		DATE	DATE	DATE		
4/26/2	2013			4/26/2013		

g

LOU-TOFFEE-IS200WETCH1A REV. A

GE Energy Part & Repair Services Louisville, KY Page 2 of 4

Functional test procedure for equipment tested on the Toffee Test system

1. SCOPE

1.1 This is a functional testing procedure for the IS200WETCH1A card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
 - **3.1.1** Check board's electronic folder for more information.

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to site specific SRA's for cleaning guidelines.
- 4.2 Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - 4.2.1.1 Wires broken or cracked
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - **4.2.1.3** Loose wires
 - 4.2.1.4 Components visually damaged
 - 4.2.1.5 Capacitors leaking
 - 4.2.1.6 Solder joints damaged or cold
 - 4.2.1.7 Circuit board burned or de-laminated
 - 4.2.1.8 Printed wire runs burned or damaged

5. EQUIPMENT REQUIRED

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1	H188818	Toffee Test System #14
1	H190090	Toffee test fixture for IS200WETCH1A

g

LOU-TOFFEE-IS200WETCH1A REV. A

GE EnergyPart & Repair Services
Louisville, KY

Page 3 of 4

6. TESTING PROCESS

- 6.1 Setup
 - **6.1.1** Install IS200WETCH1A fixture H190090 onto TOFFEE test System.
 - **6.1.2** Install Unit Under Test into test fixture.
- 6.2 Testing Procedure
 - **6.2.1** Double click on the OPERATOR INTERFACE icon on screen.
 - 6.2.2 On the user name dialogue box, choose either administrator or technician. If administrator is selected use password NGTF2008*, technician password is KISS, both are case sensitive. The next window should say configuration management and you should always click on no.
 - 6.2.3 Screen will flicker and box marked single pass will be highlighted. Click on it and it should put up another dialogue box that says Orange book is old. Click O.K. If Orange book needs to be updated, there is an icon for that but I would let Paul or Eric do it until user is familiar with system.
 - 6.2.4 The next dialogue box should say select DUT (device under test). Detected fixture should have the model number being tested and family name should say MVIe. Click the drop down box DUT and your model number should be the only option. Select it and it should appear in the DUT model number. Put your revision level of unit being tested in DUT REV and click ok.
 - 6.2.5 A delay dialogue box appears, counts down and then asks for a serial number, enter 14 and check the boxes marked RUN UPLOADS and DELETED LOGS. Click O.K. If you logged on as an administrator, you will not get this dialogue box. The test will automatically run these.
 - **6.2.6** A delay dialog box appears and counts down, do not stop it and then system runs test. You will get either a pass or fail message.
- 6.3 ***TEST COMPLETE ***

7. NOTES

7.1 Changes to the electronic Toffee test are recorded in the Software Control Database.

g

LOU-TOFFEE-IS200WETCH1A REV. A

GE Energy Part & Repair Services Louisville, KY

Page 4 of 4

8. ATTACHEMENTS

8.1 Picture of the Toffee Test System

