g		GE Energ	ЭУ	Functional T	esting Spe	ecification			
	Parts & Repa Louisville, KY		LOU-GED-118D1596G2						
	Test Procedure for a Total Control Valve Signal card								
	MENT REVISION STATUS					I			
REV.		DESCRIPTION	l		GNATURE	REV. DATE			
Α	Initial release			G.	Chandler	5/20/2013			
В									
С									
Hard co PROPR MAY N	YRIGHT GENERAL ELECTI pies are uncontrolled and are f IETARY INFORMATION — IOT BE USED OR DISCLOSI ARED BY Jandler	for reference only. THIS DOCUMENT CONTA		PERMISSION OF GENER		PROVAL			
DATE 5/20/2	2013	DATE	DATE		DATE 5/20/2013				

	g	
LOU-GED-118D1596G2	GE Energy	Page 2 of 4
REV. A	Parts & Repair Services	
	Louisville, KY	

1. SCOPE

1.1 This is a functional testing procedure for a Total Control Valve Signal card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
 - **3.1.1** Check board's electronic folder for more information
 - **3.1.2** Test Instructions P3K-AL-0403-A01

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to site specific SRA's for cleaning guidelines.
- **4.2** Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - **4.2.1.1** Wires broken, cracked, or loosely connected
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - **4.2.1.3** Components visually damaged
 - 4.2.1.4 Capacitors bloated or leaking
 - 4.2.1.5 Solder joints damaged or cold
 - 4.2.1.6 Circuit board burned or de-laminated
 - 4.2.1.7 Printed wire runs / Traces burned or damaged

5. **EQUIPMENT REQUIRED**

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		Fluke 87 DMM (or Equivalent)
2		22VDC Power supplies
2		15VDC Power supplies
1		Resistor 2K ohm ½ watt

g

LOU-GED-118D1596G2 REV. A

GE EnergyParts & Repair Services Louisville, KY

Page 3 of 4

6. <u>Testing Process</u>

- 6.1 Setup
 - **6.1.1** PS1
 - **6.1.1.1** Connect +22VDC +/-0.002VDC to pin 37.
 - **6.1.1.2** Connect -22VDC +/-0.002VDC to pin 41.
 - 6.1.1.3 Connect common to pin 39.
 - **6.1.2** PS2
 - 6.1.2.1 Connect +15VDC +/-0.1VDC to pin 21
 - 6.1.2.2 Connect -15VDC +/-0.1VDC to pin 37
 - 6.1.2.3 Connect common to pin 25.
 - **6.1.3** Connect a 2Kohm ½ watt load resistor between pins 22 and 23.
 - **6.1.4** Connect pin 7 to pin 39.
 - **6.1.5** Temporarily connect pins 9 and 11 to pin39 (PS1 common).

6.2 Testing Procedure

- **6.2.1** Connect negative lead of a DVM to pin 39.
- **6.2.2** Verify +15.7VDC +/- 1VDC at TP1.
- **6.2.3** Verify -15.7VDC +/- 1VDC at TP2.
- 6.2.4 Zero op amps:
 - **6.2.4.1** When adjusting the potentiometers in the following steps verify smooth and linear operation from full CW to full CCW.
 - **6.2.4.2** With the negative lead connected to pin 39, adjust VR50 for 0VDC +/- .001VDC at TP5.
 - **6.2.4.3** With the negative lead connected to pin 39, adjust VR51 for 0VDC +/- .001VDC at TP50.
 - **6.2.4.4** Move the negative lead of the DVM to pin25 and adjust VR52 for 0VDC +/-.001VDC at TP6.
- **6.2.5** Adjust gain and verify output:
 - **6.2.5.1** Remove 9 and 11 from pin 39.
 - **6.2.5.2** Using a precision voltage source, apply +10VDC +/- 1mV to input 1 (pin 8 with common to pin 39).
 - **6.2.5.3** With negative of DVM connected to pin 39 adjust VR1 for -5VDC at TP5.
 - **6.2.5.4** Verify -5VDC +/-20mV at output (pin22 with common to pin 25).

LOU-GED-118D1596G2
REV. A

GE Energy
Parts & Repair Services
Louisville, KY

Page 4 of 4

- **6.2.5.5** Reverse polarity of input 1 and verify +5VDC +/-20mv at output (pin22 with common to pin 25).
- **6.2.5.6** Move the input from input 1 (pin 8) to input 2 (pin 10).
- **6.2.5.7** With negative of DVM connected to pin 39 adjust VR2 for -5VDC at TP5.
- 6.2.5.8 Verify -5VDC +/-20mV at output (pin22 with common to pin 25).
- **6.2.5.9** Reverse polarity of input 2 and verify +5VDC +/-20mV at output (pin22 with common to pin 25).
- 6.3 Post Testing Burn-in

Required ___ Yes ___ No

 \mathbb{Z}

Note: All MARK I, II, & III Turbine related cards require a post testing burn-in of 100 hours.

- **6.3.1** Apply BUS or Operational power to the card for a period of 100 hours.
- **6.3.2** Re-test card while warm using the above procedure.
- 6.4 ***TEST COMPLETE ***
- 7. Notes
 - **7.1** None at this time.
- 8. Attachments
 - **8.1** None at this time.