P24B-AL-4816

3 CONT ON SHEET

SH NO.

REVISION

C. 7) MAR 14

TITLE

PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD

CONT ON SHEET

P24B-AL-4816

FIRST MADE FOR 170X337 and 170X325

(A) GENERAL

> The 125 VDC power relay board consists of relays each of which contains one N.C. and a N.O. contact each set of contacts contains a common lead. The common and N.O. and N.C. contacts are brought out of the P.C. board at a 41 pin connector.

Mercury wetted relays (G.E. dwg. U4039) are used. Since they are operated at approximately 50 VDC, dropping resistors are seriesed with them. The relays are also operated through the 41 pin connector.

The tests are set up for panel operation, ie, no probes are applied to the board unless troubleshooting is indicated.

The first test, RESISTANCE TEST, is used to determine whether or not a board is ready for the application of power. Upon satisfactory performance of this test, the relays are energized.

In the "Current Test" the relay is checked for proper current by measuring the voltage drop across a resistor of about 1/10 the circuit resistance.

The switching test uses lamps as indicators of contact performance.

The contacts of some relay boards (see table) are protected by an RC network across each contact. This is used to help protect against contact damage due to breaking of the current path to inductive loads.

When test has been completed and data recorded as required, sign and date the data sheet and furnish Control Engineering with one (1) copy.

PRINTS TO

MADE BY J.W. KOZUBAL Mar. ISSUED MAR 27 1968

STEAM TURBINE

SCHENECTADY

APPROVALS.

DIV OR \_ DEPT.

P24B-AL-4816

SH NO.

CODE IDENT N

FF-803-WA (9-66) PRINTED IN U.S.A.

LOCATION CONT ON SHEET

+

+

273-12 273-13

273-71 273-2

Les Proda D. C.

R2/

CONT ON SHEET

REVISIO

TITLE P24B-AL-4816

PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD

CONT ON SHEET

FIRST MADE FOR 170X337 and 170X325

(B) TEST EQUIPMENT

+

+

+

- (1) Standard Patch Panel
- Patch Board (Marked: Power Relay Board 125 V)
- (3) Oscilloscope, both inputs floating
- (4) Voltmeter, Digital, Hewlett Packard 3440A or equiv.
- (5) Ohmmeter, Simpson Multitester or Equiv.
- (6) Power Supply, @ 2 amp, Output within 1% no load to full load, ripple less than .03 Volts RMS. Both outputs floating. 50 - 300 VDC variable
- Resistor, 500 <u>1+ 5%</u> @ 5W (PCR 1-3) Resistor  $2K \pm 5\%$  @ 5W (PCR 4)
  - Inductor, L, U4039 Relay Coil or Equiv.
  - CAPACITOR, C, 1 Mf

273-2 273-1: 273-1 273-1

R2

MADE BY J.W. KOZUBAL APPROVALS DIV OR Mar. 21. 68 STEAM TURBINE \_ DEPT MAR 27 1968 SCHENECTADY

LOCATION CONT ON SHEET

P24B-AL-4816

CODE IDENT !

PRINTS 1

273-7

CONT ON SHEET

SH NO.

REVISIO

P24B-AL-4816

SH NO.

CONT ON SHEET 5

+

TITLE PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD

FIRST MADE FOR 170X337 and 170X325

(C) SET UP

CAUTION: A resistance test will be run first. The 125 V and 24 Volt power must be off when the board under test is plugged in. Failure to follow this will cause damage if there are shorts in the board.

- (1) Interconnect patch board and test panel as shown in fig. 1 by using pre-wired patch board.
- (2) Connect external 500 /5W resistor (PCR1-3) or 2K/5W resistor (RCR4) between BP-7 and BP-8.
- (5) Connect DVM to BP-7 and BP-8 (+ on BP-7).
- (4) Connect external power supply (125 VDC) to Bp-1 and BP-2 (+ on BP-1).
- (5) Connect L to BP-9 and BP-10.
- Connect character to BP-5 and BP-6.
- Connect l f capacitor from BP-11 to BP-12

PRINTS 1

DIV OR STEAM TURBINE P24B-AL-4816 \_ DEPT. LOCATION CONT ON SHEET

J.W. Kozubal Mar. ISSUED

SCHENECTADY

APPROVALS

sh NO. 4 CODE IDENT

FF-803-WA (2-69) PRINTED IN U.S.A.

+

**REVISIO** 

TITLE

PROCESS INSTRUCTIONS

TESTING 125 V RELAY BOARD FIRST MADE FOR 170X537 and 170X325

CONT ON SHEET SH NO.

P24E-AL-4816

(D)RESISTANCE TEST

(1) Remove all power and set SW5 down.

(2) Plug board into PCR-1 or PCR-2 or PCR-3 or FCR-4 (see table 1). (Several shorts exist it plugged into wrong one)

(5) To test for short between 125 V and 24 V circuits Set switches as follows:

	DOWN	CENTER	<u>up</u>	STEP SWITCH
	SW3 SW4			Position 1
	SW5 SW6			
S	SW7			
	sw8			

Step from 1 to 8 of stepping switch readings greater than I Meg. Record lowest reading.

(4) To check resistance of each relay-coil dropping resistor circuit: SW7 UP Step from 1 through 8 and record readings. 19.6 + 2K (PSR-4)Readings 4.4 ± .5K (PCR1-3)

(5) To sheek resistance of lamp circuits. SW6 UP S5 UP SW7 UP Move chmmeter probe from BP-5 to BP-2 step from 1 to 8 and record readings. Reading: Less than 50

APPROVALS

If all resistance readings are normal, proceed to "ourrent test."

Special Note about Step (D-4) Reference figure 1 page 15.

Remove ohmmeter

There are two 2K resistors in parallel and in series with the coil. Since the coil resistance is 8600 ohms and the 2 resistors make up another 1000 ohms, that max reading would only be 9600 ohms (9.6K).

C. Wade 3/17/2012

PRINTS 1

MADE BY J.W. Kozubal Mar. 21, 68 ISSUED

STEAM TURBINE SCHENECTADY, NY

DIV OR

LOCATION

6

SH NO.

FF-603-WA (2-69) PRINTED IN U.S.A.

+

CONT ON SHEET

CODE IDENT I

CONT ON SHEET

REVISIONS

TITLE PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD

FIRST MADE FOR 170X337 and 170X325

(E) CURRENT TEST

P24B-AL-4816

The following test will be used to determine the current drawn by each relay circuit.

(1)	DOWN	CENTER	<u>UP</u>	STEP SWITCH
	SW8 SW6	SW5	SW3 SW4	POSITION 1
	DWO		SW7	

- Apply 125 VDC (BP-1(+), BP-2(-))
- (3) Step from 1 through 8 and record reading.
- (4) READINGS: = 12.7 + 2.0 VDC (PCR1-3) 11.4 + 2.0 VDC (PCR4)
- If these readings are normal, proceed with Switching test.

Special Note about Step (E-3)

There are two 2K resistors in parallel and in series with the coil. Since the coil resistance is 8600 ohms and the 2 resistors make up another 1000 ohms, that max reading would only be 9600 ohms (9.6K).

Because of these changes in coil resistance values described in step (E-3) are not obtainable. We believe this is due to the test setup, but have no way to validate this. Readings in this step read 19.0VDC to 19.8VDC. It is recommended that we used 19.4VDC as nominal value +-2.0VDC.

C. Wade 3/17/2012

APPROVALS MADE BY J.W. Mar. 21, 68 ISSUED MAR 27 1,58

STEAM TURBINE

SCHENECTADY

DIV OR CONT ON SHEET LOCATION

P24B-AL-4816

273-71

273-138 273-132 RAF.

PRINTS TO

CODE IDENT NO

+

+

**REVISION** 

P24B-AL-4816

+

+

+

TITLE

PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD

CONT ON SHEET SH NO. FIRST MADE FOR 170X337 and 170X325

### SWITCHING TEST (F)

This test will check the operation of the relay contacts.

(1)	DOMN	CENTER	UP	STEP SWITCH
	SW4		SW3	POSITION 1
	SW8		SW5	
			Sw6	
			SW7	

- (2) Apply 24 VDC along with the 125 VDC applied previously.
- (3) step 1 through 8 observe that PI-2 light for all 8 steps. PL-1 should not light.
- (4) SW-7 down
- step 1 through 8 observe PL-1 lights for all 8 steps PL-2 should not light
- (6) Since, in the above tests, the common leads of the contacts were tied together, it is necessary to check adjacent pins of the plug, on the board, for shorts. This is done as follows:
- (7) press PB-1 and step 1 through 8 PL-1 should not light in steps 1 and 5
- press PB-2 and step 1 through 8 PL-1 should not light in steps 2 and 6
- (9) press PB-3 and step 1 through 8 PL-1 should not light in steps 3 and 7
- (10) press PB-4 and step 1 through 8 PL-1 should not light in steps 4 and 8

If arc suppression is included, proceed with test on next page. board under test does not have this feature, skip the arc suppression test and perform the low voltage test.

SCHENECTADY

273-1 Ra

273-7

273-2

273 - 1273-1

MADE BY J.W. ISSUED MAR 2/ APPROVALS STEAM TURBINE

DIV OR \_ DEPT

P24B-AL-4816

LOCATION CONT ON SHEET

FF-803-WA (9-66) PRINTED IN U.S.A

PRINTS 1

GENERAL & ELECTRIC

P2#5-AL-4816

CONT ON SHEET 9 SH NO. 8

PROCESS INSTRUCTIONS
FOR TESTING 125 V RELAY BOARD
FIRST MADE FOR 170X337 and 170X325

REVISION

(G) ARC SUPPRESSION TEST

(1) Readjust voltage to 125 VDC/

(2) N.C. Contacts

Down Center Up Step Sw. 52

<u>Down</u>	<u>Center</u>	<u>Up</u>	Step Sw.	<u>\$2</u>
SWA	SW5	SW3 SW6 SW7 SW8	7	1

NOTE: SW8 cuts in "L" between EP-9 and EP-10

- (3) Pressing and releasing of PB-Swill cause the contacts open and close. Observe scope and note that no spikes of appreciable amplitude exist on contacts associated with the step switch position.

  Record amplitude of highest spike.
- (4) Perform step 3 for step switch position 1 through 8.
- (5) N.O. contacts SW6 down SW5 up set SW2 to position 2
- (6) Perform step 3 for step switch positions 1 through 8.

**APPROVALS** 

FLY FLY

PRINTS

J.W. Kozubal Mar. 21, 68

STEAM TURBINE

SCHENECTADY, NY

DIV OR

p24B-AL-4816

SH NO. 8

**A** 

RE

FF-803-WA (2-69) PRINTED IN U.S.A.

+

+

+

+

1/

LOCATION CONT ON SHEET

CODE IDENT

P24B-AL-4816

CONT ON SHEET 10 TITLE PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD P24B-AL-4816 170X337 and 170X125 10 FIRST MADE FOR SH NO. CONT ON SHEET

(H) VOLTAGE PROFILE TEST

- (1) ADJUST EXTERNAL POWER SUPPLY FOR 70 VDC.
- (2) repeat steps 1 through 5 of "SWITCHING TEST". Relays must show proper operation at this reduced voltage.
- (3) Remove power.

+

+

+

(4) Remove relay board from socket.

TEST COMPLETE

MADE BY KOZUBAL J.W. Mar. MAR 27 1968 ISSUED

APPROVALS STEAM TURBINE

SCHENECTADY

DIV OR \_ DEPT.

P24B-AL-4816

CODE IDENT

273-7

REVISIO

273-2

273-12

<u> 273–13</u>

<u> 273–13</u>

PRINTS 1

RA

LOCATION CONT ON SHEET 10

GENERAL (%) ELECTRIC P24B-AL-4816 CONT ON SHEET 11 sh NO. 10 TITLE PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD P24B-AL-4816 CONT ON SHEET 11 FIRST MADE FOR SH NO. 170X337 and 170X325 **REVISION** TABLE I SCHEMATIC IDENT. TEST AT PLPCR-1 Power Relay 125 V 942D355G1 942D356 Comm. Coils No Contact Protection 125 V Relay Bd. PCR-3 947D398G2 947D379 Comm. Coils No Contact Protection PCR-2 125 V Relay Bd. 947D386G1 947D388 No Comm. Coils With Contact Protection PCR-3 125 V Relay Bd. 947D398G1 948D810 Comm. Coils With Contact Protection 125 V Relay Bd. PCR-3 114D6-57 114D6063 Comm. Coils With Contact Protection PCR-2 125 V Relay Bd. 947D389 947D386G2 No Comm Coils No Contact Protection PCR-4 125V Relay Bd. 141C8324 Comm. Coils With Contact Protection PCR-2 125V Relay Bd. 114D6058 No Comm. Coils With Contact Protection PCR-2 125V Relay Bd. 114D6065 G2 947D389 No Comm. Coils Without Contact Protection

PRINTS

11

MADE BY B. D. Murphy March 25, 69 ISSUED AP

Steam Turbine

Schenectady, N. Y.

APPROVALS

DIV OR \_ DEPT.

10

FF-803-WA (5-68) PRINTED IN U.S.A.

LOCATION CONT ON SHEET

CODE IDENT

11

REVISIC

APR-134 1869

0

310, stora

273-2 273-2 273-1: 273-1:

CONT ON SHEET 12

PROCESS INSTRUCTIONS
P24B-AL-4816 FOR TESTING 125 V RE

SH NO.

11

CONT ON SHEET 12

FOR TESTING 125 V RELAY BOARD FIRST MADE FOR 170X337 and 170X325

TABLE III

Note: A to E PIN NUMBERS

PCR-1

	SSW-1		SW-7 Comm	C to		D to			SSW-3
<u>Pin</u> 10	<u>Pos</u> . 1	<u>Pin</u> 20	<u>Contact</u> SW-7 Comm	<u>Pin</u> 8	Pos 1	<u>Pin</u> 14	<u>PB</u> 1	Pin 7	<u>Pos</u> .
12	2	-+	· · · · · · · · · · · · · · · · · · ·	6	2	15	2	5	2
9	3			1	3	17	3	2	3
37	4			4	4	18	4	3	4
33	5			28	5	34	1	27	5
30	6			22	6	36	2	26	6
29	7			25	7	39	3	23	7
37	8			21	8	41	4	24	8

PCR-2

A to	SSW-1	B to S	W-7 Cc	omm .	C to S	SS <u>W-2</u>	D to	PB	E_to	SSW-3
Pin 10	Pos.	<u>Pin</u>	Conta	ct	Pin	Pos.	<u>Pin</u>	PB	Pin	Pos.
10	1	11	SW-7	Comm	8	1	9	1	7	1
13	2	14	11	11	6	2	15	2	5	2
16	3	21	11	ŧ.	1	3	20	3	3	3
17	4	18	**	11	4	4	19	4	2	4
30	5	31	11	tr	29	5	32	1	28	5
33	6	, 34	11	11	27	6	41	2	26	6
35	7	<b>4</b> 0	*1	.,	25	7	39	3	24	7
36	8	37	"	***	23	8	38	4	22	8

PCR-3

,	A to	SSW-1	B to	SW-7 Comm.	C to	SSW-3	D to	PB	E to	SSW-3
	<u>Pin</u> 10	Pos.	<u>Pin</u>	Contact	Pin 8	Pos.	Pin	PB	<u>Pin</u>	Pos.
	10	1	12	SW-7 Comm	8	1	9	1	7	1
ľ	13	2			6	2	15	2	5	2
	16	3			1	3	20	3	3	3
	17	4			4	4	19	4	2 ===	4
	30	5			29	5	32	1	28	5
	33	6			27	6	41	2	26	6
	35	7			25	7	39	3	24	7
	36	8			23	8	38	4	22	8
j										

APPROVALS

FLT FI PRINTS

J. W. Kozubal March 12,69

STEAM TURBINE DIV OR DEPT.

SCHENECTADY LOCATION

P24B-AL-4816

LOCATION CONT ON SHEET 12 SH NO. 11

FF-803-WA (5-68) PRINTED IN U.S.A.

+

+

ITO

CODE IDENT

GENERAL & ELECTRIC P24B-AL-4816 CONT ON SHEET 13 TITLE PROCESS INSTRUCTIONS P24B-AL-4816 FOR TESTING 125 V RELAY BOARD CONT ON SHEET 13 SH NO. 12 FIRST MADE FOR 170X337 and 170X325 REVISIQ TABLE III Note: A to E PIN NUMBERS

A to	SSW-1	B to S	SW-7 Comm	C to	SSW-2	D to	PB	E to	SSW-3
Pin	Pos.	Pin	Contact	<u>Pin</u>	Pos.	Pin	PB	<u>Pin</u>	Pos.
35.	1	41	SW-7 Comm	7	1	8	1	9	1
33	2	39	11	10	2	11	2	12	2
3.1	3			13	3	14	3	15	3
29	4			16	4	17	4	18	4
27	5			19	5	20	1	21	5
25	6			4	6	5	2	6	6
37	7			1	7	2	3	3	7
	8				8		4		8

273**-**71 273-2 273-12

273-13

<u>273-13</u> R2/

PRINTS 1

12

DIV OR

\_ \_ \_ \_ DEPT.

P24B-AL-4816

13 LOCATION CONT ON SHEET

Steam Turbine

Schenectady, N. Y.

Mar 21.68

CODE IDENT


FF-803-WA (1-70) PRINTED IN U.S.A.

+

+

+

+



GENERAL (%) ELECTRIC P24P-AL-4816 SH NO. CONT ON SHEET TITLE PROCESS INSTRUCTIONS FOR TESTING 125 V RELAY BOARD P24B-AL-4816 FIRST MADE FOR CONT ON SHEET \_\_\_\_ SH NO. 14 170X337 and 170X325 REVISION EHC Manufacturing + Turbine Control Engineering Approved By: P.C. Callan, SUPERVISOR Turbine Control Engineering + + PRINTS 1 DIV OR STEAM TURBINE

SCHENECTADY, NY

\_ DEPT.

J 7

ISSUED

LOCATION CONT ON SHEET

CODE IDENT

SH NO.

Job #									
Serial #					Burn-in Start				
Date					es .				
Data Sheet f	or996D	957G0001	-		Burn-in Stop				
Test Procedu	reP24B-	AL-4816			Technician				
Test			Dec Brown	Boot Burn			Pot Values If applicable		
Procedure Step	Nominal	Lower Limit	Pre-Burn in Results	Post Burn in Results	Upper Limit	CW	CCW	Pass/Fail	
D3-1	>1M ohm	>1M ohm			>1M ohm	-	_		
D3-2	>1M ohm	>1M ohm			>1M ohm	-	_		
D3-3	>1M ohm	>1M ohm			>1M ohm	-	-		
D3-4	>1M ohm	>1M ohm			>1M ohm		-		
D3-5	>1M ohm	>1M ohm			>1M ohm	-	-		
D3-6	>1M ohm	>1M ohm	- 0-		>1M ohm	-	-		
D3-7	>1M ohm	>1M ohm	_		>1M ohm		-		
D3-8	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
D4-1	9.6K ohm	7.6K ohm	_		11.6K ohm	-	-		
D4-2	9.6K ohm	7.6K ohm			11.6K ohm	-	-		
D4-3	9.6K ohm	7.6K ohm			11.6K ohm		-		
D4- <b>4</b>	9.6K ohm	7.6K ohm			11.6K ohm	-	-	<u></u>	
D4-5	9.6K ohm	7.6K ohm			11.6K ohm	-			
D4-6	9.6K ohm	7.6K ohm			11.6K ohm	-	-		
D4-7	9.6K ohm	7.6K ohm			11.6K ohm	-			
D4-8	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
								. <del></del> -	
Special Note	: D4-1 thru (	D4-7, resistand	es are not attaina	ble due to to cha	nge in test circu	ıit. Value	es will be		
around 9600									
								<u></u>	

996D9 P24B-/	957G0001 AL-4816			Burn-in Start			
996D9 P24B-/	957G0001 AL-4816			_			
P24B-/	AL-4816						
ominal				Burn-in Stop			
	1		_	Technician			
אייטר	Lower Limit	Pre-Burn in Results	Post Burn in Results	Upper Limit	Pot V		Pass/Fail
7.4VUC	17.4VDC			21.4VDC	-	-	
9.4VDC	17.4VDC			21.4VDC	_		
9.4VDC	17.4VDC			21.4VDC	-	-	
9.4VDC	17.4VDC			21.4VDC		-	
9.4VDC	17.4VDC			21.4VDC			
9.4VDC	17.4VDC			21.4VDC	-	-	
9.4VDC	17.4VDC			21.4VDC		-	
N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
	-			-		_	
	_			-	-	-	
-	-			-	-	-	
				-	-	-	
				-	-	-	
<u>.</u> ]				-	-	-	
<u>.</u>				-	-	-	
-	_			-	-	-	
-1 thru E	4-7, voltages a	re not attainable	due to to change	s in test circuit.	Values v	vill be	
+-2VDC.							
	9.4VDC 9.4VDC 9.4VDC 9.4VDC 9.4VDC 9.4VDC 1.4VDC 1.4VDC 1.4VDC 1.4VDC	9.4VDC 17.4VDC	9.4VDC 17.4VDC 9.4VDC 9.4VDC 17.4VDC 9.4VDC 9.4V	9.4VDC 17.4VDC 9.4VDC 9.4VDC 17.4VDC 9.4VDC 9.4	0.4VDC       17.4VDC       21.4VDC         N/A       N/A       N/A         N/A       N/A       N/A         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -	17.4VDC	17.4VDC

Job #	-							
Serial #					Burn-in Start			<del></del> -
Date								
Data Sheet f	or996D	957G0003			Burn-in Stop			
Test Procedu	reP24B-	AL-4816		<u> </u>	Technician			
Test Procedure			Pre-Burn	Post Burn		Pot V If appl	alues icable	
Step	Nominal	Lower Limit	in Results	in Results	Upper Limit	cw	ccw	Pass/Fail
E3-1	19.4VDC	17.4VDC			21.4VDC		-	
E3-2	19.4VDC	17.4VDC			21.4VDC		-	
E3-3	19.4VDC	17.4VDC			21.4VDC	-	-	
E3-4	19.4VDC	17.4VDC			21.4VDC	-		
E3-5	19.4VDC	17.4VDC			21.4VDC	-		
E3-6	19.4VDC	17.4VDC			21.4VDC	-	-	
E3-7	19.4VDC	17.4VDC			21.4VDC	-		
E3-8	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
F1	-		-	-	-		-	
F2	-	-	-	-	-	-	-	
F3	-	-			-	-	-	
F4	-	-	<u>-</u>		-		-	
F5	-	-	-	-	-	-	-	
F6	-	<u>-</u>	-	-	-			
F7		-	-	-	-	-	-	
Special Note	· F3-1 thru F	:3-7. voltages a	are not attainable	due to to changes	in test circuit.	Values v	l will be	
around 19.4								
				<u> </u>		_		
				<u>-</u>		·		

Job #									
Serial #					Burn-in Start				
Date					-				
Data Sheet f	or996D	957G0003			Burn-in Stop				
Test Procedu	ıreP24B-	AL-4816			Technician				
Test Procedure Step	Nominal	Lower Limit	Pre-Burn in Results	Post Burn in Results	Upper Limit		Pot Values If applicable CW CCW Pass/F		
D3-1	1M ohm	1M ohm			1M ohm	-			
D4-1	9.6K ohm	7.6K ohm			11.6K ohm	-	-		
D4-2	9.6K ohm	7.6K ohm			11.6K ohm	-	-		
D4-3	9.6K ohm	7.6K ohm			11.6K ohm				
D4-4	9.6K ohm	7.6K ohm			11.6K ohm	-	-		
D4-5	9.6K ohm	7.6K ohm			11.6K ohm	-	-		
D4-6	9.6K ohm	7.6K ohm			11.6K ohm	-	_		
D4-7	9.6K ohm	7.6K ohm			11.6K ohm				
D4-8	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
D5-1	<50 ohm	<50 ohm		_	<50 ohm	-			
D5-2	<50 ohm	<50 ohm			<50 ohm				
D5-3	<50 ohm	<50 ohm			<50 ohm				
D5-4	<50 ohm	<50 ohm			<50 ohm	-			
D5-5	<50 ohm	<50 ohm			<50 ohm		-		
D5-6	<50 ohm	<50 ohm			<50 ohm_	-	-		
D5-7	<50 ohm	<50 ohm			<50 ohm				
D5-8	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
Special Note	: D4-1 thru (	D4-7, resistanc	es are not attaina	ble due to to chai	nge in test circu	iit. Value	s will be	1	
around 9600	K ohms.		_			_	<u> </u>		
						_			
					_				