


g GE Industrial Systems	Test and Operating Procedure	
	DATE : 06/07/02	PAGE 1 OF 5
DISTRICT MGR:		QUALITY REP: 
TITLE: Power Supply Module Test Procedure		PROCEDURE: LOU-GE-DS3820PSSB-B

1. INTRODUCTORY DESCRIPTION

- A. This procedure establishes the methods for testing a **DS3820PSSB Power Supply**.
- B. Environmental ranges: 70 +/- 10 Deg. F. with 20-75% R.H.
- C. Unit warm-up/stabilization period requirement: None.
- D. Personnel using this procedure are expected to have a high degree of confidence and expertise in related testing and calibration procedures.
- E. Procedures not explained here are considered to be understood as common practice.

2. TEST EQUIPMENT VERIFICATION

- A. Verify the accuracy of the standard(s) used in the repair/calibration process by evidence of recent calibration labeling affixed to the test equipment.
- B. All measurement standards used in this procedure shall be traceable to the NATIONAL INSTITUTE of STANDARDS and TECHNOLOGY (N.I.S.T.) and shall have the accuracy, stability, range and resolution required for the intended use.
- C. Unless otherwise specified, the collective uncertainty of the Measurement Standard(s) shall not exceed twenty five percent of the acceptable tolerance for each characteristic being calibrated.
- D. All deviations shall be documented.

3. EQUIPMENT CLEANING

- A. All equipment clean will be performed as instructed in the GEES SOP Sec. 14.0



4. EQUIPMENT INSPECTION

- A. The following criteria should be used as a guideline or basis for the inspection process of the this unit:
 - 1. Wires broken or cracked.
 - 2. Terminal strips / connectors broken or cracked.
 - 3. Loose wires.
 - 4. Components visually damaged.
 - 5. Capacitors leaking.
 - 6. Solder joint, cold.
 - 7. Circuit board discolored or burned.
 - 8. Printed wire runs burned or damaged.

g GE Industrial Systems	Test and Operating Procedure	
	DATE : 06/07/02	PAGE 2 OF 5
DISTRICT MGR:		QUALITY REP:
		<i>Robert D. Dull</i>
TITLE: Power Supply Module Test Procedure		PROCEDURE: LOU-GE-DS3820PSSB-B

5. REVISION HISTORY

Revision	Date	Initials	Reason for Revision
A	11/08/96	JDS	Initial Procedure – After Verification
B	06/07/02	RKD	Added section 5 & 6, Changed procedure number
C			
D			
E			
F			
G			
H			
I			
J			
K			

 GE Industrial Systems	Test and Operating Procedure	
	DATE : 06/07/02	PAGE 3 OF 5
DISTRICT MGR: _____ QUALITY REP: 		
TITLE: Power Supply Module Test Procedure		PROCEDURE: LOU-GE-DS3820PSSB-B

6. REFERENCE DOCUMENTATION

- Reference: GEK
- Factory Procedure #

7. THEORY OF OPERATION

Refer to DS3820PSSB documentation for theory of operation.

8. TEST EQUIPMENT TO BE USED

DS3820PSSB Transformer Test Assembly

Digital Multimeter



Variable Solid State Load (Transistor Devices Inc. or Equivalent)

9. FINAL TEST AND OPERATION PROCESS

- Jumper PCOM to DCOM
- Plug ribbon cable from test fixture into JA and Molex cable into JE.
- Plug variable load assembly into JC. Verify all loads are at zero.
- Verify the following jumpers:

Card	Jumper	Setting
DS3800DPSS	J1	STD
DS3800NPSY	J1	REM
“	J2	REM

- Apply Power to Variable load and UUT

 GE Industrial Systems	Test and Operating Procedure	
	DATE : 06/07/02	PAGE 4 OF 5
DISTRICT MGR:		QUALITY REP:
		
TITLE: Power Supply Module Test Procedure		PROCEDURE: LOU-GE-DS3820PSSB-B

- Verify the following measurements:

- Lead	+ Lead	Reading	Tolerance	Adjustment Pot
TP2	TP1	+5V DC	.1 V	R3
TP2	TP3	-15V DC	.3 V	R1
TP2	TP4	+15V DC	.3 V	R2
JC8	JC12	+28V DC	27 TO 33 VDC	none

- Verify that the PS OK LED is on.
- Verify with multimeter that JH24 to JH26 measures 0 ohms

Load UUT outputs per the following:

Output	Current	Output	Current
+5V	9.5 A	-15V	.45 A
+15V	.45 A	+28V	.40 A

- Reverify that all voltages are within tolerance while under load.

- Lead	+ Lead	Reading	Tolerance	Adjustment Pot
TP2	TP1	+5V DC	.1 V	R3
TP2	TP3	-15V DC	.3 V	R1
TP2	TP4	+15V DC	.3 V	R2
JC8	JC12	+28V DC	.56 V	none

- If unit maintains outputs for at least 10 minutes the unit passes.

g GE Industrial Systems	Test and Operating Procedure	
	DATE : 06/07/02	PAGE 5 OF 5
DISTRICT MGR:		QUALITY REP:
		<i>Robert D. Dull</i>
TITLE: Power Supply Module Test Procedure		PROCEDURE: LOU-GE-DS3820PSSB-B

10. SPECIAL INFORMATION

TEST WRITTEN BY: David Smith

DATE: 11/08/96

TEST VERIFIED BY: _____

DATE: _____