

1. <u>INTRODUCTORY DESCRIPTION</u>

A. This procedure establishes the methods for testing: 118D1302G0001 thru G0006 Steamline Resonance Compensator Circuit Card.

B. Environmental ranges: 70 +/- 10 Deg. F. with 20-75% R.H.

C. Unit warm-up/stabilization period requirement: 5 minutes

- D. Personnel using this procedure are expected to have a high degree of confidence and expertise in related testing and calibration procedures.
- E. Procedures not explained here are considered to be understood as common practice.

2. TEST EQUIPMENT VERIFICATION

- A. Verify the accuracy of the standard(s) used in the repair/calibration process by evidence of recent calibration labeling affixed to the test equipment.
- B. All measurement standards used in this procedure shall be traceable to the NATIONAL INSTITUTE of STANDARDS and TECHNOLOGY (N.I.S.T.) and shall have the accuracy, stability, range and resolution required for the intended use.
- C. Unless otherwise specified, the collective uncertainty of the Measurement Standard(s) shall not exceed twenty five percent of the acceptable tolerance for each characteristic being calibrated.
- D. All deviations shall be documented.

3. EQUIPMENT CLEANING

All equipment clean will be performed as instructed in the GEES SOP Sec. 14.0

4. EQUIPMENT INSPECTION

- A. The following criteria should be used as a guideline or basis for the inspection process of this unit:
 - 1. Wires broken or cracked.
 - 2. Terminal strips / connectors broken or cracked.
 - 3. Loose wires.
 - 4. Components visually damaged.
 - 5. Capacitors leaking.
 - 6. Solder joint, cold.
 - 7. Circuit board discolored or burned.
 - 8. Printed wire runs burned or damaged.

Test and Operating Procedure

GE Industrial Systems

Rober Durll

DATE: 10/17/1996 PAGE 2 OF 11

QUALITY REP:

TITLE: PROCEDURE:

Steam Line Resonance Compensator Card Test LOU- GED-118D1302-D

5. <u>REVISION HISTORY</u>

Revision	Date	Reason for Revision
A	10/17/96	Initial Procedure – After Verification
В	3/24/99	Added information for G5 and G6 cards. [BKP]
C	06/10/02	Changed procedure number to match standard.
D	3/23/2012	Updated test with line numbers and changed db to voltage values in steps, 9.33, 9.39, 9.43, 9.45, 9.47, 9.49, 9.51.
E		
\mathbf{F}		
G		
H		

6. REFERENCE DOCUMENTATION

• Reference: P3K-AL-0231

7. THEORY OF OPERATION

Function

The Steamline Resonance Compensator Circuit Card (SLRC) accepts a signal from a Pressure Amplifier Circuit Card in the BWR Pressure Control system. This signal is the total steam flow demand signal. The SLRC card is a low pass filter with minimal phase shift. The DC unity gain.

Operation

An active notch filter and lag circuit are combined to give frequency response characteristics as shown on the SLRC schematic drawing. The notch depth, width, center frequency and lag time constant are adjustable via 10 turn panel mounted dial potentiometers.

Test and Operating Procedure

g

GE Industrial Systems

DATE: 10/17/1996

PAGE 3 OF 11

QUALITY REP:

Rober Dwall

TITLE: PROCEDURE:

Steam Line Resonance Compensator Card Test LOU- GED-118D1302-D

8. TEST EQUIPMENT TO BE USED

→ +30 Volt Power Supply

- ➤ -22 Volt Power Supply
- > 0-20 Volt variable supply
- \triangleright 1K Ω load resistor
- Misc Jumpers
- ➤ Sine Wave Function Generator
- > Dual channel chart recorder
- Digital Multimeter
- Oscilloscope
- Fixture # H033641

9. FINAL TEST AND OPERATION PROCESS

- **9.1** The dual ganged potentiometers (R35-A, R35-B) and (R36-A, R36-B) must be checked for tracking between the wipers. Turn pots all the way CCW. The wipers should read within 0.1% a start of CW travel (after dead zone) and be within 1% at full CW travel (before dead zone). Reposition A with respect to B if necessary.
- **9.2** Mechanically position the four panel mounted pots with respect to the dials so that the zero dial position coincides with beginning of active portion of potentiometer travel.
- 9.3 Apply +30V, -22V, and ground to pins 17, 21, and 19 respectively.
- **9.4** Connect a $1K\Omega$ resistor load between pin 29 and ground.
- **9.5** Check TP1 and TP2 for +15.7 and -15.7 volts respectively.
- **9.6** Adjust T_0 potentiometer to dial setting 5.0.
- **9.7** Adjust VR4 approximately 4 turns from full CCW end.

GE Industrial Systems

Test and Operating Procedure

DATE: 10/17/1996

PAGE 4 OF 11

QUALITY REP:

Rober Dwell

TITLE:

Steam Line Resonance Compensator Card Test

PROCEDURE: LOU- GED-118D1302-D

- **9.8** Zero adjust the four operational amplifier amplifiers to within plus or minus one millivolt as follows. Place jumpers across C7, C13, and C16.
- **9.9** Connect pin 10 to ground.
- **9.10** Adjust VR1 and VR50 for 0.00 volts at TP4.
- **9.11** Adjust VR52 for 0.00 volts at TP6.
- **9.12** Adjust VR3 and VR51 for 0.00 volts at TP5
- **9.13** Adjust VR6 and VR53 for 0.00 volts at TP10.
- **9.14** Remove jumpers from C7, C13, and C16
- **9.15** After the voltage at TP6 stabilizes adjust VR52 for 0.00 volts at TP5. Check TP10 for 0.00 volts ± 2 mV.
- **9.16** Remove ground from pin 10 and apply +0.500 volts.
- **9.17** Adjust VR5 for +0.500 volts at TP10.
- **9.18** Apply -0.500 volts at pin 10.
- **9.19** Check TP10 for -0.500 volts.
- **9.20** Increase pin 10 to $-2.00 \text{ volts } \pm 10 \text{mV}$.
- **9.21** Check TP10 for $-2.00 \text{ volts } \pm 10 \text{mV}$.
- **9.22** Apply +2.00 volts at pin 10.
- **9.23** Check TP10 for $+2.00 \text{ volts } \pm 10 \text{mV}$.
- **9.24** Remove voltage source from pin 10.
- **9.25** Disconnect wire to wiper of R38, TR2 pot.

GE Industrial Systems

Test and Operating Procedure

DATE: 10/17/1996

PAGE 5 OF 11

QUALITY REP:

Rober Dwall

TITLE: PROCEDURE:

Steam Line Resonance Compensator Card Test LOU- GED-118D1302-D

9.26 Adjust panel mounted dials as follows:

<u>Potentiometer</u>	<u>Dial Setting</u>
C1/C2	0.00
C2	1.78
T_0	3.88
T_{R2}	1.55

- **9.27** Connect a Sine wave function generator to pin 10.
- **9.28** Monitor pins 10 and 29 with two channels of a scope
- **9.29** Adjust the function generator as follows

Group	Function Generator	Voltage
G1 - G5	0.8V P-P @ 1.5 Hz	.2828 RMS
G6	0.8V P-P @ 15.0 Hz	.2828 RMS

- **9.30** Adjust VR4 for minimum amplitude at pin 29. {DC Off-Set of wave form}
- **9.31** Adjust VR2 to further minimize the amplitude at pin 29.
- **9.32** Reiterate adjustment of VR4 and VR2 for minimum possible amplitude at pin 29. { DC Off-Set of wave form}
- **9.33** Adjust C1/C2 dial to 2.00 setting.
- **9.34** Further adjustment (if necessary), C1/C2 dial to obtain 160mV P-P down from zero at pin 29.
- **9.35** Mechanically reposition C1/C2 dial (if necessary) to read 2.00 with potentiometer in position established in step 9.34.
- **9.36** Reconnect R38 wiper.

Test and Operating Procedure

g

GE Industrial Systems

DATE: 10/17/1996

PAGE 6 OF 11

QUALITY REP:

Rober Durll

TITLE: PROCEDURE:

Steam Line Resonance Compensator Card Test LOU- GED-118D1302-D

9.37 Adjust the function generator as follows

Group	Function Generator	
G1 - G4	1.5 Hz	
G5	15.0 Hz	
G6	150 Hz	

- **9.38** Adjust C1/C2 dial to 10.0
- **9.39** Further adjustment (if necessary), T_{R2} dial to obtain 250mV P-P down from zero at pin 29.
- **9.40** Mechanically reposition T_{R2} dial (if necessary) to read 1.55 with potentiometer in position established in step 9.39. Note: When changing frequencies, readjust for .800 mV P-P.
- **9.41** Adjust C1/C2 dial to 2.00
- **9.42** Adjust the function generator as follows

Group	Function Generator	
G1 - G4	0.55 Hz	
G5	0.86 Hz	
G6	8.65 Hz	

- **9.43** Verify pin 29 amplitude should be between 360 and 450 mV P-P.
- **9.44** Adjust the function generator as follows

Group	Function Generator	
G1 - G4	0.9 Hz	
G5	1.25 Hz	
G6	12.5 Hz	

9.45 Verify pin 29 amplitude should be between 180 and 230 mV P-P

Test and Operating Procedure

GE Industrial Systems

DATE: 10/17/1996

PAGE 7 OF 11

QUALITY REP:

Rober Dunll

TITLE:

Steam Line Resonance Compensator Card Test

PROCEDURE:

LOU- GED-118D1302-D

9.46 Adjust the function generator as follows

Group	Function Generator	
G1 - G5	1.5 Hz	
G6	15.0 Hz	

9.47 Verify pin 29 amplitude should be as follows

Group	Amplitude - Min	Amplitude - Max
G1 - G4	0.04 V P-P	0.06 V P-P
G5 - G6	0.14 V P-P	0.17 V P-P

9.48 Adjust the function generator as follows

Group	Function Generator	
G1 - G5	3 Hz	
G6	30 Hz	

9.49 Verify pin 29 amplitude should be as follows

Group	Amplitude - Min	Amplitude - Max
G1 - G4	0.07 V P-P	0.09 V P-P
G5 - G6	0.37 V P-P	0.47 V P-P

Test and Operating Procedure

GE Industrial Systems

DATE: 10/17/1996

PAGE 8 OF 11

QUALITY REP:

Rober Dwell

TITLE:

Steam Line Resonance Compensator Card Test

PROCEDURE: LOU- GED-118D1302-D

9.50 Adjust the function generator as follows

Group	Function Generator	
G1 - G4	10 Hz	
G5	15 Hz	
G6	100 Hz	

9.51 Verify pin 29 amplitude should be as follows

Group	Amplitude - Min	Amplitude - Max
G1 - G4	0.03 V P-P	0.05 V P-P
G5 - G6	0.23 V P-P	0.28 V P-P

9.52 Remove 1K load resistor from pin 29 and disconnect all test equipment.

g	Test and Operating Procedure					
GE Industrial Systems						
	DATE: 10/17/1996	PAGE 9 OF 11				
QUALITY REP: Rober Dunll						
TITLE:	PROCEI	_				
Steam Line Resonance Compensator Compensat	ard Test LOU- GE	LOU- GED-118D1302-D				

10. SPECIAL INFORMATION

10.1 Data sheets for G0004 and G0005 cards are attached to this instruction.

Job #								
Serial #	erial #				Burn-in Start			
Date								
Data Sheet for118D1302G0003				Burn-in Stop				
Test ProcedureLOU-GED-118D1302-D				Technician_				
Test						Pot Values		
Procedure	Name	Lower	Pre-Burn	Post Burn		If applicable		D/E-:I
Step	Nominal	Limit	in Results	in Results	Upper Limit	CW	CCW	Pass/Fail
R35A		0.1%						
		ccw						
R35B		0.1%						
B054		CCW						
R36A		0.1%						
R36B		0.1%						
9.5A	+15.7V	+14.915V			+16.485V			
9.5B	-15.7V	-14.915V			-16.485V			
9.15	0.00V							
9.19	-0.500V							
9.21	-2.00V	-1.990V			-2.010V			
9.23	+2.00V	+1.990V			+2.010V			
9.43	.40 Vpp	.36 Vpp			.45 Vpp			
9.45	.20 Vpp	.18 Vpp			.23 Vpp			
9.47	.05 Vpp	.04 Vpp			.06 Vpp			
9.49	.08 Vpp	.07 Vpp			.09 Vpp			
9.51	.04 Vpp	.03 Vpp			.05 Vpp			
VR5					1			
VR1 @ TP4								
VR50 @ TP4								
VR52 @ TP6								
VR3 @ TP5								
VR51 @ TP5								
VR6 @ TP10								
VR53 @ TP10								
Pot 2								
Pot 4		l		l	1 1		l	

g	Test and Operating Procedure					
GE Industrial Systems	DATE: 10/17/1996	PAGE 10 OF 11				
QUALITY REP: Robert Durill						
TITLE:	PROCE	DURE:				
Steam Line Resonance Compensator Ca	ard Test LOU- G	ED-118D1302-D				

Job#								
Job # Serial #				Burn-in Start				
Date								
Data Sheet for118D1302G0005				Burn-in Stop				
Test Procedure	eLOU-GE	D-118D1302	2-D		Technician_			
Test						Pot Values		
Procedure		Lower	Pre-Burn	Post Burn		If applicable		
Step	Nominal	Limit	in Results	in Results	Upper Limit	CW	ccw	Pass/Fail
		CCW						
R35A		0.1%						
Daen		0.1%						
R35B		CCW						
R36A		0.1%						
113071		CCW						
R36B		0.1%						
9.5A	+15.7V	+14.915V			+16.485V			
9.5B	-15.7V	-14.915V			-16.485V			
9.15	0.00V							
9.19	-0.500V							
9.21	-2.00V	-1.990V			-2.010V			
9.23	+2.00V	+1.990V			+2.010V			
9.43	.40 Vpp	.36 Vpp			.45 Vpp			
9.45	.20 Vpp	.18 Vpp			.23 Vpp			
9.47	.155 Vpp	.14 Vpp			.17 Vpp			
9.49	.42 Vpp	.37 Vpp			.47 Vpp			
9.51	.255 Vpp	.23 Vpp			.28 Vpp			
VR5								
VR1 @ TP4								
VR50 @ TP4								
VR52 @ TP6								
VR3 @ TP5								
VR51 @ TP5								
VR6 @ TP10								
VR53 @ TP10								
Pot 2								
Pot 4					1			

Test and Operating Procedure

GE Industrial Systems

DATE: 10/17/1996

PAGE 11 OF 11

OUALITY REP:

PROCEDURE:

Steam Line Resonance Compensator Card Test

PROCEDURE:

LOU- GED-118D1302-D

TEST WRITTEN BY: GE Steam Turbine DATE: 05/23/76

Procedure # P3K-AL-0231

TEST COPIED BY: Robert Duvall DATE: 10/17/96

TEST VERIFIED BY: G. Chandler DATE: 3/23/2012