ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	1 / 18

ACS/ACH550-01 R5

Test Specification for ABB drive service workshop

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	2 / 18

CONTENT

ACS/ACH550-01/ R5	Error! Bookmark not defined.
CONTENT	2
1 General	3
1.1 Version history	3
1.2 General	3
2 Visual inspection	4
3 Basic measurement with multimeter	7
4 Reassembling the unit	10
5 Insulation resistance measurement	10
6 Testing the I/O-board and control panel	11
7 Testing the main circuit	14
8 Final steps	16
ACS/ACH550 INSPECTION REPORT	

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	3 / 18

1 General

1.1 Version history

Version	Comments	Author	Date
Draft 1	First version	Kimmo Hirvonen	7.2.2006
REV. A	Several updates		

WARNING! All electrical installation and maintenance work on the ACx550 should be carried out by qualified electricians.

Do not attempt any work on a powered ACx550. After switching off the mains, always allow the intermediate circuit capacitors 5 minutes to discharge before working on the frequency converter, the motor or the motor cable. The voltage between each input terminal (U1, V1, W1) and earth must be measured with a multimeter (impedance at least $1M\Omega$) to ensure that the frequency converter is discharged before beginning work.

All insulation tests must be carried out with the ACx550 disconnected from the cabling.

The ACx550 motor cable terminals are at a dangerously high voltage when input power is applied, regardless of motor operation. No work on the motor cable should be attempted with mains power applied.

There can be dangerous voltage inside the ACx550 from external control circuits when the ACx550 input power is shut off. No work on the control cables should be attempted when power is applied to the frequency converter or to the external control circuits. Exercise appropriate care when working with the unit.

ESD (Electro Static Discharge) The printed circuit boards contain integrated circuits that are extremely sensitive to electrostatic discharge. Exercise appropriate care when working on the unit to avoid permanent damage to the circuits. Do not touch the boards unnecessarily.

WARNING! Only qualified electricians are allowed to carry out work described in this instruction. Before working with the ACx550 read carefully the Safety Instruction on the ACx550 User's Manual. Ignoring the safety instructions can cause injury or death.

1.2 General

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	4 / 18

The purpose of this document is to specify how whole ACx550 frequency converter must be tested. The testing includes following steps:

- Visual inspection
- Basic measurement with multimeter
- Insulation resistance test
- Testing the I/O-board, control panel
- Electrical testing
 - Testing without load
 - Testing with load

Required tools and measuring equipments for the testing:

- Crosshead screwdriver
- Insulation resistance tester (megger)
- Multimeter
- Ammeters
- Torxhead keys
- Torque wrench


The test motor for the drive must be selected according to ACx550 User's manual dimensioning instructions. The test motor rated current must be enough high to take out rated continuous RMS current (I_{2N}) from the frequency converter. There must be another load motor on connected to the test motor shaft, which can be used as load machine. There will be needed also another drive for controlling the load motor. The load motor must be higher or equal size with the test motor. It is also possible to use 50 % smaller load motor (motor current is only 50% of the I_{2N}), but in that case the loading time is double.

2 Visual inspection

First step of the test procedure is the visual inspection of the main circuit. The purpose of the test is to check that all the critical electrical connections are made properly, to check that the unit is clean and make sure that the boards are not corroded that there are no mechanical damages on the unit. In order to make the visual inspection, the plastic top cover and skeleton of the frequency converter must be taken off. Below figure 2.1 presents how to remove the top cover and skeleton after removing the control panel.

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	5 / 18







b) Open torx screws



d) Lift the cover and remove ribbon cables from xINT-board.



e) Remove the xMIO-board from skeleton. Note: Loose the raising screw and notice guide pins (red arrows) when removing or placing xMIO-board.

Figure 2.1 Remove the front cover and skeleton.

STEP 1	Visual inspection of heat sink
Performance	Check the heat sink of the frequency converter is clean
Pass criterion	
Meaning of the test	Heat sink is clean.
STEP 2	Visual inspection of fans
Performance	Check the fans are installed properly
Pass criterion	
Meaning of the test	Fans are properly installed.

Only if the Rectifier Bridge and/or IGBT module have been replaced check this step 3

STEP 3	Check the tightening of power semiconductor module
Performance	If the IGBT module or rectifier bridge module have changed by a new

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	6 / 18

	one.
	Check that the power semiconductor modules are tightened properly to
	the right torque. (See figure 2.1)
Pass criterion	Rectifier bridge: 1,5/4,5 Nm (initial/final),
	IGBT module: 1,5/3 Nm (initial/final)
Meaning of the test	Power semiconductor modules are tightened properly.




Figure 2.1 Frame R5 thyristor diode rectifier module and IGBT module.

STEP 4	Check circuit boards and main circuit connections
Performance	In visual inspection special attention must be paid to all electrical connections are properly fastened.
	Check that all mounting screws are tight
	Check DC-capacitors and AC-choke connections
	Current transducers (CT) connections
	Check circuit boards connections (xINT-, xMIO- and xRFC-board)
	Check AC and DC bus bars connections
	Inspect the condition of the power modules gate wiring
	(See figure 2.2)
Pass criterion	
Meaning of the test	Connections are properly made

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltag	ge Drives	Test instruction for ACS/ACH550-01 R5		
Date 2006-Oct-12	Author	Checked / Approved Kimmo Hirvonen	Revision A	Page 7 / 18







c)

Figure 2.2 Visual inspections for R5. Screws that must be inspected are marked with blue, red and green circles (See picture a). Check gate wiring of the power modules and DC bus bars screws (See figure b). Check also tightness of the AC-choke wiring, xRFC-board and AC cables mounting marked with yellow circles (See picture c).

3 Basic measurement with multimeter

Some basic functionality must be tested with multimeter before putting any power to the drive. These measurements are:

- Input bridge measurement
- Motor IGBT freewheeling diode measurement
- IGBT gate measurement
- Charging resistor measurement

Before starting any individual thyristor/diode module measurement described below the broken component can be located by measuring between the (+) busbar and input phases and similarly (-) busbar and input phases if an input phase is short-circuited. Similarly broken IGBT module can be located by measuring between the (+) busbar and output phases and (-) busbar and output phases.

ABB Discrete Automation a	nd Motion ABB drive service workshop		
BU Low Voltage Drives	Test instruction for ACS/ACH550-01	R5	
Date Author 2006-Oct-12	Checked / Approved Kimmo Hirvonen	Revision A	Page 8 / 18

Check also thyristor/diode and IGBT modules visually. Sometimes the thyristor/diode or IGBT module may be broken or burned by for example an arc caused by a short-circuit inside the module.

Undo also gate control wiring before measuring.

In below tables infinite value is OL = Over limit.

Note that the values shown by the multimeter depends on its brand and type. Different multimeters show slightly different values when measuring semiconductors.

If forward voltage of some of the diodes is different from the others, the diode is most probably broken.

STEP 1	Input bridge (thyris	tor/diode module) me	easurement
Performance	Measure with multimeter that the input bridge is OK. (See figure 3.1)		
Pass criterion	When using diode measurement of the multimeter, you get following values:		
	+ prope	- prope	display
	1	2	OL
	1	4	OL
	3	1	~0,4 V
	+ prope	- prope	display
	1	3	OL
	2	1	OL
	4	1	OL
	2	4	~0 V
	Measurement in the re-	sistance mode:	
	+ prope	- prope	display
	4	~16 ohm	
Meaning of the test	Input bridge is OK		




Figure 3.1 Circuit diagram of the thyristor/diode module.

STEP 2	Motor IGBT freewheeling diode measurement
Performance	Measure with multimeter that the output bridge freewheeling diodes are

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	9 / 18

	OK. (See figure 3.2)		
Pass criterion	When using diode measurement of the multimeter, you get following values:		
	+ prope	- prope	display
	C1	C2E1	OL
	C2E1	E2	OL
	C2E1	C1	~0,3 V
	E2	C2E1	~0,3 V
Meaning of the test	IGBT freewheeling diod	es are OK	
STEP 3	IGBT gate measurer	nent	
Performance	Measure with multimeter the condition of the IGBT gates. The condition of the IGBT gates can be measured, when the multimeter is turned to the Ohm measurement. (See figure 3.2) NOTE! The IGBT gate — emitter resistance measurement does not automatically mean that the IGBT module is OK. If the IGBT gate — emitter only leaks slightly, it is possible that this measurement shows		
	correct value even thou	gh the module is broken	
Dana suitavias	Resistance values for the IGBT gate – emitter measurement:		
Pass criterion	nesistance values for ti	ie iodi gale – emiller n	leasurement.
Pass criterion	+ prope	- prope	display
Pass criterion			
Pass criterion	+ prope	- prope	display
Pass criterion	+ prope G1	- prope C2E1	display OL




Figure 3.2 Frame R5 IGBT-module's connectors.

STEP 4	Charging resistor measurement
Performance	The condition of the charging resistor can be measured, when the multimeter is turned to the Ohm measurement. There is one 12 Ω or two parallel connected 25 Ω resistors in R5.
Pass criterion	Resistance value for the charging resistors measurement:
	R_{37} (12 Ω) or two parallel resistors R_{39} (25 Ω) and R_{37} (25 Ω). Parallel resistance value ~12,5 Ω

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltag	ge Drives	Test instruction for ACS/ACH550-01 R5		
Date 2006-Oct-12	Author	Checked / Approved Kimmo Hirvonen	Revision A	Page 10 / 18

Meaning of the test	Charging resistors are OK

4 Reassembling the unit

After the visual inspection and multimeter measurements the unit must be carefully reassembled before the electrical testing. Double check that all the screws are tightened and all the cables are fastened properly.

5 Insulation resistance measurement

The insulation resistance of the unit must be measured between the main circuit and the unit frame. Before the insulation resistance measurement, all supply, DC and output terminals (input, output, DC bus) must be connected together. Filter board grounding screws (F1, F2 and V) must be removed before the test. If this is not done, the varistors of the unit might explode and the leakage current is too big. Connect the insulation resistance measurement device between the main circuit and the frame of the unit and apply voltage (500 VDC) for 3 seconds. The insulation resistance and the used voltage must be according to the table below.

STEP 1	Insulation resistance test of the main circuit
Performance	Before the test connect all supply, DC and output terminals together. Also filter board grounding screws (F1, F2 and V) must be removed. See figure 5.1. Measure the insulation resistance between the main circuit and frame of the unit. (500 VDC, 3 s)
	After the insulation resistance test connect grounding screws back to the unit.
Pass criterion	Insulation resistance R1> 10 $M\Omega$
Meaning of the test	Insulation is OK




Figure 5.1 Grounding screws F1, F2 and V.

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltag	ge Drives	Test instruction for ACS/ACH550-01 R5		
Date 0.1.40	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	A	11 / 18

6 Testing the I/O-board and control panel

Before I/O-board testing connect supply cables to the U1, V1 and W1 connectors of the frequency converter. Make sure that there are no motor cables and brake resistor cables connected.

STEP 1	Connection of supply voltage
Performance	Connect mains supply and grounding to the frequency converter
	U1-V1-W1 and ground (230VAC or 480VAC)
	Measure the supply voltages
Pass criterion	
Meaning of the test	Supply voltage is correct
STEP 2	DC circuit
Performance	Read inverter measurement of DC-bus voltage (parameter 0107) and
	compare with measured DC-bus voltage.
Pass criterion	DC-voltages are the same within +/- 5 %
Meaning of the test	DC circuit is OK
STEP 3	Supply voltages for electronics
Performance	Measure +24 V and +10 V from I/O-terminal:
	_
	Between:
	X1:10 (24V) and X1:11 (GND),
	X1:4 (10V) and X1:3 (AGND) ~24 VDC and ~10 VDC
Pass criterion	
Meaning of the test	Electronics has supply voltages
OTED 4	Bull and the state of the state
STEP 4	Back up copy of the customer's parameter settings
Performance	Take parameters back up copy of the customer's parameter settings.
Pass criterion	
Meaning of the test	Parameters back up copy from the frequency converter.
STEP 5	Frequency converter software and drive rating
Performance	Read frequency converters' software. Compare it to database values.
	Load current software if needed.
Pass criterion	SW and drive rating must be correct
Meaning of the test	SW and drive rating is correct
CTED C	Obselvend along the foult law of the delice
STEP 6	Check and clear the fault log of the drive
Performance	Check and note down the fault log of the drive.
	T 1 6 1011
	To clear fault history:
	Using control panel in Parameters mode, select parameter 0401

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltag	ge Drives	Test instruction for ACS/ACH550-01 R5		
Date 2006-Oct-12	Author	Checked / Approved Kimmo Hirvonen	Revision A	Page 12 / 18

	2. Press EDIT (or ENTER on the Basic control panel)
	3. Press Up and Down buttons at the same time
	or root op and bown batterio at the came time
	4. Press SAVE
Pass criterion	
Meaning of the test	Checking the fault history of the drive
OTED 7	Object the control of control of the Public
STEP 7	Check the actual signal indicating RUN TIME
SIEP /	Check the actual signal indicating RUN TIME
SIEP /	
	(actual signal 0140)
Performance	
	(actual signal 0140) The lifetime of the main and auxiliary fan is about 60 000 h.
Performance	(actual signal 0140)
	(actual signal 0140) The lifetime of the main and auxiliary fan is about 60 000 h.
Performance	(actual signal 0140) The lifetime of the main and auxiliary fan is about 60 000 h.

Testing I/O-board

STEP 8	Analogue input 1
Performance	All VOLTAGES
	First check the position of J1-DIP switches for Analog Inputs. Set Al1
	jumper to voltage position (See ACS550's User manual)
	Supply Al1=0V
Pass criterion	Read parameter 0120: Al1=0V (0%)
Performance	Supply Al1=5V
Pass criterion	Read parameter 0120: Al1=5V (50%)
Performance	Supply Al1=10V
Pass criterion	Read parameter 0120: Al1=10V (100%)
Meaning of the test	Al 1 works correctly

STEP 9	Analogue input 2
Performance	AI2 CURRENTS
	First shoot the goalties of 14 DID switches for Angles bounts Cot AIO
	First check the position of J1-DIP switches for Analog Inputs. Set Al2 jumper to current position (See ACS550's User manual)
	jampor to camon poonem (coo no coo c coo manaa.)
	Supply Al2=0mA
Pass criterion	Read parameter 0121: Al2=0mA (0%)
Performance	Supply Al2=10mA
Pass criterion	Read parameter 0121: Al2=10mA (50%)
Performance	Supply Al2=20mA
Pass criterion	Read parameter 0121: Al2=20mA (100%)
Meaning of the test	Al 2 works correctly

STEP 10	Digital inputs
Performance	Set digital inputs "010101"
Pass criterion	Read parameters 0118: Word 010 & 0119: Word 101
Performance	Set digital inputs "101010"
Pass criterion	Read parameters

ABB Discrete Automation and Motion	n ABB drive service workshop		
BU Low Voltage Drives	Test instruction for ACS/ACH550-01 R5		
Date Author 2006-Oct-12	Checked / Approved Kimmo Hirvonen	Revision A	Page 13 / 18

	0118: Word 101
	0110: Mard 010
Dorformonoo	0119: Word 010 Reset digital inputs: "000000"
Performance Meaning of the test	Digital inputs works correctly
iviearing of the test	Digital inputs works correctly
STEP 11	AO1 & RO1
Performance	Set 1401 to 4 (Fault)
	Read parameter 0122 and measure also RO1 function (pins: 19, 20, 21)
	by using ohm meter.
Pass criterion	RO1 pin 19 connected to pin 20
	Dood payers stay 0100; Mayd "001"
Performance	Read parameter 0122: Word "001" AO1=0mA set parameter 1504 to 0
Pass criterion	Measure AO1=0mA ± 0.8mA
Performance	AO1=10mA set parameter 1504 to 10
Pass criterion	Measure AO1=10mA± 0.8mA
Performance	AO1=20mA set parameter 1504 to 20
Pass criterion	Measure AO1=20mA± 0.8mA
Meaning of the test	AO1 and Relay 1 test
Performance	Reset 1504 to 0
1 Chomianoc	110001 1004 10 0
STEP 12	AO2&RO1
Performance	Set 1401 to 1 (Ready)
	` , , , , , , , , , , , , , , , , , , ,
	Read parameter 0122 and measure also RO1 function (pins: 19, 20, 21)
Pass criterion	by using ohm meter. RO1 pin 19 connected to pin 21
Fass Chlehon	Read parameter 0122: Word "101"
	Troda paramotor or 22. Word To
Performance	AO2=0mA set parameter 1510 to 0
Pass criterion	Measure AO2=0mA ± 0.8mA
Performance	AO2=10mA set parameter 1510 to 10
Pass criterion	Measure AO2=10mA± 0.8mA
Performance	AO2=20mA set parameter 1510 to 20
Pass criterion	Measure AO2=20mA± 0.8mA
Meaning of the test	AO2 and Relay 1 test
Performance	Reset 1510 to 0
2777 / 2	
STEP 13	Relay 2 & 3
Performance	Set 1402 to 3 (Fault(-1)) = 1
	Cot 1400 to 4 (Foult) 0
	Set 1403 to 4 (Fault) = 0
	Read parameter 0122 and measure also RO2 function (pins: 22, 23, 24)
	by using ohm meter.
Pass criterion	Read parameter 0122: Word "110"
Performance	Set 1402 to 2 (Run) = 0
	Set 1403 to 3 (Fault(-1)) = 1

ABB Discrete Automation and Motion	ABB drive service workshop		
BU Low Voltage Drives	Test instruction for ACS/ACH550-01 R5		
Date Author 2006-Oct-12	Checked / Approved Kimmo Hirvonen	Revision A	Page 14 / 18

	Read parameter 0122 and measure also RO3 function (pins: 25, 26, 27) by using ohm meter.
Pass criterion	Read parameter 0122: Word "101"
Meaning of the test	Checking function of relay 2 and 3

In case the unit is equipped with the control panel, the panel must be tested. The ACx550 works with either of two different control panel types, assistant control panel and basic control panel. The ACx550 control panel features can be found in ACx550 User's manual.

STEP 14	Testing the control panel
Performance	Note that this automatic panel self diagnostic function does not worked with some old panel version or Basic control panel. In that case test the old panel functions manually.
	Check that the main power is off.
	Press and hold upper right hand soft key (MENU) and both UP and DOWN arrow buttons simultaneously.
	Switch on the power supply for the frequency converter.
	System activates automatically self diagnostic testing for the control panel. Follow the diagnostic testing until the test finished.
Pass criterion	No error messages during self testing
Meaning of the test	Panel works correctly
Performance	Switch off the power supply

7 Testing the main circuit

The purpose of the main circuit tests is to make sure that the main circuit of the frequency converter is working correctly. The following tests will cover charging circuit, power supply, input bridge, current transducers, gate driver circuits, output bridge and brake chopper IGBT.

STEP 1	Testing with AC without motor
Performance	Connect supply cables to the U1, V1, W1 and ground connectors of the drive (230VAC or 480VAC). Make sure that there are no motor cables or brake resistor cables connected.
	Read inverter measurement of DC-bus voltage (parameter 0107) and compare with measured DC-bus voltage.
Pass criterion	DC-voltages are the same within +/- 5 %
Performance	Set correct start-up data to group 99. Set factory default parameters by selecting parameter 9902 = 1. Change drive control mode to SCALAR control (parameter: 9904), set reference to 25 Hz and start the drive without motor for 15 seconds. Make sure that there are no faults. Also make sure that the main fan and possible internal fan is working. The fan stops quite soon after powering the drive, if the unit is not modulating.
Pass criterion	No faults detected
STEP 2	Testing with AC and motor

ABB Discrete Automation and Motion	ABB drive service workshop		
BU Low Voltage Drives	Test instruction for ACS/ACH550-01 R5		
Date Author 2006-Oct-12	Checked / Approved Kimmo Hirvonen	Revision A	Page 15 / 18

Performance	Connect a test motor to the frequency converter. There must be another motor on connected to the motor shaft, which can be used as load		
	machine. The motor used to test the drive must be smaller or equal s		
	with the load machine. It is also possible to use 50 % smaller load motor		
(motor current is only 50% of the I_{2N}).			
Performance	Set the frequency converter to VECTOR control mode (parameter:		
	9904). Set correct motor data to group: 99.xx. Perform the standa		
- ID run	run for the motor.		
Pass criterion	ID run succeed		
Performance	Test with the light load. Load the drive only with shaft mass.		
- Test with the light Check the fault memory			
load			
	Start drive to 0 Hz		
	Cot around to EO LIT		
	Set speed to 50 Hz		
	Wait around 10 seconds until the speed is stabile.		
Pass criterion	No faults detected		
Performance	Measure input currents: U1, V1, W1		
Pass criterion	Input currents must be symmetrical		
Meaning of the test	Line currents are symmetrical		
Performance	Measure output currents: U2, V2, W2		
Pass criterion	Output currents must be symmetrical		
Performance	Change direction		
	ŭ		
	Set reference to 20Hz		
	Check output frequency parameter 0103 = 20Hz		
Pass criterion	Should be 20 Hz.		
Performance	Stop the drive and wait 10 sec		
	Object the different color for each 15 FO H and 15 M Object to 15		
	Start the drive and set reference to 50 Hz and wait 10 sec to speed up.		
	Change direction and wait until the speed is stabile		
Performance	Stop the drive and check the fault status		
Pass criterion	No faults detected		
1 ass chemon	The facility delegated		
STEP 3	Test with the nominal load		
Performance	Test with the nominal load. It is also possible to use 50 % smaller load		
	motor (motor current is only 50% of the I_{2N}), but in that case the loading		
	time is double. If smallest allowed motor is used, then run the motor for 2		
	hours.		
	Load the drive with continuous RMS current I_{2N} .		
	Check the fault memory		
	Otant divisa to 0.11-		
	Start drive to 0 Hz		
	Sat speed to 50 Hz		
Dace critorian	Set speed to 50 Hz No faults detected		
Pass criterion	ואט ומטונס טכנפטנפט		

ABB Discrete Automation and Motion	ABB drive service workshop		
BU Low Voltage Drives	Test instruction for ACS/ACH550-01 R5		
Date Author 2006-Oct-12	Checked / Approved Kimmo Hirvonen	Revision A	Page 16 / 18

Performance	Start the load motor and load the drive with continuous RMS current I_{2N} .
	Total drive period 1 hour (minimum) continuous full load so that drive is warm.
	Measure input currents: U1, V1, W1
Pass criterion	Input currents must be symmetrical
Performance	Measure output currents: U2, V2, W2
Pass criterion	Output currents must be symmetrical
Performance	Monitor temperature of the drive during the nominal load test (param. 0110)
Pass criterion	Temperature: R1R4 & R7/R8: < 100 °C, R5/R6: < 110 °C
Performance	After 1 hour stop the drive and check the fault status
	Switch off the power supply
Pass criterion	No faults detected

Test below is only valid for drives, which are equipped with built-in brake chopper (ACS550 R1 and R2). The correct brake resistor value must be selected according to the latest manual.

STEP 4	Brake chopper test (Only for ACS550 R1 and R2)
Performance	Connect the brake resistor to the drive.
	Connect Brake Resistor across BR + and BR -
	Power up the drive. Set overvoltage controller off: Parameter 2005 = 0
	Start the drive and set speed to 50Hz
	Monitoring actual torque, actual power signal and DC Bus voltage.
	Parameters: 0105, 0106 and 0107
	Change rotation direction and measure braking current to brake resistor.
	Change rotation direction again and measure braking current to brake resistor.
Meaning of the test	Brake chopper function test
Performance	Stop the drive, restore overvoltage controller ON and switch the mains power off.
Pass criterion	No faults detected and brake chopper worked
Performance	Disconnect brake resistor

8 Final steps

After the test make sure that all the customer's I/O options are properly fastened to the drive with screws. Inspect that xMIO-board has all the connectors and control panel is properly placed. Power up the unit for one more time and check that the control panel is working. Use control panel to check that the fault log is empty and that the customer's parameters are returned to the drive. In case the customer parameters cannot be restored, select ABB STANDARD or HVAC default macro and

ABB Discrete Automation and Motion		ABB drive service workshop		
BU Low Voltage Drives		Test instruction for ACS/ACH550-01 R5		
Date	Author	Checked / Approved	Revision	Page
2006-Oct-12		Kimmo Hirvonen	Α	17 / 18

make an application reset for the drive. Finally in a test report and deliver it to the customer with the drive.

ACS/ACH550 INSPECTION REPORT

Inspection date:	
Tested by:	
Repair workshop contact information:	
Type code of the tested unit:	
Serial number of the unit:	

1. Visual inspection

ABB Discrete Automation and Motion BU Low Voltage Drives		ABB drive service workshop Test instruction for ACS/ACH550-01 R5		
Date 2006-Oct-12	Author	Checked / Approved Kimmo Hirvonen	Revision A	Page 18 / 18
	 Power module 	el of the unit the unit		- - - -
2. Measure	• IGBT gate me	easurement eewheeling diode measurement		- - -
3. Insulation resistance measurement				
4. Testing	the I/O-board			_
5. Testing	the control panel			_
6. Customer parameters backed up				
7. Testing the main circuit Testing with AC without motor Testing with AC and motor Testing with the nominal load				
8. Drive equipped with the braking chopper • Testing of brake chopper				
9. Final ste	 Customer para 			- - -