SH NO

REVISIONS

161A7395

CONT ON SHEET

+

+

+

TEST INSTRUCTIONS

i ji


FIRST MADE FOR 103506A105A6

1. CHECK APPEARANCE OF UNIT

- 2. INSPECT ALL INTERNAL WIRING TO MAKE SURE IT AGREES WITH WIRING DIAGRAM.
- 3. TEST OUTPUT OF INVERTER AS FOLLOWS:

TITLE

A. RECOMMENDED TEST SET-UP:



- B. CONNECT INVERTER IN CIRCUIT SHOWN ABOVE.
- C. OBSERVE VOLTAGE FROM L1 TO L2 WITH SCOPE.
 OUTPUT SHOULD BE 39 \$\frac{1}{2}\$V PP. SQUARE WAVE
 WITH 4 TO 6 MILLISECONDS PER CYCLE.
- D. INVERTER MUST MEET THE ABOVE SPECS WITH SI OPEN AND CLOSED.

CONTACT ACCESSORIES ENGINEERING, EXT. 375 OR 610 IF THERE ARE ANY QUESTIONS.

7D 7 A6A A2C

PRINTS TO

PRINTED IN U.S.A.

APPROVALS

INDUSTRY CONTROL DIV OR SLAEM, VA.

151A7395

CONT ON SHEET

SH NO.