

REV
MO 0

TITLE

CONT ON SHEET 2

SH NO 1

P3K-AL-0652-A01

CIRCUIT BOARD TEST INSTRUCTIONS FOR
TRACKING VC 148D2649G2 1M3, 1T3

CONT ON SHEET 2

SH NO 1

FIRST MADE FOR EHC MARK II

1M3, 1T3

15580

REVISIONS

A. Power Supplies

$$1. \quad 14.7 < V_{TP1} < 16.7$$

$$2. \quad -16.7 < V_{TP2} < -14.7$$

B. Input Differential Amplifier (IC1)

1. Ground TP13 and TP14 and Null IC1.

2. SS Gain

$$\left. \begin{array}{l} -5.05 < V_{TP50}/(V_{TP14} - V_{TP13}) < -4.95 \quad (V_{TP14} > V_{TP13}) \\ 4.95 < V_{TP50}/(V_{TP14} - V_{TP13}) < 5.05 \quad (V_{TP13} > V_{TP14}) \end{array} \right\} \begin{array}{l} |V_{TP14} - V_{TP13}| < 0.6 \\ |V_{TP14} - V_{TP13}| > 0.7 \end{array}$$

$$\left. \begin{array}{l} V_{TP50}/(V_{TP14} - V_{TP13}) = 0 \\ 3.5 < |V_{TP50}| < 4.0 \end{array} \right\}$$

See Figure 1.




FIGURE 1: SS Gain - IC1

COPYRIGHT 1983 GENERAL ELECTRIC CO.

THIS DOCUMENT INCLUDING THE INFORMATION IT CONTAINS IS CONFIDENTIAL AND PROPRIETARY TO GENERAL ELECTRIC COMPANY AND IS MADE AVAILABLE SOLELY TO THE RECIPIENT FOR HIS USE OR MAKE A USE AS A POTENTIAL VENDOR. IT MAY BE USED FOR OTHER PURPOSES WITHOUT THE WRITTEN PERMISSION OF GENERAL ELECTRIC COMPANY. IF YOU ARE A RECIPIENT OF THIS DOCUMENT, YOU WILL TAKE ALL APPROPRIATE STEPS TO PROTECT THE CONFIDENTIALITY OF THE INFORMATION IT CONTAINS.

273-2

273-12

273-71

273-138

273-221

273-227

PRINTS TO

MADE BY *V. Schmeible* JUL 20 1983

APPROVALS

Steam Turbine

DIV OR DEPT.

P3K-AL-0652-A01

ISSUED JUL 20 1983

Schenectady, N.Y.

LOCATION

CONT ON SHEET

SH NO

REV NO. 0	TITLE		CONT ON SHEET 3	SH NO. 2
P3K-AL-0652-A01	CIRCUIT BOARD TEST INSTRUCTIONS FOR TRACKING VC 148D2649G2 1M3, 1T3			
CONT ON SHEET 3	SH NO. 2	FIRST MADE FOR EHC MARK II		

				REVISIONS
B. Input Differential Amplifier IC1 (continued)				
3. Dynamic Gain				
$-2.13 < V_{TP50}/V_{TP14} < -1.48$ ($V_{TP13} = 0, V_{TP14} = 1 @ f = 5 \text{ KHz}$) $1.48 < V_{TP50}/V_{TP13} < 2.13$ ($V_{TP14} = 0, V_{TP13} = 1 @ f = 5 \text{ KHz}$)				
C. Input Differential Amplifier (IC3)				
1. Ground TP15 and TP16 and Null IC3.				
2. SS Gain				
$-5.05 < V_{TP51}/(V_{TP16} - V_{TP15}) < -4.95$ ($V_{TP16} > V_{TP15}$) $4.95 < V_{TP51}/(V_{TP16} - V_{TP15}) < 5.05$ ($V_{TP15} > V_{TP16}$)				
$V_{TP51}/(V_{TP16} - V_{TP15}) = 0$ $3.5 < V_{TP51MAX} < 4.0$				
$ V_{TP16} - V_{TP15} < 0.6$ $ V_{TP16} - V_{TP15} > 0.7$				
3. Dynamic Gain				
$-2.13 < V_{TP51}/V_{TP16} < -1.48$ ($V_{TP15} = 0, V_{TP16} = 1 @ f = 5 \text{ KHz}$) $1.48 < V_{TP51}/V_{TP15} < 2.13$ ($V_{TP16} = 0, V_{TP15} = 1 @ f = 5 \text{ KHz}$)				
D. Input Differential Amp (IC5)				
1. Ground TP17 and TP18 and Null IC5.				
2. SS Gain				
$-5.05 < V_{TP52}/(V_{TP18} - V_{TP17}) < -4.95$ ($V_{TP18} > V_{TP17}$) $4.95 < V_{TP52}/(V_{TP18} - V_{TP17}) < 5.05$ ($V_{TP17} > V_{TP18}$)				
$V_{TP52}/(V_{TP18} - V_{TP17}) = 0$ $3.5 < V_{TP52MAX} < 4.0$				
$ V_{TP18} - V_{TP17} < 0.6$ $ V_{TP18} - V_{TP17} > 0.7$				
PRINTS TO				

MADE <i>V. Schnieble</i> JUL 20 1983	APPROVALS	Steam Turbine	DIV OR DEPT.	P3K-AL-0652-A01
ISSUED JUL 20 1983		Schenectady, N.Y.	LOCATION	CONT ON SHEET 3 SH NO 2

REV NO 0	TITLE	CONT ON SHEET 4	SH NO. 3
P3K-AL-0652-A01	CIRCUIT BOARD TEST INSTRUCTIONS FOR TRACKING VC 148D2649G2 1M3, 1T3		
CONT ON SHEET 4	FIRST MADE FOR EHC MARK II		

REVISIONS

D. Input Differential Amplifier IC5 (continued)

3. Dynamic Gain

$$-2.13 < V_{TP52}/V_{TP18} < -1.48 \quad (V_{TP17} = 0, V_{TP18} = 1 @ f = 5 \text{ KHz})$$

$$1.48 < V_{TP52}/V_{TP17} < 2.13 \quad (V_{TP18} = 0, V_{TP17} = 1 @ f = 5 \text{ KHz})$$

E. VC1 (IC2)

1. Voltage Range

$$1.45 < V_{TP3} < 2.02 \quad (VR1 \text{ CCW})$$

$$7.3 < V_{TP3} < 8^* \quad (VR1 \text{ CW})$$

$$-2.02 < V_{TP4} < -1.45 \quad (VR2 \text{ CCW})$$

$$-8 < V_{TP4} < -7.3^* \quad (VR2 \text{ CW})$$

2. Adjustments

a) Positive

$$1) \text{ Adjust } VR1 \rightarrow V_{TP3} = 3.0$$

$$2) \text{ Apply } V_{TP50} = 2.500$$

$$3) \text{ Adjust } VR1 \rightarrow K1 \text{ (and DS1) just energize}$$

$$4) \text{ Reduce } V_{TP50} \rightarrow K1 \text{ (and DS1) just de-energize}$$

$$\text{Record } V_{TP50} = \text{_____} \text{ (D.O.) } .820 \checkmark$$

* Design Note: To conform to the 711 spec that the differential input voltage be $< 5V$, R8, 11, 24, 27, 40, 43 = 10K should be changed to 2K which will give:

$$0.355 < V_{TP3}, \text{ etc} < 0.437 \quad (VR1, \text{ etc. CCW})$$

$$3.60 < V_{TP3}, \text{ etc} < 3.74 \quad (VR1, \text{ etc. CW})$$

1K-G1
10K-G2
to 2K?

PRINTS TO

MADE BY V. Schneible JUL 20 1983	APPROVALS	Steam Turbine	DIV OR DEPT.	P3K-AL-0652-A01
ISSUED JUL 20 1983		Schenectady, N.Y.	LOCATION	CONT ON SHEET 4 SH NO 3

REV
NO. 0

TITLE

CONT ON SHEET 5

SH NO. 4

P3K-AL-0652-A01

CIRCUIT BOARD TEST INSTRUCTIONS FOR
TRACKING VC 148D2649G2 1M3, 1T3

CONT ON SHEET 5

SH NO. 4

FIRST MADE FOR EHC MARK II

REVISIONS

E. VC1 (IC2) (continued)

2. Adjustments (continued)

b) Negative

1) Adjust VR2 \rightarrow $V_{TP4} = -3.0$

-1.0

2) Apply $V_{TP50} = -2.500$

- .833

3) Adjust VR2 \rightarrow K1 (and DS1) just energize4) Reduce $V_{TP50} \rightarrow$ K1 (and DS1) just de-energizeRecord $V_{TP50} =$ _____ (D.O.)

- .890

3. Hysteresis

$$\text{Hyst} = |V_{TP50_{PU}} - V_{TP50_{DO}}| < 0.3$$

$$\begin{array}{r} .890 \\ .822 \\ \hline .068 \end{array}$$

for a) and b) above.

4. Logic

See Figure 2.




FIGURE 2: VC Logic

PRINTS TO

MADE *V. Schmitt* JUL 20 1983

APPROVALS

Steam Turbine

DIV OR
DEPT.

P3K-AL-0652-A01

ISSUED JUL 20 1983

Schenectady, N.Y.

LOCATION

CONT ON SHEET 5

SH NO 4

REV
NO

TITLE

CONT ON SHEET 6

SH NO 5

P3K-AL-0652-A01

CIRCUIT BOARD TEST INSTRUCTIONS FOR
TRACKING VC 148D2649G2 1M3, 1T3

CONT ON SHEET 6

SH NO. 5

FIRST MADE FOR EHC MARK II

REVISIONS

F. VC2 (IC4)

1. Voltage Range

- 1.45 $< V_{TP6} < 2.02$ (VR3 CCW)
7.3 $< V_{TP6} < 8^*$ (VR3 CW) +1
-2.02 $< V_{TP7} < -1.45$ (VR4 CCW)
-8 $< V_{TP4} < -7.3^*$ (VR4 CW) -2.0

2. Adjustments

a) Positive

- 1) Adjust VR3 $\rightarrow V_{TP6} = 3.0$
2) Apply $V_{TP51} = 2.500$
3) Adjust VR3 \rightarrow K2 (and DS2) just energize
4) Reduce $V_{TP51} \rightarrow$ K2 (and DS2) just de-energize
Record $V_{TP51} = \underline{\hspace{2cm}}$ (D.O.)

b) Negative

- 1) Adjust VR4 $\rightarrow V_{TP7} = -3.0$
2) Apply $V_{TP51} = -2.500$
3) Adjust VR4 \rightarrow K2 (and DS2) just energize
4) Reduce $V_{TP51} \rightarrow$ K2 (and DS2) just de-energize
Record $V_{TP51} = \underline{\hspace{2cm}}$ (D.O.)

3. Hysteresis

$$\text{Hyst} = |V_{TP51\text{PU}} - V_{TP51\text{DO}}| < 0.3$$

for a) and b) above.

4. Logic

See Figure 2.

PRINTS TO

MADE BY *V. Schnable* JUL 20 1954
ISSUED JUL 20 1954

APPROVALS

Steam Turbine

DIV OR
DEPT.

P3K-AL-0652-A01

Schenectady, N.Y.

LOCATION

CONT ON SHEET 6

SH NO 5

REV
NO. 0

TITLE

CONT ON SHEET 7

SH NO. 6

P3K-AL-0652-A01

CIRCUIT BOARD TEST INSTRUCTIONS FOR
TRACKING VC 148D2649G2 1M3, 1T3

CONT ON SHEET 7

SH NO. 6

FIRST MADE FOR EHC MARK II

REVISIONS

G. VC3 (IC6)

1. Voltage Range

- $1.45 < V_{TP9} < 2.02$ (VR5 CCW)
 $7.3 < V_{TP9} < 8^*$ (VR5 CW)
 $-2.02 < V_{TP10} < -1.45$ (VR6 CCW)
 $-8 < V_{TP10} < -7.3^*$ (VR6 CW)

2. Adjustments

a) Positive

- 1) Adjust VR5 $\rightarrow V_{TP9} = 3.0$
2) Apply $V_{TP52} = 2.500$
3) Adjust VR5 \rightarrow K3 (and DS3) just energize
4) Reduce $V_{TP52} \rightarrow$ K3 (and DS3) just de-energize

Record $V_{TP52} =$ _____ (D.O.)

b) Negative

- 1) Adjust VR6 $\rightarrow V_{TP10} = -3.0$
2) Apply $V_{TP52} = -2.500$
3) Adjust VR6 \rightarrow K3 (and DS3) just energize
4) Reduce $V_{TP52} \rightarrow$ K3 (and DS3) just de-energize

Record $V_{TP52} =$ _____ (D.O.)

3. Hysteresis

$$\text{Hyst} = |V_{TP52_{PU}} - V_{TP52_{DO}}| < 0.3$$

for a) and b) above.

4. Logic

See Figure 2.

PRINTS TO

MADE BY

V. Schmeible JUL 20 1983

APPROVALS

Steam Turbine

DIV OR
DEPT.

P3K-AL-0652-A01

ISSUED

JUL 20 1983

Schenectady, N.Y.

LOCATION

CONT ON SHEET 7

SH NO 6

REV NO. 0

TITLE

CONT ON SHEET --

SH NO. 7

P3K-AL-0652-A01

CIRCUIT BOARD TEST INSTRUCTIONS FOR
TRACKING VC 148D2649G2 1M3, 1T3

CONT ON SHEET --

SH NO. 7

FIRST MADE FOR EHC MARK II

REVISIONS

PREPARED BY:

S.S. Abelson

DATE

6/30/83

S.S. Abelson
Electrical Design Engineering
Building 285 Room 120

APPROVED BY:

P.C. Callan

DATE

7-1-83

P.C. Callan, Manager
Electrical Design Engineering
Building 285 Room 112

PRINTS TO

MADE BY

V. Schnitzler JUL 20 1983

APPROVALS

Steam Turbine

DIV OR
DEPT.

P3K-AL-0652-A01

ISSUED

JUL 20 1983

Schenectady, N.Y.

LOCATION

CONT ON SHEET --

SH NO. 7

CODE IDENT NO