g		GE Energ	у	Functional Testing Specification			
	Parts & Repa Louisville, K			7	7556D10Gx		
	Test Procedure for a						
	MENT REVISION STATUS		entry in the "REV" a				
REV.		DESCRIPTION			GNATURE	REV. DATE	
Α	Initial release			So	cott Cash	11-14-2017	
В							
С							
Hard co PROPR MAY N	YRIGHT GENERAL ELECT opies are uncontrolled and are LIETARY INFORMATION – NOT BE USED OR DISCLOS ARED BY Cash	for reference only. THIS DOCUMENT CONTA		PERMISSION OF GENER		COMPANY.	
11-2-			DATE		27.12		

	g	
LOU-	GE Energy	Page 2 of 5
REV. A	Parts & Repair Services	
	Louisville, KY	

1. SCOPE

1.1 This is a functional testing procedure for a Card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

3.1 The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
3.1.1

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.
- **4.2** Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - 4.2.1.1 Wires broken, cracked, or loosely connected
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - 4.2.1.3 Components visually damaged
 - **4.2.1.4** Capacitors bloated or leaking
 - 4.2.1.5 Solder joints damaged or cold
 - 4.2.1.6 Circuit board burned or de-laminated
 - 4.2.1.7 Printed wire runs / Traces burned or damaged

5. EQUIPMENT REQUIRED

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		Appropriate connector breakout box for 125xxx boards
2		Dual Tenma Power supply or similar
1		Switch box for connections to breakout box

LOU-	g GE Energy	Page 3 of 5
LOU-		rage 3 of 3
REV. A	Parts & Repair Services	
11-1171	Louisville, KY	

6. <u>TESTING PROCESS</u>

6.1 Setup G1 procedure is section 6.2 and G2 is 6.3.

6.2 Testing Procedure G1

- **6.2.1** Connect PS1 +30 to pin 17.
- **6.2.2** Connect PS1 -22 to pin 21.
- **6.2.3** Connect common to pin 19.
- **6.2.4** Plug card into Breakout box.
- 6.2.5 Turn R2 and R4 full CW.
- **6.2.6** Connect 50K ohm load from pint 25 to common.
- 6.2.7 Verify +15 Vdc +/- .8v on the positive leg of C1 to common.
- **6.2.8** Verify -15 Vdc +/- .8v on the negative leg of C2 to common.
- **6.2.9** Connect PS2 to Pin39 and common to Pin19.
- 6.2.10 With Pin 39 still at 0 Vdc verify 0 Vdc +/- 25 mv at TP3.
- **6.2.11** Apply 2 Vdc to Pin 39 and verify (-7.8 to -8.2 Vdc) at Pin25, TP2 and TP3.
- **6.2.12** Apply -2 Vdc to Pin 39 and verify (7.8 to 8.2 Vdc) at Pin25.
- **6.2.13** Turn R4 full CCW and verify (2.5 to 2.9 Vdc) at Pin 25.
- **6.2.14** Apply 2 Vdc to Pin 39 and verify (-7.3 to -7.7 Vdc) at Pin25.
- **6.2.15** Turn R2 full CCW and verify (-1.4 to -1.8 Vdc) at TP3.
- **6.2.16** Verify (-.9 to -1.3 Vdc) at Pin 25.
- **6.2.17** Apply -2 Vdc to Ping 39 and verify (.33 to .73 Vdc) at Pin 25.
- 6.2.18 G1 Test complete

6.3 Test Procedure G2,

- **6.3.1** Connect PS1 +30 to pin 17.
- **6.3.2** Connect PS1 -22 to pin 21.
- **6.3.3** Connect common to pin 19.
- **6.3.4** Plug card into Breakout box.
- **6.3.5** Turn R2 and R4 full CW.
- **6.3.6** Connect 50K ohm load from pint 25 to common.
- **6.3.7** Verify +15 Vdc +/- .8v on the positive leg of C1 to common.
- **6.3.8** Verify -15 Vdc +/- .8v on the negative leg of C2 to common.
- **6.3.9** Connect PS2 to Pin39 and common to Pin19.
- **6.3.10** With Pin 39 still at 0 Vdc verify 0 Vdc +/- 25 mv at TP3.

	g	
LOU-	GE Energy	Page 4 of 5
REV. A	Parts & Repair Services	
	Louisville, KY	

- **6.3.11** Apply 2 Vdc to Pin 39 and verify (-7.8 to -8.2 Vdc) at Pin25 and TP3.
- **6.3.12** Apply -2 Vdc to Pin 39 and verify (7.8 to 8.2 Vdc) at Pin25.
- **6.3.13** Turn R4 full CCW and verify (7.3 to 7.7 Vdc) at Pin 25.
- **6.3.14** Apply 2 Vdc to Pin 39 and verify (-2.5 to -2.9 Vdc) at Pin25.
- **6.3.15** Turn R2 full CCW and verify (-1.4 to -1.8 Vdc) at TP3.
- **6.3.16** Verify (-.33 to -.73 Vdc) at Pin 25.
- **6.3.17** Apply -2 Vdc to Ping 39 and verify (.9 to 1.3 Vdc) at Pin 25.
- **6.3.18** G2 test complete.

○ ***TEST COMPLETE ***

Section 7



