

REV NO 1

P3K-AL-0656-A01

CONT ON SHEET 4 SH NO. 3

TITLE  
CIRCUIT BOARD SPECIFICATIONS  
VALVE POSITION DRIVER 169C4773, 1F1-F3  
VALVE POSITION DRIVER - AMS 186C8105, 1F1-F4  
FIRST MADE FOR ENG MARK II

F. 3 KHZ OSCILLATOR (continued)2. Distortion

## a. FET (2N3822) Distortion

Adjusting VR50 too far CW will cause the output TP12 to distort. Check distortion by centering the signal on both the amplitude and sweep coordinates as shown in Figure 3. Distortion occurs when  $|T_1 - T_2| > 10 \text{ usec.}$  and can be eliminated by backing down on VR50 (TP50).

b. Saturation Distortion

Saturation will occur when  $|V_{\text{peak TP12}}| > V_{T1} \text{ or } V_{T2}$  and is eliminated by decreasing VR51.

3. V<sub>Gate</sub> (V<sub>TP50</sub>) Setting

Adjust VR50 so that the oscillator runs at the upper limit of linearity ( $|T_1 - T_2| \approx 10 \text{ usec.}$ ); i.e:

$$|V_{\text{GATE}}| \approx |V_{\text{GATE FET DIST}}| - .010$$

Operation around this point gives maximum temperature and load change stability. A sampling of 25 FET's has shown the upper limit to be:

$$-2.6 < V_{\text{GATE}} < -1.0$$

4. Amplitude Setting

Adjust VR51 for  $V_{TP12} = 6.000 \pm .010 \text{ VRMS.}$

5. Frequency

$$3000 < f < 3400 \text{ Hz}$$

6. Regeneration

The oscillator must restart in all of the following situations:

- Simultaneously interrupt the +22 VDC and the -22 VDC power. Reconnect.
- Interrupt the +22 VDC power. Reconnect.

REVISION

① PAULISI MAY 16 1983

CHG. THIS SHEET.

PRINTS

MADE BY J. Aulisi 14 Sept. 1981

ISSUED

SEP 14 1981

APPROVALS

Steam Turbine

DIV OR DEPT.

Schenectady, N.Y.

LOCATION

P3K-AL-0656-A01

CONT ON SHEET 4

SH NO. 3

set VR50 for 2.5VDC at TP50  
set VR51 for 6.0VRMS at TP3

adjust VR 50 for  
2.5VDC at TP 50 ③  
with VR 51 CCW

REV  
NO. 1

P3K-AL-0656-A01

CONT ON SHEET 5

SH NO. 4

TITLE  
CIRCUIT BOARD SPECIFICATIONS  
VALVE POSITION DRIVER 169C4773, 1F1-F3  
VALVE POSITION DRIVER - AMS 186C8105, 1F1-F4  
FIRST MADE FOR EHC MARK II

REVISION

MAY 16 1983

PAULISI

NO CHG THIS COPY

1

Drift

Does not

3.060 VRMS.

or continuously

MTH

PRINTS

F. 3 KHZ OSCILLATOR (continued)6. Regeneration (continued)

- c. Interrupt the -22 VDC power. Reconnect.  
d. Withdraw and insert the Valve Position Driver Board.

7. Temperature Stability

This test may be conducted with oscillator unloaded.

With  $V_G$  set as in Step 3 at ambient temperature ( $T_A$ ) then:

$$|\Delta V_{TP12}| \leq .060 \text{ VRMS} \quad (T_A \leq T \leq 130^\circ\text{F})$$

A small change in  $V_G$  may be necessary to meet this spec. If

$\Delta V_{TP12} > +.060$  for  $T_A \leq T \leq 130^\circ\text{F}$ , decrease  $V_{GATE}$ . If

$\Delta V_{TP12} > -.060$ , increase  $V_{GATE}$ .

8. Load Variance

No transducer position should change  $V_{TP12}$  more than .15 mv RMS.

$$\Delta V_{TP12} \leq .015 \text{ VRMS}$$

9. Envelope Modulation

Envelope modulation should not exceed .015V ptp.

G. DEMODULATOR

$$V_{TP12} = .6 \text{ VRMS}$$

1. Fully extend the transducer to its linear limit (as in valves wide open position) and adjust VR3 so that: (Top Stop)

$$V_{TP8} = 0.000 \pm 0.010 \text{ VDC}$$

- a. Verify  $V_{TP7}$  by Figure 4. (use Scope)

- b. Verify  $V_{TP52}$  by Figure 5. (use Scope)

Note: Region of Transducer used is  
2.5" from body to 6" from Body

MADE BY J. Aulisi 14 Sept. 1981

ISSUED SEP 14 1981

APPROVALS

Steam Turbine

Schenectady, N.Y.

DIV OR DEPT.

LOCATION

P3K-AL-0656-A01

CONT ON SHEET 5

SH NO. 4

# GENERAL ELECTRIC

P3K-AL-0394-A01

CONT ON SHEET

2

SH NO.

1

REV NO. 1

P3K-AL-0394-A01

CONT ON SHEET

2

SH NO.

1

TITLE

SPECIFICATIONS AND TEST INSTRUCTIONS

VALVE POSITION DEMODULATOR CKT. BD. ASM. DWG. 115D2248

FIRST MADE FOR

EHK MARK II

1F1-C

REVISIONS

271981  
no chg. this sht

## A. BOARD CONTENTS

The board assembly contains:

1. 3 KHz oscillator
2. 4 ea. regulated power supplies
3. 4 ea. rectifier demodulator circuits with adjustments in both meter zeroing and range.
4. Connections to accomodate 4 position transducers and their corresponding panel meters.

## B. TEST SETUP

See Figure 1.

## C. POWER SUPPLIES (INITIAL CHECK)

1. VTP1:  $15.7 \pm 1.0$  VDC
2. VTP2:  $-15.7 \pm 1.0$  VDC
3. VTP51:  $15.0 \pm 0.75$  VDC @  $T_{room}$ ,  $< 16.5$  VDC, hot
4. VTP52:  $-15.0 \pm 0.75$  VDC @  $T_{room}$ ,  $> -16.5$  VDC, hot

USE

see Mark

## D. 3 KHZ OSCILLATOR

→ See P3K-AL-0656-A01 marked up & DO.

All tests, except that for temperature sensitivity, are to be done with the oscillator normally loaded.

### 1. Initial Starting

Adjust VR50 to mid range and observe TP3 with a scope (2 volt/div amplitude, 50 us/div sweep). If necessary readjust for a non-distorted sine wave.

### 2. Distortion

#### a. FET (2N3822) Distortion

Adjusting VR50 too far CW will cause the output TP3 to distort. Check distortion by centering the signal on both the amplitude and sweep coordinates as shown in Figure 2. Distortion occurs when  $|T_1 - T_2| > 10$  usec and can be eliminated by backing down on VR50 (TP50).

#### b. Saturation Distortion

Saturation will occur when  $V_{peak} TP3 > V_{zener}$  and is eliminated by decreasing VR51.

273-2

273-12

273-71

273-138

273-221

273-221

PRINTS TO

MADE BY

J. Polacek Sept. 15, 1977

APPROVALS

Steam Turbine

DIV OR

DEPT.

P3K-AL-0394-A01

ISSUED

SEP 20 1977

Schenectady, N.Y.

LOCATION

CONT ON SHEET

2

SH NO. 1

REV. NO. 1	TITLE	CONT ON SHEET 3	SH NO. 2
P3K-AL-0394-A01	SPECIFICATIONS AND TEST INSTRUCTIONS		
CONT ON SHEET 3	VALVE POSITION DEMODULATOR CKT. BD. ASM. DWG. 115D2248		
SH NO. 2	FIRST MADE FOR EHC MARK II		

D. 3 KHZ OSCILLATOR (continued)

3. VGATE (VTP50) Setting

Adjust VR50 so that the oscillator runs at the upper limit of linearity ( $|T_1 - T_2| \leq 10 \text{ usec}$ ); ie:

$$|V_{GATE}| \approx |V_{GATE \text{ FET DIST}}| - .010$$

Operation around this point give maximum temperature and load change stability. A sampling of 25 FET's has shown the upper limit to be:

$$-2.6 < V_{GATE} < -1.0$$

4. Amplitude Setting

Adjust VR51 for  $V_{TP3} = 6.000 \pm .010V \text{ RMS}$ .

\* 5. Frequency

$$3000 < f < 3400 \text{ Hz}$$

6. Regeneration

The oscillator must restart in all of the following situations:

- Simultaneously interrupt the +22 VDC and the -22 VDC power. Reconnect.
- Interrupt the +22 VDC power. Reconnect.
- 22 VDC power. Reconnect.
- Withdraw and insert the Valve Pos. Demodulator board.

7. Temperature Stability

This test may be conducted with oscillator unloaded. With  $V_G$  set as in Step 3 at ambient temperature ( $T_A$ ) then:

$$\Delta V_{TP3} \leq .060 \text{ VRMS } (T_A \leq T \leq 130^\circ\text{F})$$

A small change in  $V_G$  may be necessary to meet this spec. If  $\Delta V_{TP3} > +.060$  for  $T_A \leq T \leq 130^\circ\text{F}$ , decrease  $V_{GATE}$ . If  $\Delta V_{TP3} > -.060$ , increase  $V_{GATE}$ .

8. Load Variance

No combination of transducer positions should change  $V_{TP3}$  more than 10 mv RMS.

$$\Delta V_{TP3} \leq .010 \text{ V RMS}$$

REVISION:

1. PAULI OCT 27 1981  
\* Chg. made

PRINTS 1

MADE BY J. Polacek Sept. 15, 1977	APPROVALS	Steam Turbine	DIV OR DEPT.	P3K-AL-0394-A01
ISSUED SEP 20 1977		Schenectady, N.Y.	LOCATION	CONT ON SHEET 3 SH NO. 2

REV NO. <u>1</u>  P3K-AL-0394-A01  CONT ON SHEET <u>4</u> SH NO. <u>3</u>	TITLE SPECIFICATIONS AND TEST INSTRUCTIONS VALVE POSITION DEMODULATOR CKT. BD. ASM. DWG. 115D2248  FIRST MADE FOR EHC MARK II
---	---

REVISION

D. 3 KHZ OSCILLATOR (continued)

9. Envelope Modulation

Envelope modulation should not exceed .015V ptp.

E. POWER SUPPLIES

With the oscillator loaded at 6V RMS:

1. Steady State

With Ammeters on pins 37 and 41:

a. +22 VDC:  $I_{board} \approx 170 \pm 25$  ma

b. -22 VDC:  $I_{board} \approx -140 \pm 25$  ma

2. Transients

To check the presence and value of C5 and C7, connect the +22 and -22 VDC. In both at TP51 and TP52:

$$t_{rise} > 0.5 \text{ m sec.}$$

F. DEMODULATORS

With  $V_{TP3} = 6.000 \pm .010$  V RMS.

Check the minimum and maximum sensitivity of each circuit, where:

$$\text{Sensitivity} = \frac{\% \text{ meter movement}}{1'' \text{ xducer displacement}}$$

In both cases, zero the meter when the transducer rod is inserted (valves closed position).

$$8.6 < \text{Sensitivity min} < 9.5$$

$$28 < \text{Sensitivity max} < 35$$

10/27/81  
 No chg. this sheet

PRINTS TO

MADE BY J. Polacek Sept. 15, 1977  ISSUED <u>SEP 20 1977</u>	APPROVALS  <div style="border: 1px solid black; padding: 2px; text-align: center;">             Steam Turbine              Schenectady, N.Y.           </div>	DIV OR DEPT.  LOCATION	P3K-AL-0394-A01  CONT ON SHEET <u>4</u> SH NO. <u>3</u>
---	---	------------------------------	---

REV NO. <b>101</b>  P3K-AL-0394-A01  CONT ON SHEET <b>5</b> SH NO. <b>4</b>	TITLE SPECIFICATIONS AND TEST INSTRUCTIONS VALVE POSITION DEMODULATOR CKT. BD. ASM. DWG. 115D2248  FIRST MADE FOR <b>EHC MARK II</b>
---	--

REVISIONS

OCT 27 1981  
 ① CPALU  
 no chg. this sheet

Transducers  
 GM-1025-1  
 119C9638-1  
 8" Stroke

115D2248 G-1

Panel Meters  
 U4392-2  
 -0.5-0+0.5 ma




FIGURE 1: TEST SETUP

PRINTS T

MADE BY <b>J. Polacek Sept. 15, 1977</b>  ISSUED <b>SEP 20 1977</b>	APPROVALS  <div style="border: 1px solid black; padding: 2px; text-align: center;">             Steam Turbine              Schenectady, N.Y.           </div>	DIV OR DEPT.  <b>P3K-AL-0394-A01</b>  LOCATION CONT ON SHEET <b>5</b> SH NO. <b>4</b>
---	---	--

REV NO. 1

TITLE

CONT ON SHEET

6

SH NO.

5

P3K-AL-0394-A01

SPECIFICATIONS AND TEST INSTRUCTIONS

VALVE POSITION DEMODULATOR CKT. BD. ASM. DWG. 115D2248

CONT ON SHEET

6

SH NO. 5

FIRST MADE FOR

EHC MARK II

REVISIONS

① DRAUGHT 27 1981  
no chg. this sheet




FIGURE 2 FET DISTORTION -  $|T_1 - T_2| > 10\text{usec}$

PRINTS T

MADE BY J. Polacek Sept. 15, 1977

APPROVALS

Steam Turbine

DIV OR DEPT.

P3K-AL-0394-A01

ISSUED

Schenectady, N.Y.

LOCATION

CONT ON SHEET

6

SH NO.

5

REV NO. 01  
P3K-AL-0394-A01  
CONT ON SHEET SH NO. 6

TITLE  
SPECIFICATIONS AND TEST INSTRUCTIONS  
VALVE POSITION DEMODULATOR CKT. BD. ASM. DWG. 115D2248  
FIRST MADE FOR EHC MARK II

REVISIONS

PREPARED BY

S.S. Abelson

DATE

2/27/74

S.S. Abelson  
EHC DESIGN ENGINEERING

ESA

9/24/81

OCT 27 1981  
① P. Callan  
no chg. this sh

APPROVED BY

P.C. Callan

DATE

9-6-77

P.C. Callan - MANAGER  
EHC DESIGN ENGINEERING

TEST PROCEDURE

REVIEWED BY

R. Debertolis

DATE

R. Debertolis  
EHC TEST ENGINEER

PRINTS TO

MADE BY  
J. Polacek Sept. 15, 1977  
ISSUED  
SEP 20 1977

APPROVALS

Steam Turbine

DIV OR  
DEPT.

Schenectady, N.Y.

LOCATION

P3K-AL-0394-A01

CONT ON SHEET

SH NO.

CODE IDENT N