g	GI	E Energy	Functional Testing Specification
	Parts & Repair Services Louisville, KY.		LOU-GED-DS3800NDID

Test Procedure for a DS3800NDID card

DOCUMENT REVISION STATUS: Determined by the last entry in the "REV" and "DATE" column					
REV.	DESCRIPTION	SIGNATURE	REV. DATE		
Α	Initial release	Jeffrey D. Barton	7/11/02		
В	Changed Header	C. Wade	7/25/2008		
С	Added asset numbers to section 5.	D. Bush	8/13/2010		
D	Added step 6.1.2.	Cristyn Edlin	12/4/2012		
E					

© COPYRIGHT GENERAL ELECTRIC COMPANY

Hard copies are uncontrolled and are for reference only.

PROPRIETARY INFORMATION – THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION OF GENERAL ELECTRIC COMPANY AND MAY NOT BE USED OR DISCLOSED TO OTHERS, EXCEPT WITH THE WRITTEN PERMISSION OF GENERAL ELECTRIC COMPANY.

PREPARED BY Jeffrey D. Barton	REVIEWED BY D. Bush	REVIEWED BY Cristyn Edlin	Rober Dunll
DATE 7/11/02	DATE 1/13/2010	DATE 14/4/2012	DATE 07/22/02

TIDS3800NDID.doc
REV. D

GE Energy
Parts & Repair Services
Louisville, KY

Page 2 of 3

Functional test procedure for a DS3800NDID control card.

1. SCOPE

1.1 This is a functional testing procedure for a Digital Siltron Control card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
 - **3.1.1** Check electronic folder for more information.

4. **ENGINEERING REQUIREMENTS**

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.
- 4.2 Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - 4.2.1.1 Wires broken or cracked
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - **4.2.1.3** Loose wires
 - 4.2.1.4 Components visually damaged
 - 4.2.1.5 Capacitors leaking
 - 4.2.1.6 Solder joints damaged or cold
 - 4.2.1.7 Circuit board burned or de-laminated
 - 4.2.1.8 Printed wire runs burned or damaged

5. **EQUIPMENT REQUIRED**

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1	H033779	ATE Test Fixture for DS3800NDID Board
1		ATE Test Rack with #27 Personality Card
1	H188587	ATE Test Fixture DS3800DDIB Card
1	H033700	Digital Siltron Test Drive
1		Digital Siltron Test Drive DS3800DDIB Card

GE Energy
Parts & Repair Services
Louisville, KY

TIDS3800NDID.doc REV. D

6. TESTING PROCESS

6.1 Setup

- **6.1.1** Inspect surface mounted diodes on U78 hybrid card for cold solder joints, you may find hairline cracks in the solder joints.
- **6.1.2** Ensure that U22 24 are NEC-D71055C and U52 54 are NEC-D71054-10. If they are not, replaced them.

6.2 Testing Procedure

6.2.1 ATE Test

6.2.1.1 Run the DS3800NDID test on the ATE.

6.2.2 Drive Test

- 6.2.2.1 Install DS3800DDIB drive test daughter card on UUT.
- 6.2.2.2 Install UUT in Digital Siltron Drive.
- 6.2.2.3 Power up test drive.
- **6.2.2.4** Verify unit goes thru self-diag. cycles by watching LED's sequence and all IMOK LEDS illuminate on both drive boards.
- 6.2.2.5 After sequence of self diag. completes, watch center meter (AMATURE VOLTAGE), located at top of drive unit, it will cycle from meter center to the right 6 times, then from center meter to the left 6 times.
- **6.2.2.6** During motor startup, left meter (FIELD AMPS), at top of drive will move to the right at 100% then drop to 70%, showing drive is in energy saving mode.
- 6.2.2.7 Let drive run for a 4hr. burn-in.
- **6.2.2.8** If drive continues to operate after burn-in test, all test passed and UUT is ready for completion.
- **6.2.2.9** Remove UUT and remove all test firmware and reinstall test firmware back in to drive test board.
- 6.2.2.10 Install complete drive test board back into drive unit.

6.3 ***TEST COMPLETE ***

7. Notes

7.1 None at this time.

8. Attachments

8.1 None at this time