

P3K-AL-0373-A01	TITLE
CONT ON SHEET 7 SH NO. 6	TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER 1L1-G001
	FIRST MADE FOR EHC MARK II (LOAD CONTROL UNIT)

TEST INSTRUCTIONS 1L1-G001

Assembly 115D2291

Schematic 115D2289

PROCEDURE:

1. Refer to Fig. A for test circuit.
2. Refer to Fig. B for equipment list and setup instructions.

NOTE: All settings and specifications are +1MV unless otherwise specified.

All setpoints must not be closer than 2 turns from either end of setpoint pot.

Before Plugging Board In:

3. Adjust VR2 CW. Adjust VR5 CCW.
4. ALL SWITCHES DOWN.

Plug Board In:

5. Check test supply voltages for +22.00VDC at Pin 37 and -22.00 VDC at Pin 41.

REVISIONS

PRINTS TO

MADE BY	APPROVALS	Steam Turbine	DIV OR DEPT.	P3K-AL-0373-A01
ISSUED		Schenectady	LOCATION	CONT ON SHEET 7 SH NO. 6

REV NO.	P3K-AL-0373-A01		TITLE		CONT ON SHEET	8	SH NO.	7	
CONT ON SHEET			8			SH NO.			7
TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER 1L1-G001			FIRST MADE FOR						
<p>6. Check ckt. bd. supply voltages at TP1 and TP2 for +15.7 and -15.7 VDC (Tol. = ± 1.0VDC).</p> <p>7. S2 up - ground TP9.</p> <p>8. Adj. VS1 and VS2 for 0.00VDC at pins 27 and 26 (TP7 and TP6).</p> <p>9. Adjust offset (VR50) of IC 1 for 0 VDC at pin 33. (TP3)</p> <p>10. Adj. offset (VR51) of IC 2 for 0 VDC at pin 29. (TP10)</p> <p>11. Adj. VS1 for 10.00 VDC at pin 27. (TP7)</p> <p>12. Check saturation voltage of IC 1. (> -13.00 VDC at TP4)</p> <p>13. Check saturation voltage of IC 2. (> -12.00 VDC at TP10)</p> <p>14. Adj. VS1 for -10.00 VDC at pin 27. (TP7) S1 up. <i>checked</i></p> <p>15. Check saturation voltage of IC 1. ($> +13.00$ VDC at TP4)</p> <p>16. Check saturation voltage of IC 2. ($> +12.00$ VDC at TP10) S1 down. <i>ok</i></p> <p>17. Adj. VR2 CCW.</p> <p>18. Check range of VR3 at TP3.</p> <p style="text-align: center;"> $\frac{CW}{-1.275 / 1.531 \text{ VDC}}$ $\frac{CCW}{-1.308 / 1.572 \text{ VDC}}$ $\frac{CW}{11.355 / 11.819 \text{ VDC}}$ $\frac{CCW}{6.309 / 7.216 \text{ VDC}}$ </p> <p>19. Adj. VR2 CW (Final Setting)</p> <p>20. Check range of VR3 at TP3.</p> <p style="text-align: center;"> $\frac{CW}{11.355 / 11.819 \text{ VDC}}$ $\frac{CCW}{6.309 / 7.216 \text{ VDC}}$ </p> <p>21. Adj. VR3 at TP3 for +10.000 VDC (Final Setting).</p>								REVISIONS	
MADE BY								APPROVALS	
ISSUED								<div>Steam Turbine</div> <div>Schenectady</div> <div>LOCATION</div>	
DIV OR DEPT.								<div>P3K-AL-0373-A01</div> <div>CONT ON SHEET</div> <div>8</div> <div>SH NO.</div> <div>7</div>	
PRINTS TO									

REV NO.	TITLE		CONT ON SHEET	9	SH NO.	8						
P3K-AL-0373-A01		TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER										
CONT ON SHEET	9	SH NO.	8	FIRST MADE FOR								
<p>22.- Adj. VS1 for -1.000VDC at pin 27 (TP7).</p> <p>23.- Check TP3 for +4.900 to 5.100VDC.</p> <p>24.- Adj. VS1 for 0.00VDC. Adj. VS2 for -1.000VDC at pin 26 (TP6).</p> <p>25.- Check the range of VR1 at TP3.</p> <p style="text-align: center;"><u>CW</u> <u>CCW</u></p> <p style="text-align: center;">+3.680/3.830VDC 1.189/1.305</p> <p>26.- Adj. VS2 for 0.00 VDC.</p> <p>27.- S2 down.</p> <p>28.- Check TP5 for 19.940 to 10.158 VDC.</p> <p>29.- Remove VS2 from pin 26. Connect VS2 to TP5. Adj. VS2 for +1.000 at TP5.</p> <p>30.- S3 up.</p> <p>31.- Check TP3 for -1.960 to 2.040 VDC. (Wait for C3 to charge)</p> <p>32.- Adj. VS2 for 0.00VDC. Remove VS2 from TP5. S2 up.</p> <p>33.- Remove the ground from TP9.</p> <p>34.- Check range of VR4 at TP9.</p> <p style="text-align: center;"><u>CW</u> <u>CCW</u></p> <p style="text-align: center;">-10.462/10.682VDC -9.408/9.784VDC</p> <p>35.- Adj. VR4 for -10.000VDC at TP9.</p> <p>36.- Check TP3 for +9.980 to 10.020 VDC.</p> <p>37.- Adj. VR4 for +10.000 at TP3.</p> <p>38.- Check TP10 for +10.000VDC.</p>						REVISIONS						
												PRINTS TO
						MADE BY	APPROVALS		DIV OR DEPT.		P3K-AL-0373-A01	
						ISSUED			Schenectady		LOCATION	CONT ON SHEET 9 SH NO. 8

FP-803-WB (6-74)
PRINTED IN U.S.A.

P3K-AL-0373-A01

CONT ON SHEET 11 SH NO. 10

REV
t.O.

TITLE

P3K-AL-0373-A01

TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER

CONT ON SHEET 11 SH NO. 10

FIRST MADE FOR

54. The noise suppression lag time constant of the closing bias input will be measured by applying a step input voltage and measuring the amplifier response with a plotter.

Use S2 to apply a step from 0V to +10.0VDC (at TP5). The acceptable response at TP3 is as shown in Figure 1.

55. Adj. VS2 for -10.000VDC at pin 26 (TP6).

56. Adj. VS1 for +7.000VDC at pin 27 (TP7).

57. ^{sup} Remove the ground from TP9.

58. S2 up.

59. Adj. VR1 for 0.00VDC at TP3. (Final Setting)

60. End of Test.

REVISIONS

PRINTS TO

MADE BY

APPROVALS

Steam Turbine

DIV OR
— DEPT.

P3K-AL-0373-A01

ISSUED

Schenectady

LOCATION

CONT ON SHEET 11 SH NO. 10

REV
NO.

TITLE

P3K-AL-0373-A01

TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER

CONT ON SHEET 12 SH NO. 11

FIRST MADE FOR

DC Gain has been
checked in previous step
PDC 4-14-89

TABLE 1

APPLY INPUT	INPUT FREQ.	INPUT AMPLITUDE	MONITOR OUTPUT	MEASURE OUTPUT	OUTPUT AMPLITUDE	A VDC V/V	fo HZ
PIN	HZ	VOLTS RMS	TP	PIN	VOLTS RMS		HZ
27	104	1.0	3	33	3.28/3.81	5	105 +12
26	143	1.0	3	33	2.47/2.86	3.76	144 +16

REVISIONS

PRINTS TO

MADE BY

APPROVALS

ISSUED

Steam Turbine

DIV OR
DEPT.

Schenectady

LOCATION

P3K-AL-0373-A01

CONT ON SHEET 12

SH NO. 11

REV
NO.

TITLE


P3K-AL-0373-A01

TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER

CONT ON SHEET 13 SH NO. 12

FIRST MADE FOR

REVISIONS

FIGURE 1

The time constant is the time required for the output to rise to 63% of its final value; in this case -12.6 VDC.

For acceptance, the time constant must be between 750 and 1120 MS.

PRINTS TC

MADE BY

APPROVALS

Steam Turbine

DIV OR
DEPT.

P3K-AL-0373-A01

ISSUED

Schenectady

LOCATION

CONT ON SHEET 13 SH NO. 12




FIGURE A

REV NO.		TITLE		CONT ON SHEET 15 SH NO. 14	
P3K-AL-0373-A01		TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER			
CONT ON SHEET 15 SH NO. 14		FIRST MADE FOR			
<p><u>EQUIPMENT NEEDED</u></p> <p>A. DVM 5 digit AC/DC SD7005A</p> <p>B. VS1, VS2 DC power supply HP6112A</p> <p>C. Function generator HP3300A</p> <p>D. Frequency counter SD6150</p> <p>E. Scope TEK R5103N</p> <p>F. XY plotter Honeywell 530</p> <p><u>SETUP INSTRUCTIONS</u></p> <p>1. All loads to be applied to the ckt, under test are $\pm 1\%$ tolerance.</p> <p>2. All signals are measured and applied with respect to Pin. 39.</p> <p><u>FIGURE B</u></p>				REVISIONS	
PRINTS TO					
MADE BY		APPROVALS		DIV OR DEPT.	
ISSUED				P3K-AL-0373-A01	
		Steam Turbine		LOCATION	
		Schenectady		CONT ON SHEET 15 SH NO. 14	

REV NO.	TITLE TEST INSTRUCTIONS FOR INTERCEPT VALVE AMPLIFIER 1L1-G001 (ASS'Y DRAWING 115D2291 G-1)		CONT ON SHEET ---	SH NO. 15
P3K-AL-0373-A01		FIRST MADE FOR EHC MARK II (LOAD CONTROL UNIT)		
CONT ON SHEET ---		SH NO. 15		REVISIONS
PREPARED BY <u>D. Economou</u> DATE <u>7/26/73</u> D. Economou EHC DESIGN ENGINEERING				
APPROVED BY _____ DATE _____ P.C. Callan - MANAGER EHC DESIGN ENGINEERING				
TEST PROCEDURE PREPARED BY _____ DATE _____ C. Bugg EHC TEST ENGINEER				
TEST PROCEDURE REVIEWED BY _____ DATE _____ D. Economou EHC DESIGN ENGINEERING				
MADE BY _____				PRINTS TO
ISSUED _____		APPROVALS	Steam Turbine Schenectady, N.Y.	DIV OR DEPT. P3K-AL-0373-A01
			LOCATION	CONT ON SHEET --- SH NO. 15