GENERAL & ELECTRIC

P3K-AL-0133-A01

TITLE

CONT ON SHEET

P3K-AL-0133-A01

INSTRUCTION FOR TESTING THE BYPASS VALVE AMPLIFIER CIRCUIT BOARD

CONT ON SHEET SH NO. FIRST MADE FOR 947D374 G6 AND G7

REVISIONS

This process instruction provides a method for performing a functional check with the necessary adjustments for the subject circuit board prior to installation in the EHC cabinet. Rl and R2 will require further trimming when the circuit board is installed in the EHC Cabinet.

TEST PROCEDURE

- 1. Examine the circuit board to see that the electrical components and printed circuits are not physically damaged.
- 2. Plug circuit board 947D374 G-6 into the test fixture.
- 3. Use an ohmmeter to check that there are no short circuits between any combination of pins 17, 19, 21, 38, and 40.
- 4. Connect a resistor of 2.2K ohms, 1 Watt between pins 23 and 19.
- 5. Connect an adjustable 1.0K ohm potentiometer between pins 27 and 19. The potentiometer slider should be connected to pin 26. Connect the potentiometer electrically such that the slider is shorted to pin 27 when the potentiometer is in the full clockwise position. This potentiometer will be referred to as $R_{\rm p}$.
- Connect an adjustable 5.0% ohm potentiometer between pins 22 and 19. The potentiometer slider should be connected to pin 25. Connect the potentiometer electrically such that the slider is shorted to pin 22 when the potentiometer is in the full clockwise position. This potentiometer will be referred to as R.
- 7. Connect the input of a high gain DC operational amplifier to pin 39 and the output to pin 41.
- 8. Connect a well regulated (+) 30.0 volt DC power supply to pins 17 and 38. The negative voltage terminal should be connected to pin 19. -22.0
- 9. Connect a well regulated (-) 20+0 volt DC power supply to pins 21 and 40. The positive voltage terminal should be connected to pin 19.
- 10. All voltage measurements will be made with respect to test point TP11.
- 11. Set Rp to full counterclockwise position and connect TP5 and pin 29 to signal ground, pin 19.

APPROVALS

DIV OR

GNT 1983 GENERAL ELECTRIC CO.

+

Steam Turbine

P3K-AL-0133-A01

Schenectady, N.Y. LOCATION SH NO. 2

CONT ON SHEET

PRINTS TO

-		GENERAL & ELECTRIC P3K-AL-0133-A01	•					
REN	P3K-AL-0133-A01 ONT ON SMEET 4 SH NO. 3 FIRST MADE FOR 947D374 G6 AND G7							
3	=	-5,26 for G6 TEST PROCEDURE (continued)	REVISIONS					
		Apply 4.75 volts to pin 35. The voltage at TP3 and pin 23 should be between +4.9 to +5.1 volts.	FOR 5Y					
-105-01		Remove the 1.75 volt input to pin 35 and the signal ground from pin 29.						
25 for G:	14. Apply -0.475 volts to pin 29 and +5.000 volts to pin 35. 15. Adjust R2 until the voltage at TP3 is 0.000 volts. 16. Remove the-0.475 volts from pin 29 and the +5.000 volts from pin 35.							
	17.	Remove the signal ground from TP5 and connect pins 29 and 35 to signal ground, pin 19.						
	18.	Set R _B to give -0.125 volts at TP3. Connect the input of a high gain DC operation amplifier to pin 33 and						
	19.	Connect the input of a*high gain DC operation amplifier to pin 33 and the output to pin 37.						
	20.	Set RJ to the full clockwise position.						
	21.	Adjust R1 to give +5.00 volts at TP3. 5.47 +0 5.67						
	22.	The voltage at TP4 and pin 25 should be between -4.90 and -5.10 volts.						
	23.	Remove the signal ground from pin 29 and apply -06 volts to pin 29.						
	24.	Slowly turn RJ counterclockwise.						
:	25.	Observe that the magnitude of the negative voltage at TP4 and the positive voltage at TP3 are reduced. When the voltage at TP3 reaches approximately +2.5 volts, it will become fixed while the voltage at TP4 continues to decrease.	8					
	26.	Remove all test equipment.						
+	27.	Remove the circuit board from the test fixture and identify it with a suitable mark to indicate that it has been tested and adjusted in accordance with this instruction.	£1-273 273-2 273-12 273-13					
			273-13					

D.D. Mon June 2 1971 APPROVALS

Steam Turbine DHY OR P3K-AL-0133-A01

ISSUED June 3 1971 Schenectady, N.Y. LOCATION CONT ON SHEET 4 SH NO. 3

11771 CODE IDENT MC

·

Data Sheet

Job #								
Serial #					Burn-in Start			
Date								
Data Sheet f	or125De	6292G0005			Burn-in Stop			
Test Procedu	ure _P3K-A	L-0133-A01			Technician _			
Test			.	B B		Pot Values		
Procedure Step	Nominal	Lower Limit	Pre-Burn in Results	Post Burn in Results	Upper Limit	If applicable CW CCW Page 1		Pass/Fail
8	30VDC		THE TOTAL OF THE T	- III III Galla	Оррен Енти			
9	-22VDC							
12	5VDC	<u>4</u> .9V			5.1V			
15	0VDC				_			
15 -R2								
21	5.5VDC	5.4V			5.6V			
21 - R1							_	
22	-5.4VDC	-5.3V			-5.5V			
25	TP4							
	TP3							

					_			
								<u>_</u>
					_			