g	GE Industrial Systems		al Systems	Functional Testing Specification		
	Renewal Serv Louisville,KY			LOU	J-GED-DS3800N	PSL
		Test Proc	edure for DS380	00NPSL		
DOCUI	MENT REVISION STATUS	: Determined by the last e	ntry in the "REV" a	nd "DATE" columi	n	
REV.		DESCRIPTION	···· , ··· ··· · · · · · · · · · · · · · · ·		SIGNATURE	REV. DATE
Α	Initial release				John Wychulis	08/22/02
В						
С						
PROPR		RIC COMPANY THIS DOCUMENT CONTAIN ED TO OTHERS, EXCEPT W				
PREPA	ARED BY Wychulis	REVIEWED BY	REVIEWE	D BY	Rober of DATE	

LOU-GED-DS3800NPSL
REV. A

GE Industrial Systems
Renewal Services
Louisville, KY

Functional test procedure for a Card

Page 2 of 6

1. SCOPE

1.1 This is a functional testing procedure for a DS3800NPSL Power Supply Card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

3.1 The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.3.1.1

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.
- 4.2 Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - 4.2.1.1 Wires broken or cracked
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - **4.2.1.3** Loose wires
 - 4.2.1.4 Components visually damaged
 - 4.2.1.5 Capacitors leaking
 - 4.2.1.6 Solder joints damaged or cold
 - 4.2.1.7 Circuit board burned or de-laminated
 - 4.2.1.8 Printed wire runs burned or damaged

5. EQUIPMENT REQUIRED

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		Fluke 85 DMM (or Equivalent)
1	HO33772	DS3800 Power Supply
1		NRTB Test Fixture

GE Industrial Systems
Renewal Services
Louisville, KY
Page 3 of 6

LOU-GED-DS3800NPSL REV. A

6. TESTING PROCESS

- 6.1 Setup
 - **6.1.1** Connect power supply to test fixture
 - Note:
- 6.2 Testing Procedure
 - **6.2.1** Install the NPSL board in the test fixture. Turn on power supply
 - 6.2.2 NPSL –measure across C3 for 28v(24v)-Check to see if light is on. NRTB—measure the caps below the pots for the plus and minus 15 v supplies
- 6.3 ***TEST COMPLETE ***
- 7. NOTES

LOU-GED-DS3800NPSL REV. A

GE Industrial Systems Renewal Services Louisville, KY

Page 4 of 6

9.0 NPSL TEST INSTRUCTIONS

9.1 SCOPE

THE FOLLOWING DESCRIBES THE SETUP AND TEST PROCEDURE FOR THE PWB DS380ONPSL. THIS TEST APPLIES TO THE FOLLOWING VERSIONS:

9.2 SPECIAL TEST EQUIPMENT

METER USED FOR MEASUREMENTS SHOULD MEASURE TRUE RMS

9.3 POWER SUPPLY REQUIREMENTS

> PA75 (SET FOR ABOUT .2 AMP CURRENT LIMIT) P28 DCOM PAL 43. 79

9.4 INITIAL SETUP

NONE

9.5 DAUGHTER BOARD

NONE

9.6 ELECTRICAL TEST

- 1. PRIOR TO APPLYING POWER INSPECT THE PWB AS FOLLOWS:
 - A. VERIFY THAT THREE TRANSFORMERS ARE PRESENT AND THAT PINS 1. 2. AND 3 OF EACH TRANSFORMER ARE SOLDERED TO PADS LABELED 1. 2. AND 3 ON THE BOARD. VERIFY THAT Q1-4 ARE MOUNTED CORRECTLY.
- 2. APPLY POWER PER SECTION 9.3.
- VERIFY A 20 +/- 4 KHZ SIGNAL AT UI-3. THE PULSE SHOULD BE A POSITIVE PULSE WITH AN AMPLITUDE OF ABOUT 3 VOLTS AND A DURATION OF ABOUT 200 NANOSEC. (VOLTAGE AMPLITUDE AND PULSE DURATION NOT VERY CHITICAL.
- VERIFY THAT THE VOLTAGE MEASURED BETWEEN THE COLLECTOR (CASE) OF Q2 TO THE COLLECTOR OF Q4 IS 52 +/- 6 VRMs.
- 5. VERIFY THAT CR39 IS ON.

REV. 1	REV. 4	REV. 7	DL 109 PA	ENGINEER	GENERAL 😭 ELECTRIC	Test Specifications
REV. 2	REV. 5	IISSUED	0/83		_	
REV. 3	REV. 6	MADERY	nderpool		DSO SALEM, VA. U.S.A.	DS 3 8 0 0 N P S L CONT. ON SH. 9BA SH. NO. 9AA

g

LOU-GED-DS3800NPSL REV. A

GE Industrial Systems Renewal Services Louisville, KY

Page 5 of 6

6. VERIFY THAT THE FOLLOWING GROUPS OF PINS CONSTITUTE ISOLATED +/- 15 VOLT POWER SUPPLIES. REFERENCED TO THE ASSOCIATED COM THE PI5 AND NIS MAGNITUDE SHOULD BE 15.0 +/- .3 VOLTS.

GROUP	P15	COM	NIS
0	PA52	PA54	PA50
1	PA44	PA42	PA38
2	PA22	PA20	PA18
3	PA 12	PA.IO	PA8
4	PA64	PA62	PA60
5	PA4	PA6	PA2
6	PA32	PA34	PA30
7	PA74	PA72	PA 70

END OF TEST

REV. 2 REV. 5 ISSUED 3/10/83

REV. 3 REV. 6 MADE SY. Vanuerpool Engineer DSO SALEM, VA. U.S.A. CONT. ON SH. F1 SH. NO.9BA

DSD 9151 (99-76)

LOU-GED-DS3800NPSL
REV. A

GE Industrial Systems
Renewal Services
Louisville, KY

Page 6 of 6

8. Oscilloscope Verification Examples:

Fig. 1

Fig. 2