g		GE Energy	Function	tional Testing Specification					
	Parts & Repair Services Louisville, KY			148D1647Gx					
	Test Procedure for a 148D1647G0004								
DOCUM REV.	MENT REVISION STATUS:	Determined by the last entry in the DESCRIPTION	he "REV" and "DATE" colur	nn SIGNATURE	DEV DATE				
A	Initial release	DESCRIPTION		Scott Cash	12-20-2017				
В									
С									
© COPYRIGHT GENERAL ELECTRIC COMPANY									
Hard copies are uncontrolled and are for reference only. PROPRIETARY INFORMATION – THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION OF GENERAL ELECTRIC COMPANY AND MAY NOT BE USED OR DISCLOSED TO OTHERS, EXCEPT WITH THE WRITTEN PERMISSION OF GENERAL ELECTRIC COMPANY.									
PREPA Scott	RED BY Cash	REVIEWED BY	REVIEWED BY	QUALITY AP L. Groves	PROVAL				
DATE 11-2-2	2017	DATE	DATE	DATE 12/21/2017	•				

	g	
148D1647Gx	GE Energy	Page 2 of 6
	Parts & Repair Services Louisville, KY	

1. SCOPE

1.1 This is a functional testing procedure for a Card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

3.1 The following document(s) shall form part of this specification to the extent specified herein.Unless otherwise indicated, the latest issue shall apply.3.1.1

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.
- 4.2 Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - **4.2.1.1** Wires broken, cracked, or loosely connected
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - 4.2.1.3 Components visually damaged
 - 4.2.1.4 Capacitors bloated or leaking
 - 4.2.1.5 Solder joints damaged or cold
 - 4.2.1.6 Circuit board burned or de-laminated
 - 4.2.1.7 Printed wire runs / Traces burned or damaged

5. EQUIPMENT REQUIRED

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		Appropriate connector breakout box for 125xxx boards
2		Dual Tenma Power supply or similar
1		Switch box for connections to breakout box
2		Fluke meters to measure current.

	g	
148D1647Gx	GE Energy	Page 3 of 6
	Parts & Repair Services Louisville, KY	

6. TESTING PROCESS

6.1 Setup

6.1.1 Setup breakout box, switches and power supply per drawing in section 7.

6.2 Testing Procedure


- **6.2.1** Wire UUT per diagram in section 7.
- 6.2.2 Power up UUT.
- **6.2.3** Use 124 ohm ISV resistor to start.
- **6.2.4** Verify +/- 15 Vdc at TP1 and TP2.
- **6.2.5** Set Voltage source connected to pin 11 at 0 Vdc verify Pin 9 is at 0 Vdc.
- 6.2.6 Set VR2 and VR54 full CCW. Set pin 11 to 1 Vdc and verify 3.9-4.2 Vdc at pin 10.
- **6.2.7** Verify .09 to .1 ma on current meter B connected to pins 12 and 13.
- **6.2.8** Set VR2 full CCW and VR54 full CW. Set 1 Vdc on pin 11 and verify -4.8 to -5.2 Vdc on pin 10.
- **6.2.9** Change ISV resistor to 249 ohms and verify there is very little change to voltage at pin 10 and current on meter A. Set resistor back to 124 ohms.
- 6.2.10 Adjust VR2 for .4 Vdc at TP6.
- **6.2.11** Verify between .2 and .23 ma on current meter B between pins 12 and 13.
- **6.2.12** Change ISV resistor to 249 ohms and verify there is very little change to voltage at pin 10 and current on meter A. Set resistor back to 124 ohms.
- **6.2.13** Use a digital Tektronix scope to make following measurements and adjustments.
- 6.2.14 Adjust VR50 for 6 Vac RMS at TP12.
- **6.2.15** Verify signal at TP12 is between 3 and 3.4 Khz.
- **6.2.16** Verify the oscillator signal at TP12 restarts after the following conditions.
 - **6.2.16.1** Remove both the +/- 22 Vdc at the same time and reapply.
 - **6.2.16.2** Remove the + 22 Vdc and reapply.
 - 6.2.16.3 Remove the -22 Vdc and reapply.
- **6.2.17** The board should be stable at room temp by this time, verify the oscillator signal at TP 12 signal doesn't vary more that .06 Vdc.
- 6.2.18 Note: There is a hump on the shaft of the Transducer approximately 8.5" from the threads, this is the Top Stop (TS), six inches back toward the threads it the Bottom Stop (BS). They are marked on the 8" Transducer, if you run the transducer in and out a few times while watching the scope you will see the stops on the scope. Inserted is BS and extended it TS.

148D1647Gx


GE Energy
Parts & Repair Services
Louisville, KY

Page 4 of 6

6.2.19 With Transducer at TS (extended) verify 2-3 Vac 3 Khz at TP7. See below.



6.2.21 With Transducer at BS (Inserted) verify 12-13 Vac 3 Khz at TP 7. See below.



6.2.23 With Transducer at BS (Inserted) verify 12.5-13 Vp-p at TP52. See below.

6.2.20


148D1647Gx

g

GE Energy Parts & Repair Services Louisville, KY Page 5 of 6



6.2.25 With Transducer at TS (extended) verify 3.0 to 3.2 Vp-p at TP52. See below.



6.2.26

6.2.24

- **6.2.27** Set TP8 to 0 Vdc with transducer.
- 6.2.28 Verify TP13 is also at 0 Vdc. If not it can be set to zero with VR53.
- **6.2.29** Set TP8 at 1 Vdc with the transducer. Set VR4 to full CW. Verify -6.5 to -7.9 Vdc TP13.

	g	
148D1647Gx	GE Energy	Page 6 of 6
	Parts & Repair Services Louisville, KY	

- 6.2.30 Set VR4 to full CCW and verify TP13 is between -1.24 Vdc and -1.18 Vdc.
- 6.2.31 Test complete.

o ***TEST COMPLETE ***

Section 7

