| g | GE Industrial Control Systems | Test and Operat | ing Procedure | | |
|--------|--|-----------------|---------------|--|--|
| | | DATE: 06/14/02 | PAGE 1 OF 14 | | |
| | QUALITY REP: Rober Dunll | | | | |
| TITLE: | PROCEDURE: DC-300 APPLICATION CARD TEST PROCEDURE LOU-GED-531X139APM-C | | | | |

1. INTRODUCTORY DESCRIPTION

- A. This procedure establishes the methods for testing a 531X139APM Application Card.
- B. Environmental ranges: 70 +/- 10 Deg. F. with 20-75% R.H.
- C. Unit warm-up/stabilization period requirement: NONE
- D. Personnel using this procedure are expected to have a high degree of confidence and expertise in related testing and calibration procedures.
- E. Procedures not explained here are considered to be understood as common practice.

2. TEST EQUIPMENT VERIFICATION

- A. Verify the accuracy of the standard(s) used in the repair/calibration process by evidence of recent calibration labeling affixed to the test equipment.
- B. All measurement standards used in this procedure shall be traceable to the NATIONAL INSTITUTE of STANDARDS and TECHNOLOGY (N.I.S.T.) and shall have the accuracy, stability, range and resolution required for the intended use.
- C. Unless otherwise specified, the collective uncertainty of the Measurement Standard(s) shall not exceed twenty five percent of the acceptable tolerance for each characteristic being calibrated.
- D. All deviations shall be documented.

3. EQUIPMENT CLEANING

A. All equipment clean will be performed as instructed in the GEES SOP Sec. 14.0

4. EQUIPMENT INSPECTION

- A. The following criteria should be used as a guideline or basis for the inspection process of this unit:
 - 1. Wires broken or cracked.
 - 2. Terminal strips / connectors broken or cracked.
 - 3. Loose wires.
 - 4. Components visually damaged.
 - 5. Capacitors leaking.
 - 6. Solder joint, cold.
 - 7. Circuit board discolored or burned.
 - 8. Printed wire runs burned or damaged.

| g | GE Industrial Control Systems | Test and Operating Procedure | | | |
|--------|-------------------------------|------------------------------|------------------|-------------------------|--|
| | | DATE: 06/14/02 | | PAGE 2 OF 14 | |
| | QUALITY REP: Rober Dunll | | | | |
| TITLE: | DC-300 APPLICATION CARD TES | ST PROCEDURE | PROCEI LOU-GE | DURE: D-531X139APM-C | |

5. <u>REVISION HISTORY</u>

| Revision | Date | Initials | Reason for Revision |
|----------|----------|----------|--|
| A | 5-13-98 | | Initial Procedure – After Verification |
| В | 5-6-02 | RKD | Incorporated info for 531X132APM |
| C | 06/14/02 | RKD | Added Initial column to section 5 |
| D | | | |
| ${f E}$ | | | |
| ${f F}$ | | | |
| G | | | |
| H | | | |
| I | | | |
| J | | | |
| K | | | |

| g | GE Industrial Control Systems | Test and Operating Procedure | | | |
|--------|-------------------------------|---|--------------|--|--|
| | | DATE: 06/14/02 | PAGE 3 OF 14 | | |
| | | QUALITY REP: | | | |
| | | Rober Dunll | | | |
| TITLE: | | PROCE | DURE: | | |
| | DC-300 APPLICATION CARD TES | 00 APPLICATION CARD TEST PROCEDURE LOU-GED-531X139APM-C | | | |

6. REFERENCE DOCUMENTATION

- Reference: GEK
- Factory Procedure # ______

7. THEORY OF OPERATION

• Reference: GEK

8. TEST EQUIPMENT TO BE USED

DC 300 test fixture Asset H033766 FLUKE 85 OR EQUIVLENT

9. FINAL TEST AND OPERATION PROCESS

• XX = don't care

| SETUP for most 531X139 cards | | | | | | | |
|------------------------------|-----------|-----------|------------|----------|--|--|--|
| JP1 1-2 | JP18 1-2 | *JP30 XX | JP40 1-2 | JP55 2-3 | | | |
| JP2 XX | JP19 1-2 | JP30A 6-7 | JP41 1-2 | JP56 2-3 | | | |
| JP3 XX | *JP20 2-3 | JP30B 2-4 | JP42 1-2 | JP57 1-2 | | | |
| JP4 XX | JP21 1-2 | JP30C 3-8 | JP43 1-2 | JP58 1-2 | | | |
| JP5 3-4 | JP22 1-2 | *JP31 XX | JP44 1-2 | JP59 1-2 | | | |
| JP6 1-2 | JP23 1-2 | JP31A 6-7 | JP45 1-2 | JP60 1-2 | | | |
| JP7 2-3 | JP24 2-3 | JP31B 2-4 | JP46 1-2 | | | | |
| JP8 2-3 | JP25 1-2 | JP31C 3-8 | JP47A 1-2 | | | | |
| JP9 1-2 | JP26 2-4 | | JP47B 1-2 | | | | |
| JP10 1-2 | JP27 2-4 | JP32 1-2 | | P1 XX | | | |
| JP11 1-2 | JP28 1-2 | JP33 1-2 | JP47C open | P2 50% | | | |
| JP12 1-2 | | JP34 1-2 | JP48 2-3 | P3 75% | | | |
| JP13 1-2 | *JP29 XX | JP35 1-2 | JP51 1-2 | P4 100% | | | |
| JP14 1-2 | JP29A 6-7 | JP36 1-2 | JP52 1-2 | P5 100% | | | |
| JP15 1-2 | JP29B 2-5 | JP37 1-2 | JP53 1-2 | P6 50% | | | |
| JP16 1-2 | JP29C 3-8 | JP38 1-2 | JP53 1-2 | P7 100% | | | |
| JP17 1-2 | | JP39 1-2 | JP54 2-3 | P8 0% | | | |
| <i>Par.</i> 014 = 128 | | | | | | | |

| * SETUP for APMACM3 & APMAFM1 cards | | | | | |
|-------------------------------------|----------|----------|----------|--|--|
| JP20 1-2 | JP29 2-5 | JP30 2-4 | JP31 2-4 | | |

| SETUP for 531X132 cards | | | | | | | |
|-------------------------|-----|-----|-----|-----|-----|-----|---------|
| JP1 1-2 | JP2 | 1-2 | JP3 | 1-2 | JP4 | 1-2 | JP5 3-4 |
| JP6 1-2 | JP7 | 1-2 | JP8 | 2-3 | | | |
| Par. $014 = 0$ | | | | | | | |

• SETUP: 20K FROM DTB1-2 TO ETB1-2 AND DTB2-5 TO ETB2-5

GE Industrial Control Systems

TITLE:

Test and Operating Procedure

DATE: 06/14/02 PAGE 5 OF 14

QUALITY REP:

PROCEDURE:

DC-300 APPLICATION CARD TEST PROCEDURE

LOU-GED-531X139APM-C

NOTE: All buttons and switches have the same name as the input and output that are being tested per the prints.

- Pull red **E-STOP** button out (Located next to DC300 on right)
- LEDs on Main Control Card will all come on then scroll form right to left unless a fault has occurred. Reference DC300 manual for troubleshooting information
- **FCMET** meter on Control Panel will read approx. 7 VDC
- Turn all pots on Control Panel CCW
- Push **MODE 6** on Control Panel to the down pos. and XSTOP to the up pos. all other switches to middle.
- Plug HAND HELD PROGRAMMER into 18PL on Main Control Card
- Turn RELAY SELECT to 1
- Connect a ohmmeter to the yellow and black TEST JACKS.
- Verify the following
- Turn MSR pot on Control Panel to MIN

SLD RELAY TEST

| RELAY | MSR | POS | OHMS | MSR | POS | OHMS |
|-------|-----|-----|------|-----|-----|------|
| SLD 0 | MIN | 1 | OPEN | MAX | 1 | 0 |
| | MIN | 2 | 0 | MAX | 2 | OPEN |
| SLD 1 | MIN | 3 | OPEN | MAX | 3 | 0 |
| | MIN | 4 | 0 | MAX | 4 | OPEN |
| SLD 2 | MIN | 5 | OPEN | MAX | 5 | 0 |
| | MIN | 6 | 0 | MAX | 6 | OPEN |
| SLD 3 | MIN | 7 | OPEN | MAX | 7 | 0 |
| | MIN | 8 | 0 | MAX | 8 | OPEN |
| SLD 4 | MIN | 9 | OPEN | MAX | 9 | 0 |
| | MIN | 10 | 0 | MAX | 10 | OPEN |

| g | GE Industrial Control Systems | Test and Operati | ng Procedure | | |
|--------|-------------------------------|---------------------|----------------|--|--|
| | | DATE: 06/14/02 | PAGE 6 OF 14 | | |
| | | QUALITY REP: | | | |
| | | Rober Dunll | | | |
| TITLE: | | PROCE | DURE: | | |
| | DC-300 APPLICATION CARD TES | ST PROCEDURE LOU-GE | D-531X139APM-C | | |

BCD INPUT TEST (16PL)

- Plug white cable for Control Panel into 16PL on Application Card
- Set thumbwheel switch to **0000**
- Push **START** on Control Panel
- Push **MODE 0** to up pos.
- Set thumbwheel switch to **1000**
- Press **PSB** on Control Panel
- VMET meter will read 2 VDC
- Set thumbwheel switch to **2000**
- Press **PSB** on Control Panel
- VMET meter will read 4 VDC
- Set thumbwheel switch to **2750**
- Press **PSB** on Control Panel
- VMET meter will read 5.5 VDC
- The HAND HELD PROGRAMMER will read "A 100\$ 19\$"
- Press STOP on Control Panel
- Push **MODE 0** to down pos.
- END OF BCD TEST

MODE TEST (13PL)

- Push **START** on Control Panel
- Push **MODE 0** to up POS.
- **VMET** meter will read 5.5 VDC
- Push **MODE 1** to up pos.
- The HAND HELD PROGRAMMER will read "A 22\$ 13\$" and the motor will decrease in speed
- Push both **MODE 0 & 1** back to middle pos. (Motor may surge then go to zero)
- Push **MODE 2** up pos.
- VMET meter will read 4 VDC
- Push **MODE 2** to middle pos. (Motor will **DEC & VMET** will go to 0 V)
- Push **MODE 3** up pos.
- **VMET** meter will read 2 VDC
- Push **MODE 3** to middle pos. (Motor will **DEC & VMET** will go to 0 V)

| g | GE Industrial Control Systems | Test and Operating Procedur | | | |
|----------|---|-----------------------------|--------------|--|--|
| | | DATE: 06/14/02 | PAGE 7 OF 14 | | |
| | | QUALITY REP: | | | |
| | | Rober Durll | | | |
| TITLE: | | PROCEI | OURE: | | |
| | DC-300 APPLICATION CARD TEST PROCEDURE LOU-GED-531X139APM-C | | | | |

- Push MODE 5 up until VMET reads -2 VDC then push it back to the middle pos.(This is slow to increace) (VMET will stay at -2 VDC)
- Push MODE 4 up and VMET will decrease to 0 VDC
- Push **MODE 4** back to middle pos.
- Press **STOP** on Control Panel
- Push **MODE 6** to the middle pos.
- LEDs 16-4-1 (FLT 21) on Main Control Card (531X300XXXX) will come on solid.
- Push **MODE 6** to the down pos.
- Press **RESET** on Control Panel
- All LEDs will come on then scroll right to left
- Push **MODE 7** to the up pos.
- LED 16 (FLT 16) on Main Control Card (531X300XXXX) will come on solid.
- Push **MODE 7** to the middle pos.
- Press RESET on Control Panel
- All LEDs will come on then scroll right to left
- END OF MODE_ TEST

| g | GE Industrial Control Systems | Test and Operating Procedur | | | | |
|--------|-------------------------------|-----------------------------|----------------|--|--|--|
| | | DATE: 06/14/02 | PAGE 8 OF 14 | | | |
| | | QUALITY REP: | | | | |
| | | Robert Dunll | | | | |
| TITLE: | | PROCE | DURE: | | | |
| | DC-300 APPLICATION CARD TES | ST PROCEDURE LOU-GE | D-531X139APM-C | | | |

NOTE: The AN1 & AN2 test is not performed on the 132 GXX or the 139 G2 cards.

AN1 & AN2 TEST (13PL)

- The following actions are performed on the Handheld Programmer.
- Press "SET"
- Press "DRV"
- Press "77"
- Press "ENTER"
- The Programmer will display "PARAMETER"
- Press "**RESET**" one time
- The Programmer will display "DIAGNOSTIC"
- Press "TEST" (Blue letters)
- Press "11"
- Press "ENTER"
- The Programmer will display "DG 0000.0000" (Note may occasionally flicker to FFFF.FFFF)
- Push AN1 and AN2 to up
- The Programmer will display "DG 03Fx.03Fx" (x) = Don't care
- Push AN1 and AN2 to down
- The Programmer will display "DG FBEx.FBEx" (x) = Don't care
- Push AN1 and AN2 to the middle
- Press "RESET" 2 times (Located on control panel)
- The Programmer will display "OPERATE" then after a few seconds "M 00\$ 00\$"
- END OF AN1 & AN2 TEST

ANALOG INPUT TEST (13PL INPUT TO U4 MUX)

- The following actions are performed on the Handheld Programmer.
- Press "SET"
- Press "DRV"
- Press "77"
- Press "ENTER"
- The Programmer will display "PARAMETER"
- Press "**RESET**" one time
- The Programmer will display "DIAGNOSTIC"

Test and Operating Procedure DATE: 06/14/02 PAGE 9 OF 14 QUALITY REP: Rober Dunct PROCEDURE: DC-300 APPLICATION CARD TEST PROCEDURE LOU-GED-531X139APM-C

• Press "RAM"

- This is the start of Analog Input test
- Press "413"
- The Programmer will display "413 XXX"
- Press and hold **LTA** on Control Panel
- Press "**ENTER**" on the Programmer
- The Programmer will display "413 63" approx
- Press "**RESET**" one time on Programmer
- The Programmer will display "DIAGNOSTIC"
- Press "RAM"
- Press "459"
- The Programmer will display "459 0"
- Press and hold **SJ1** on Control Panel
- Press "ENTER" on the Programmer
- The Programmer will display "459 1101" approx
- Press "**RESET**" one time on Programmer
- The Programmer will display "DIAGNOSTIC"
- Press "RAM"
- Press "457"
- The Programmer will display "457 0"
- Press and hold **SJ2** on Control Panel
- Press "ENTER" on the Programmer
- The Programmer will display "457 242" approx
- Press "**RESET**" one time on Programmer
- The Programmer will display "*DIAGNOSTIC*"
- Press "RAM"
- Press "469"
- The Programmer will display "469 0"
- Press and hold **PSREF** on Control Panel
- Press "**ENTER**" on the Programmer
- The Programmer will display "469 1016" approx
- Press "**RESET**" one time on Programmer
- The Programmer will display "DIAGNOSTIC"
- Press "RAM"
- Press "380"

Test and Operating Procedure DATE: 06/14/02 PAGE 10 OF 14 OUALITY REP: Robert Dunct PROCEDURE: DC-300 APPLICATION CARD TEST PROCEDURE LOU-GED-531X139APM-C

- The Programmer will display "380 0"
- Press and hold **ASP1** on Control Panel
- Press "**ENTER**" on the Programmer
- The Programmer will display "380 61" approx
- Press "**RESET**" one time on Programmer
- The Programmer will display "DIAGNOSTIC"
- Press "RAM"
- Press "461"
- The Programmer will display "461 0"
- Press and hold **ASP2** on Control Panel
- Press "ENTER" on the Programmer
- The Programmer will display "461 1016" approx
- Press "**RESET**" one time on Programmer
- The Programmer will display "DIAGNOSTIC"
- Press "RAM"
- Press "467"
- The Programmer will display "467 0"
- Press and hold **FRA** on Control Panel
- Press "**ENTER**" on the Programmer
- The Programmer will display "467 449" approx
- Press "**RESET**" one time on Programmer
- The Programmer will display "DIAGNOSTIC"
- Press "RAM"
- Press "414"
- The Programmer will display "414 0"
- Press and hold **CLA** on Control Panel
- Press "**ENTER**" on the Programmer
- The Programmer will display "414 63" approx
- Press "**RESET**" two times on Programmer

Test and Operating Procedure DATE: 06/14/02 PAGE 11 OF 14 OUALITY REP: Robert Dunct TITLE: PROCEDURE:

ASR TEST (13PL)

• Monitor TP **ASR** on Application Card with a voltmeter

DC-300 APPLICATION CARD TEST PROCEDURE

- Turn **ASR** pot on Control Panel to MAX
- Adjust P1 on card for 4 VDC @ TP ASR

NOTE: The MAP INPUT test is not performed on the 132 GXX cards. ETB is the green terminals on application card

LOU-GED-531X139APM-C

MAP INPUT TEST (11PL AND 13PL)

- With a voltmeter verify the table below
- BLACK test lead is COM.
- Turn P7 CW & P8 full CCW

| MAP1 | MAP2 | MAP3 | VOLTS | VOLTS | | | |
|------|----------------------|------|---------------|---------------|--|--|--|
| SW | SW | SW | OUT | OUT | | | |
| POS | POS | POS | ETB2-5 | ETB2-2 | | | |
| UP | MID | MID | + 3.6 V | 0 V | | | |
| UP | DOWN | MID | 0 V | 0 V | | | |
| DOWN | DOWN | MID | -3.98 V | 0 V | | | |
| DOWN | UP | MID | 0 V | 0 V | | | |
| MID | MID | UP | 0 V | -3.5 V | | | |
| MID | MID | DOWN | 0 V | +3.7 V | | | |
| | VOLTAGE TOL. +/1 VDC | | | | | | |

Test and Operating Procedure GE Industrial Control Systems DATE: 06/14/02 **PAGE 12 OF 14 QUALITY REP:** TITLE: **DC-300 APPLICATION CARD TEST PROCEDURE** LOU-GED-531X139APM-C

NOTE: Allow five seconds for the reading to stabilize when making each of the following measurements.

EXTERNAL FAULT TEST

Measure from **COM**. To **4TB** - __ and verify the chart below is true .

| Values for a 139 Card | | | | | |
|-----------------------|------------|------------|--|--|--|
| 4TB | RESET | RESET | | | |
| | PUSHED IN | RELEASED | | | |
| 40 | + 26.5 VDC | + 1.25 VDC | | | |
| 41 | + 26.5 VDC | + 1.25 VDC | | | |
| 42 | + 26.5 VDC | + 1.25 VDC | | | |
| 43 | + 26.5 VDC | + 1.25 VDC | | | |
| 44 | + 26.5 VDC | + 1.25 VDC | | | |
| 45 | + 26.5 VDC | + 1.25 VDC | | | |
| 39 | + 26.5 VDC | + 1.25 VDC | | | |
| | | | | | |

| Values for a 132 Card | | | | |
|-----------------------|-------------|-----------|--|--|
| | RESET RESET | | | |
| | PUSHED IN | RELEASED | | |
| B01 | + 25.7 VDC | + 1.3 VDC | | |
| B02 | + 25.7 VDC | + 1.3 VDC | | |
| B03 | + 25.7 VDC | + 1.3 VDC | | |

END OF EXTERNAL FAULT TEST

| g | GE Industrial Control Systems | Test and Operating Procedure | | |
|--------|-------------------------------|------------------------------|---------------|--|
| | | DATE: 06/14/02 | PAGE 13 OF 14 | |
| | QUALITY REP: | | | |
| | | Rober Dunll | | |
| TITLE: | | PROCEDURE: | | |
| | DC-300 APPLICATION CARD TES | | | |

IF CARD DOES NOT HAVE AN LED SKIP REST OF TEST

ENCODER TEST (11PL)

- Verify **Red** LED is on
- Verify MSR is set to Min on Control Panel
- Press "START" on Control Panel
- Verify that the Freq at **JP47B** is **0 Hz**.(This can be done with DMM by selecting DC and pressing HZ on meter)
- Turn **MSR** to Max
- Verify that the Freq at **JP47B** is **15.5 KHz**.
- Turn **MSR** to **Min**
- Press "STOP" on Control Panel
- Set thumbwheel switch to **0000**
- END OF ENCODER TEST

GE Industrial Control Systems

Test and Operating Procedure

DATE: 06/14/02

PAGE 14 OF 14

QUALITY REP:

Rad

PROCEDURE:

DC-300 APPLICATION CARD TEST PROCEDURE LOU-GED-531X139APM-C

8. SPECIAL INFORMATION

TITLE:





TEST WRITTEN BY: DAVID SMITH **TEST VERIFIED BY:** James Archibald

DATE: 5-13-98 **DATE:** 5-06-02