Test Specifications for POWER SUPPLY

277A3714

FIRST MADE FOR LC3600FP7U

EVISION

Rating:

105VDC @ 5A

@ .25A 50VDC

TITLE

28VDC @ .5A

TEST PROCEDURE

A. Preliminary Inspection:

The PWB shall be inspected prior to application of power to verify that it is assembled according to the assembly drawing.

B. 105VDC Test:

25-R 500W

Connect a 0 to 5 amp load between pins 23 and 3. Set to max. resistance - (minimum amperage). Apply 115VAC + 10%, 60HZ between pins 35 and 47. Set load amps to 5 amps. Verify that the voltage across the load and the voltage at pin 31 + (3-) is 105VDC + 20%. Disconnect the input voltage and the load.

50VDC and 28VDC Test:

Connect pin 9 and 17 to pin 21.

Connect pin 13 to pin 3.

Connect a .25A @ 50VDC load between pins 21 and 3.

Apply 36VAC + 10%, 60HZ between pins 35 and 47.

Verify that the voltage across the load is 50VDC + 20% with <

7V P-P ripple.

Change the voltage between pins 35 and 47 to 20VAC + 10%, 60HZ.

Verify that the voltage across the load is 28VL + 20% with <

7V P-P ripple.

Disconnect the input voltage and the load.

1. BU945UG JVG 780415

4EF1

1338

ITS TO

Vanderpool 8/29/77

DRIVE SYSTEMS SALEM, VA. U.S.A.

LOCATION

277 A 3 7 1 4

FF-803 WF (3-74) PRINTED IN U.S.A.

277A3714

ner an auger El auma

277A3714

Test Specifications for POWER SUPPLY

OUT ON SHEET FL SH NO. 2

FIRST MADE FOR IC3600EPZU

TEST PROCEDURE (Continued)

D. Pin Continuity Test:

Verify 0 ohm between the following pins.

TITLE

FROM PIN	TO PIN
47	49
35	37
21	23
3	5
3	41
3	43

END OF TEST.

18A2

4EEL

(334

TETS TO

R.E.Vanderpool 8/29/77

Ortober 12, 197

96

DRIVE SYSTEMS

SALEM, VA. U.S.A

2 7 7 36

FL SH NO

FF-803 WF (3-76) PRINTED IN U.S.A.

+

+