g		GE Energy		Function	onal Testing	Specification		
	Parts & Repair Services Louisville, KY					LOU-GED-872D490G3		
	Test Procedure for a 872D490G3 Turbine Card							
DOCUI	MENT REVISION STATUS:	Determined by the last er	ntry in the "REV" a	nd "DATE" col	umn			
REV.		DESCRIPTION	,	27112 001	SIGNATURI	E REV. DATE		
Α	Initial release, re-wro	ote procedure P24B-AL	-4837 into this f	ormat so it	C. Wade & Cash			
В								
С								
	YRIGHT GENERAL ELECTE							
Hard copies are uncontrolled and are for reference only. PROPRIETARY INFORMATION – THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION OF GENERAL ELECTRIC COMPANY AND MAY NOT BE USED OR DISCLOSED TO OTHERS, EXCEPT WITH THE WRITTEN PERMISSION OF GENERAL ELECTRIC COMPANY.								
PREPA S. Ca	ARED BY sh	REVIEWED BY	REVIEWE	D BY	_	ry APPROVAL Lie Wade		
DATE 2/18/2	2012	DATE	DATE		DATE 2/18/2			

	g	
LOU-GED- 872D490G3	GE Energy	Page 2 of 6
REV. A	Parts & Repair Services	
	Louisville, KY	

1. SCOPE

1.1 This is a functional testing procedure for an 872D490G3 Turbine Card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
 - **3.1.1** Check board's electronic folder for more information
 - 3.1.2 Reference Schenectady Test P24B-AL-4837

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to site specific SRA's for cleaning guidelines.
- **4.2** Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - **4.2.1.1** Wires broken, cracked, or loosely connected
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - **4.2.1.3** Components visually damaged
 - 4.2.1.4 Capacitors bloated or leaking
 - 4.2.1.5 Solder joints damaged or cold
 - 4.2.1.6 Circuit board burned or de-laminated
 - 4.2.1.7 Printed wire runs / Traces burned or damaged

5. **EQUIPMENT REQUIRED**

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		Fluke 87 DMM (or Equivalent), Two voltage and
		current Meters
3		+/- 15VDC Power Supplies

g

LOU-GED- 872D490G3 REV. A

GE Energy Parts & Repair Services Louisville, KY

Page 3 of 6


6. Testing Process

6.1 Setup

- **6.1.1** Connect board as per figure 2. See attachment in section 8. Data sheet is also attached in section 8.
- **6.1.2** Open SW3, SW4, SW5, & SW6.
- **6.1.3** Plug in board and ground TP-9. Turn Pot 8 fully CW.

6.2 Testing Procedure

- **6.2.1** Power up card.
- **6.2.2** Adjust R31 for +5.10V at TP-5.
- **6.2.3** Set SW4 down (close SW4). The voltage at TP-5 should drop to 0VDC +- 0.05.
- **6.2.4** Set SW4 up (open SW4).
- **6.2.5** The voltage at TP-5 should return to +5.10V.
- **6.2.6** Remove ground from TP-9. Ground TP-8, set SW5 up (open SW5).
- **6.2.7** Turn load limit pot #8 fully CW. The voltage at TP-5 should be +5.10V.
- 6.2.8 Turn Pot 8 fully CCW and adjust R30 for 0V at TP-5
- **6.2.9** Turn Pot 8 fully CW, close SW5.
- **6.2.10** Remove ground from TP-8 and adjust R26 for 3.0V at TP-5.
- **6.2.11** Turn Pot 8 fully CCW, the voltage at TP-5 should be 0V,
- 6.2.12 Adjust Pot8 for 2.5V at TP-5; Set SW3 and SW4 down (close SW3 & SW4).
- **6.2.13** The voltage at TP-5 should be 0V. Adjust Pot8 from it full CW to it full CCW limit. The voltage at TP-5 should not change in value from the allowable dead-band of +- 0.05V.
- 6.2.14 Turn Pot 8 fully CW. Open SW3, SW4, & SW5; output at TP-5 should be +5.10V.
- **6.2.15** Connect TP-4 to BP-3. Hook up a memory type of oscilloscope to read voltage at TP-5
- **6.2.16** Close SW6, the oscilloscope trace should be the same as shown in figure 1



LOU-GED- 872D490G3
REV. A

GE Energy
Parts & Repair Services
Louis ville, KY

Page 4 of 6

- 6.2.17 Open SW6, close SW5, and adjust R26 for 0VDC at TP-5.
- **6.2.18** Open SW5
- **6.2.19** Close SW6 and observe that the oscilloscope trace is the same as in figure 1.
- **6.2.20** Re-adjust R26 for +3.0V at TP-5.
- **6.2.21** End of test
- 6.3 Post Testing Burn-in Required _X_ Yes ___ No
 - Note: All MARK I, II, & III Turbine related cards require a post testing burn-in of 100 hours.
 - **6.3.1** Apply BUS or Operational power to the card for a period of 100 hours.
 - **6.3.2** Re-test card while warm using the above procedure.
- 6.4 ***TEST COMPLETE ***
- 7. Notes
 - 7.1 Fill out data sheet in Section 8

LOU-GED- 872D490G3
REV. A

GE Energy
Parts & Repair Services
Louisville, KY

Page 5 of 6

8. Attachments

8.1 Data Sheet

Job #										
Serial #					Burn-in Start					
Date										
Data Sheet for872D490G0003				Burn-in Stop						
Test Procedu	ureP24B-AL-4	837			Technician					
						Pot Values If				
Test Procedure	Nominal	Lower	Pre-Burn	Post Burn	Unner Limit	applicable CW	Pacc/Fa			

Test Procedure		Lower	Pre-Burn	Post Burn		Pot Values If applicable CW	0 /5 :
Step	Nominal	Limit	in Results	in Results	Upper Limit	CCW	Pass/Fail
4	5.1VDC	-			-		
4a		-	-	-	-		
10	0VDC	-			-		
10a		-	-	-	-		
12	3.0VDC	-			-		
12a		-	-	-	-		

LOU-GED- 872D490G3 REV. A **GE Energy** Parts & Repair Services Louisville, KY

g

Page 6 of 6

8.2 Figure 2

