g	GE Industrial Systems Fun			tional Testing Specification	
	Renewal Services Louisville, KY		LOU-GED-44C359030-D		
		Test Procedure for 44C3	59030G01		
	MENT REVISION STATUS	: Determined by the last entry in the "REV"	and "DATE" colu	mn	
REV.		DESCRIPTION		SIGNATURE	REV. DATE
A	Initial release			Paul Kelley	8/26/2003
В	Updated voltage randrawing.	ges for the saturable reactor test and	updated	Paul Kelley	9/25/2003
С	Clarified instructions	3		Paul Kelley	12/18/2003
PROPR		RIC COMPANY THIS DOCUMENT CONTAINS PROPRIETARY I ED TO OTHERS, EXCEPT WITH THE WRITTEN			

9/9/03

8/26/2003

8/26/2003

	g	
LOU-	GE Industrial Systems	Page 2 of 6
REV. A	Renewal Services	
	Louisville, KY	

### Functional test procedure for a 44C359030G01 board

### 1. SCOPE

**1.1** This is a functional testing procedure for a Card.

## 2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

## 3. APPLICABLE DOCUMENTS

3.1 The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.3.1.1

# 4. **ENGINEERING REQUIREMENTS**

- 4.1 Equipment Cleaning
  - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to the local documented procedures for cleaning guidelines.
- 4.2 Equipment Inspection
  - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
    - 4.2.1.1 Wires broken or cracked
    - 4.2.1.2 Terminal strips / connectors broken or cracked
    - **4.2.1.3** Loose wires
    - 4.2.1.4 Components visually damaged
    - 4.2.1.5 Capacitors leaking
    - 4.2.1.6 Solder joints damaged or cold
    - 4.2.1.7 Circuit board burned or de-laminated
    - 4.2.1.8 Printed wire runs burned or damaged

### 5. EQUIPMENT REQUIRED

**5.1** The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1		Fluke 85 DMM (or Equivalent)
1		Variac (isolated)
2		0 to 110V DC PS
1		120V Bulb Load
1		44C359030G01 TEST KIT

LOU- REV. A	GE Industrial Systems Renewal Services	Page 3 of 6
REV. A	Louisville, KY	

### 6. TESTING PROCESS

### 6.1 Setup

6.1.1 Using the 44C359030G01 Test Kit connect as shown in the diagram below in Fig.1 (positive to TB2A-J for the bias supply) with nothing on monitor 1 and 2, bias supply at 0 V and the variac set to 0. Refer to Fig. 2 for connection 28 and to find components. CR6 and CR7 in figure 1 below are the two diodes immediately to the right of the heat sinks and slightly to the left of the doughnut shaped saturable reactor.



Note: There are terminals TB2 and TB2A. Read carefully.

### **6.2** Testing Procedure

- **6.2.1** Turn variac to get 60 volts AC to UUT. With a meter on DC you should be reading approx 50 volts across the bulb load.
- **6.2.2** Start raising the bias voltage. The light should start going out below 1 volt and be completely out at 1 volt.
- **6.2.3** Turn off and disconnect the bias supply.
- **6.2.4** Connect the monitor 1 supply set to 0 volts (positive to TB2-U and negative to TB2-V). The output to the load should be approx 50 volts DC.
- 6.2.5 Start increasing voltage on the monitor 1 supply. The voltage to the load should start decreasing at approx 8 to 20 volts and the bulb should be completely out at approx 40 to 65 volts on the monitor 1 input.
- **6.2.6** Continue increasing monitor 1 voltage. The voltage to the bulb should start increasing at about 92 to 105 volts and be at the full 50 volts at a monitor input of 105 volts. Leave it at 105 volts.
- **6.2.7** Verify closed relay contacts on the TB2-B to TB2-M terminals.
- **6.2.8** Verify open relay contacts on the TB2-M to TB2-L terminals.
- **6.2.9** Keep the supply on the monitor 1 input and apply 100 volts to monitor 2 input (positive to TB2-S and negative to TB2-P).
- **6.2.10** Verify approx 24 volts across CR13 (24 volt zener).
- **6.2.11** Remove the supply from the monitor 1 input.
- **6.2.12** Verify open relay contacts on the TB2-B to TB2-M terminals.
- **6.2.13** Verify closed relay contacts on the TB2-M to TB2-L terminals.

	g	
LOU-	GE Industrial Systems	Page 4 of 6
REV. A	Renewal Services	
	Louisville, KY	

- **6.2.14** Verify that voltage to the bulb load goes from 0 to 50 volts by adjusting the monitor 2 input from 85 to 110 volts.
- **6.2.15** Disconnect the variac and all power supplies to the UUT.
- 6.2.16 Monitor the DC voltage across C2 while inputting 120V AC from the isolated variac to the following combinations of inputs (monitor 1 on TB2) one at a time T to U, T to V and U to V. C2 should read approx 124 volts with each combination. This tests the 3 phase rectifier bridge for monitor 1.
- 6.2.17 Monitor the DC voltage across C1 while inputting 120V AC from the isolated variac to the following combinations of inputs (monitor 2 on TB2) one at a time R to S, R to P and S to P. C1 should read approx 124 volts with each combination. This tests the 3 phase rectifier bridge for monitor 2.

6.2.18

6.3 \*\*\*TEST COMPLETE \*\*\*

# 7. NOTES

	g		
LOU-		GE Industrial Systems	Page 5 of 6
REV. A		Renewal Services	
		Louisville, KY	




Fig. 2



