g		GE Energ	ЭУ	Functional 1	resting Spe	ecification		
	Parts & Repair Services Louisville, KY			LOU-BENT-3300-39				
Test Procedure for a Bentley Nevada System Monitor Card								
	MENT REVISION STATUS	Determined by the last	entry in the "REV" a	nd "DATE" column				
REV.		DESCRIPTION	1		IGNATURE	REV. DATE		
Α	Initial release			Ste	eve Pharris	1/30/12		
В								
С								
Hard co PROPR MAY N	YRIGHT GENERAL ELECTI pies are uncontrolled and are f IETARY INFORMATION — IOT BE USED OR DISCLOSI ARED BY Pharris	or reference only. ΓΗΙS DOCUMENT CONTA		PERMISSION OF GENE		OMPANY. PROVAL		
<b>DATE</b> 01/30	/12	DATE	DATE		DATE 1/30/2012	m		

LOU-BENT-3300-39 REV. A	GE Energy Parts & Repair Services	Page 2 of 3
	Louisville, KY	

#### 1. SCOPE

**1.1** This is a functional testing procedure for a Bently Nevada Card.

### 2. STANDARDS OF QUALITY

**2.1** Refer to the current revision of the IPC-A-610 standard for workmanship standards.

### 3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
  - **3.1.1** Check Blue Binders next to equipment for BOMs, drawings, etc.
  - **3.1.2** Check board's electronic folder for more information (working to scan data into system on going and not yet completed)

### 4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
  - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to site specific SRA's for cleaning guidelines.
- 4.2 Equipment Inspection
  - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
    - 4.2.1.1 Wires broken, cracked, or loosely connected
    - 4.2.1.2 Terminal strips / connectors broken or cracked
    - 4.2.1.3 Components visually damaged
    - 4.2.1.4 Capacitors bloated or leaking
    - 4.2.1.5 Solder joints damaged or cold
    - 4.2.1.6 Circuit board burned or de-laminated
    - 4.2.1.7 Printed wire runs / Traces burned or damaged

## 5. EQUIPMENT REQUIRED

**5.1** The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1	140700	Bently 3300 Test Station

LOU-BENT-3300-39
REV. A

GE Energy
Parts & Repair Services
Louis ville, KY

Page 3 of 3

### 6. <u>Testing Process</u>

- **6.1.1** Boot Bentley computer. If it asks for a password, just hit "enter".
- **6.1.2** Open "TESTLAN" and select "A", and follow instruction on screen.
- **6.1.3** Go through the following selections.
  - 6.1.3.1 Test Configuration
  - 6.1.3.2 Job Information
  - **6.1.3.3** Equipment Configuration
  - **6.1.3.4** Quit Program when done with the above selections.

### **6.2** \*\*\*TEST COMPLETE \*\*\*

# 7. Notes

7.1 None at this time.

### 8. Attachments

**8.1** None at this time.