g		GE Energ	ЭУ	Functional 1	esting Spe	ecification	
Parts & Repair Services Louisville, KY			LOU-BENT-3300-52				
Test Procedure for a Bentley Nevada System Monitor Card							
	MENT REVISION STATUS	Determined by the last	entry in the "REV" a	nd "DATE" column			
REV.		DESCRIPTION	1		IGNATURE	REV. DATE	
Α	Initial release			Ste	eve Pharris	1/30/12	
В							
С							
Hard co PROPR MAY N	YRIGHT GENERAL ELECTI pies are uncontrolled and are f IETARY INFORMATION — IOT BE USED OR DISCLOSI ARED BY Pharris	or reference only. ΓHIS DOCUMENT CONTA		PERMISSION OF GENEI		OMPANY.	
DATE 01/30	/12	DATE	DATE		DATE 1/30/2012		

	g	
LOU-BENT-3300-52	GE Energy	Page 2 of 3
REV. A	Parts & Repair Services	
	Louisville, KY	

1. SCOPE

1.1 This is a functional testing procedure for a Bently Nevada Card.

2. STANDARDS OF QUALITY

2.1 Refer to the current revision of the IPC-A-610 standard for workmanship standards.

3. APPLICABLE DOCUMENTS

- **3.1** The following document(s) shall form part of this specification to the extent specified herein. Unless otherwise indicated, the latest issue shall apply.
 - **3.1.1** Check Blue Binders next to equipment for BOMs, drawings, etc.
 - **3.1.2** Check board's electronic folder for more information (working to scan data into system on going and not yet completed)

4. ENGINEERING REQUIREMENTS

- 4.1 Equipment Cleaning
 - **4.1.1** Equipment should be clean and free of debris prior to applying power unless performing an initial check. Refer to site specific SRA's for cleaning guidelines.
- 4.2 Equipment Inspection
 - **4.2.1** Equipment should be visually inspected for any defects prior to applying power. This inspection should include the following as a minimum:
 - 4.2.1.1 Wires broken, cracked, or loosely connected
 - 4.2.1.2 Terminal strips / connectors broken or cracked
 - 4.2.1.3 Components visually damaged
 - 4.2.1.4 Capacitors bloated or leaking
 - 4.2.1.5 Solder joints damaged or cold
 - 4.2.1.6 Circuit board burned or de-laminated
 - 4.2.1.7 Printed wire runs / Traces burned or damaged

5. <u>EQUIPMENT REQUIRED</u>

5.1 The following equipment is required to perform the process requirements. Equipment may be substituted provided that all accuracy's and test ratios are equivalent or better.

Qty	Reference #	Description
1	140700	Bently 3300 Test Station

LOU-BENT-3300-52
REV. A

GE Energy
Parts & Repair Services
Louis ville, KY

Page 3 of 3

6. Testing Process

- **6.1.1** Boot Bentley computer. If it asks for a password, just hit "enter".
- **6.1.2** Open "TESTLAN" and select "A", and follow instruction on screen.
- **6.1.3** Go through the following selections.
 - 6.1.3.1 Test Configuration
 - 6.1.3.2 Job Information
 - **6.1.3.3** Equipment Configuration
 - **6.1.3.4** Quit Program when done with the above selections.

6.2 ***TEST COMPLETE ***

7. Notes

7.1 None at this time.

8. Attachments

8.1 None at this time.