

REV. NO. P3K-AL-0451-A01 CONT ON SHEET 2 SH NO. 1	TITLE TEST INSTRUCTIONS FOR MAIN STOP VALVE AMPLIFIER 1L1-F005 (ASSEMBLY DRAWING 125D3618 G1) FIRST MADE FOR EHC MARK II
---	---

REVISIONS

I. SCOPE

This instruction outlines the test specifications for circuit board 1L1-F005 (Ref. Drawing 125D3618 G1-Schematic 125D2008)

II. CIRCUIT DESCRIPTION

The purpose of the main stop valve amplifier circuit is to produce a flow reference signal for the number two valve position unit.

This version of the MSVA circuit is to be used on those turbines that have starting and loading on the control valves and use the number two main stop valve bypass valve for warming.

A speed error signal is summed with a warming rate signal at the input of an IC Op-Amp. The speed signal serves to control an overspeed condition only during rotor-shell warming.

This circuit does not have an emitter follower power amplifier due to the small load requirement.

The output has a "maximum flow reference" limit circuit that determines the maximum positive signal that can be obtained. A plus and minus 15.7 volt zenereed power supply furnishes the IC with necessary voltages.

During rotor-shell warming the speed error signal is connected to the Op-Amp input by opening the connection between pins 26 and 27.

The warming rate signal is connected to the Op-Amp input by opening the connection between pins 24 and 25 during both the Rotor Shell and Chest Warming modes.

When the chest warming mode is selected the speed error signal is shorted to ground by connecting pin 26 to pin 27.

273-2

273-12

273-71

273-138

273-221

273-227

PRINTS TO

MADE BY <i>Stolacer</i> SEP 26 1977 ISSUED SEP 26 1977	APPROVALS	Steam Turbine Schenectady, N.Y.	DIV OR DEPT. LOCATION	P3K-AL-0451-A01 CONT ON SHEET 2 SH NO. 1
---	-----------	------------------------------------	--------------------------	---

870

REV  
NO. 0

TITLE

P3K-AL-0451-A01

CONT ON SHEET 3 SH NO. 2

TEST INSTRUCTIONS FOR MAIN STOP VALVE AMPLIFIER 1L1-F005  
(ASSEMBLY DRAWING 125D3618 G-1)

FIRST MADE FOR EHC MARK II

REVISIONS

III. CIRCUIT SPECIFICATIONS

## A. POWER SUPPLY REQUIREMENTS

1. Power Supply 1:  $\pm 22.000 \pm 0.002$  VDC  
(Pin 37) at 260 MA (approx.)2. Power Supply 2:  $-22.000 \pm 0.002$  VDC  
(Pin 41) at 150 MA (approx.)

## B. OPERATING SIGNAL LEVELS

1. Input 1 (Speed Error Signal):  $\pm 10$  VDC (0 volts, 1 volt/1%  
speed error)2. Input 2 (Warming Rate Signal):  $+0.5$  to  $-10$  VDC  
( $+0.5$  volts closed valve,  $-10$  volts  
maximum rate) (controlled by  
warming rate pot)

## C. OUTPUT LOADS

1. Load 1:  $50K$  Ohms  $\pm 1\%$  (Max Load)  
(Pin 10)

## D. INDIVIDUAL STAGE PERFORMANCE SPECIFICATIONS

1. Power Supply (CR1, 2, 3, and 4, R1 and 2)

a. TP1:  $+15.7 \pm 1.0$  VDCb. TP2:  $-15.7 \pm 1.0$  VDC

2. Main Stop Valve Amplifier (IC1) \*

a. Acceptable offset at TP4  
(zero input):  $\pm 1.0m$  VDC  
(Adjustable through VR50 - adjustment point should be at least  
two turns away from either pot ends)b. Transfer function for Speed Error Signal  
(R7, R8, R9, R14, C2)

$$\frac{TP4}{TP8} = \frac{-G1}{1 + T1 S}$$

Where: Gain (G1) =  $-2.000 \pm .040$  volts/volt  
Noise Suppression Lag Time Constant (T1) =  $1.49 \pm .09$  msec.  
Noise Suppression Breakpoint (F1) =  $107 \pm 6$  HZc. Transfer Function for Warming Rate Signal  
(R21, R22, R23, R14, C4)

PRINTS TO

MADE BY *Stalacer* SEP 26 1977

APPROVALS

Steam Turbine

DIV OR  
DEPT.

P3K-AL-0451-A01

ISSUED

SEP 26 1977

Schenectady, N.Y.

LOCATION

CONT ON SHEET

3

SH NO. 2

REV. NO. 0

TITLE

P3K-AL-0451-A01

TEST INSTRUCTIONS FOR MAIN STOP VALVE AMPLIFIER 1L1-F005  
(ASSEMBLY DRAWING 125D3618 G-1)  
FIRST MADE FOR EHC MARK II

CONT ON SHEET 4

SH NO. 3

REVISIONS

III. CIRCUIT SPECIFICATIONS (continued)

## D. (continued)

## 2. c. (continued)

$$\frac{TP4}{TP7} = \frac{-G1}{1 + T3 S}$$

Where: Gain (G4) = 1.000  $\pm$  .020 volts/voltNoise Suppression Lag Time Constant (T4) = 1.61  $\pm$  .18 msec.Noise Suppression Breakpoint (F3) = 100  $\pm$  11 HZ-

## d. Saturation Limits (TP5)

 $\pm$  13 VDC (minimum)

## 3. Voltage Divider Network for Rotor Warming Potentiometer (5K connected from pin 21 to pin 22).

VR4 POSITIONVR5 POSITIONVOLTAGE AT PIN 21

CCW

CCW

+2.487  $\pm$  1.354 VDC

CW

CCW

+10.691  $\pm$  0.634 VDC

CCW

CW

-3.814  $\pm$  1.082 VDC

CW

CW

+5.218  $\pm$  0.539 VDC

## 4. Voltage Divider for Max. Flow Ref.

\* (50K 1% load connected to pin 10). IC1 driven into positive saturation.

VR2 POSITIONVOLTAGE AT TP4

CCW

\* { 6.450  $\pm$  0.352 VDC  
11.688  $\pm$  0.110 VDC

CW

IV. SET POINTS

## A. Adjustment of VR50

With zero input to IC1 VR50 should be adjusted so that TP4 voltage is  $\pm$  1.0 mV.

## B. Adjustment of VR4, VR5

With warming rate potentiometer (5K) connected between pins 21, 22 and wiper connected to pin 23, VR4, VR5 should be adjusted so that the range of TP7 voltage is -10.000 VDC to +0.500 VDC.

PRINTS TO

MADE BY *Stolacek* SEP 26 1977

APPROVALS

Steam Turbine

DIV OR  
DEPT.

P3K-AL-0451-A01

ISSUED

SEP 26 1977

Schenectady, N.Y.

LOCATION

CONT ON SHEET 4

SH NO. 3

P 3K-AL-0451-A01

REV NO. 0

**TITLE**

CONT ON SHEET 5

SH NO. 4

P 3K-AL-0451-A01

TEST INSTRUCTIONS FOR MAIN STOP VALVE AMPLIFIER 1L1-F005  
(ASSEMBLY DRAWING 125D3618 G-1)

CONT ON SHEET

5

SH NO. 4

FIRST MADE FOR EHC MARK II

### C. Adjustment of VR2

With IC1 in saturation, adjust VR2 for +10.000 VDC at TP4.

## REVISIONS

PRINTS TO

MADE BY

SEP 26 1977  
MAILED SEP 26 1977

## APPROVALS

## Steam Turbine

DIV OR  
- DEPT.

P 3K-AL-0451-A01

Schenectady, N.Y.

**LOCATION**

CONT ON SHEET 5

SH NO. 4

REV.  
NO.

TITLE

P3K-AL-0451-A01

TEST INSTRUCTIONS FOR MAIN STOP VALVE AMPLIFIER 1L1-F005  
(ASSEMBLY DRAWING 125D3618 G-1)  
FIRST MADE FOR EHC MARK II

CONT ON SHEET

SH NO. 5

REVISIONS

PREPARED BY

M.J. Sindoni  
M.J. Sindoni  
EHC DESIGN ENGINEERING

DATE

4/16/75

APPROVED BY

P.C. Callan  
P.C. Callan - MANAGER  
EHC DESIGN ENGINEERING

DATE

9-12-77

TEST PROCEDURE

REVIEWED BY

R. W. Debertolis  
R. Debertolis  
EHC TEST ENGINEER

DATE

9-9-77

PRINTS TO

Spolacer SEP 26 1977

ISSUED

SEP 26 1977

APPROVALS

Steam Turbine

DIV OR  
DEPT.

Schenectady, N.Y.

LOCATION

P3K-AL-0451-A01

CONT ON SHEET

SH NO. 5